

# CEPC linac/DR EDR plan

Jingru Zhang

2024.02.28

On behalf of linac group, Institute of High Energy Physics, CAS


# Content

- 研究内容
  - **Physical design of LINAC**
  - **Double-bunch-per-pulse experiment on HEPS Linac**
  - **C-band test bench**
  - **R&D of 5 cell normal conducting cavity**
- 经费需求
- 人员
- 时间节点
- 低温平行耦合加速结构现状

# Physical design of LINAC in EDR




Meng Cai

- TDR finished: Start to end simulations with errors have been conducted for both electron and positron beams with qualities satisfying design requirements
- In EDR:
  - Optimization of the physics design, especially double-bunch acceleration simulation will be done
  - Availability analysis of the Linac
    - During the CDR phase, there is a preliminary analysis, which will be further analyzed



e- in linac

e+ in linac



# Double-bunch-per-pulse experiment in EDR

- This is the proposed operation modes of CEPC, the pulse repetition rate of the linac is 100Hz. For Z mode, **double bunch per pulse** is needed

	tt(180GeV)	Higs(120GeV)	W(80GeV)	Z(45.5GeV)
Pulse repetition rate(Hz)	100	100	100	100
Bunch number per pulse	1	1	1	2

- double-bunch acceleration
  - The accelerators that achieve double-bunch acceleration are KEKB (high bunch charge) and the Swiss FEL (low bunch charge)
  - SuperKEKB is currently reattempting double-bunch acceleration operation mode. There are **still significant challenges**, especially with high bunch charge

# Double-bunch-per-pulse experiment on HEPS Linac

- The HEPS linac is a 500-MeV S-band normal conducting linear accelerator
- A maximum bunch charge of 8 nC at the exit of the Linac can be routinely achieved
- There is still time for Linac based machine studies before commissioning the HEPS storage ring
- With minor modification, the HEPS Linac could be used for double-bunch-per-pulse experiments







# Double-bunch-per-pulse experiment on HEPS Linac

Modification and upgrade for the Double-bunch-per-pulse experiment



- The e-Gun
  - Only one pulser are currently installed
  - Additional pulser is needed for the double-bunch experiment
- Timing upgrade
  - One additional high precision timing module is needed for the second pulser
- Beam diagnostics
  - Current beam diagnostics can only be used for single-pass long separation pulses
  - A new system need to be developed for pulses with separation about 77 ns



# Sources-TDR finished

- Electron source
  - Traditional thermionic triode gun
  - Mature technology
- Design parameters of the TDR
  - 1.5 nC bunch charge for electron injection
  - 10 nC bunch charge for positron production
- The HEPS and BEPCII design can meet our requirement

Parameter	Unit	Value
Type	-	Thermionic Triode Gun
Cathode	-	Dispenser cathode
Beam current	A	> 10
High voltage of anode	kV	150
Bunch charge 1	nC	3.3 (e <sup>-</sup> injection)
Bunch charge 2	nC	11 (e <sup>+</sup> production)
Repetition rate	Hz	100
Pulse duration	ns	1







# Sources-TDR finished

## ■ Positron source

- Incident electron beam: 4 GeV/10nC/100Hz, Beam power 4kW
- Fixed Target (tungsten, 15mm thickness, Beam size: 0.5 mm)
- Energy deposition: 0.784 GeV/e- @ FLUKA, 784 W → water cooling
- We have made a prototype of the flux concentrator and it's power supply and successfully high power tested

- For the beam energy is high, under normal circumstances, there is no problem. We **will research on** the protection method of positron conversion target under extreme conditions




Design of positron converter device



The FLUX concentrator



The 15kA solid-state modulator



Test of the peak pulse magnetic field




# RF system

## RF distribution of the 30 GeV linac


- S-band, 80 MW klystron, the number of S-band Acc. Structure is 93, big hole s-band structure after the positron source is 16. the number of pulse compressor is 33
  - 1-1(ESBS), 1 accelerating structure, 22MV/m
  - 1-4 (FAS), 21 sets, 84 standard accelerating structures, with pulse compressor, 22MV/m
  - 1-2(PSPAS), 8 sets, 16 big hole accelerating structures, 22MV/m, with pulse compressor
  - 1-2(SAS), 4 sets, 8 accelerating structures, 27MV/m , with pulse compressor
- C-band, 50 MW klystron, C-band structures: 470, with 235 pulse compressors
  - 1.1GeV-30GeV, 1-2(TAS), 235 sets, 470 accelerating structures, ~40MV/m,

Parameter	Unit	S-band	C-band
Frequency	MHz	2860	5720
Length	m	3.1	2.0
Cavity mode		$2\pi/3$	$3\pi/4$
Aperture	mm	19~26	25
Gradient	MV/m	22/27	22
Cells (include coupler cells)		86	55
Number of Acc. Stru.		93	16
Number of Klystron		33	236
Klystron Power	MW	80	50




# Bunching cavities and S-band RF system-TDR finished

- The SHBs & buncher
  - Traditional cavity structure
    - Re-entrant SW for SHBs
    - TW/CI for buncher
- The same as HEPS only the frequency is a little difference
- S-band RF system
  - The prototype for CEPC was tested and the average gradient has reached 33 MV/m at high power test (with SLED)
- The S-band RF system successfully used in HEPS project and the gradient with beam reached 26MV/m



SHBs for HEPS



Buncher for HEPS



HEPS pulse compressor

For bunching cavities and S-band RF system, the technology is mature now for us.

# C-band RF system-TDR finished


- The situation of other labs
  - The maximum average gradient with beam is about 40MV/m

	IHEP	SARI	RIKEN	INFN	PSI
Frequency(MHz)	5712	5712	5712	5712	5712
Mode	$3\pi/4$	$4\pi/5$	$2\pi/3$	$2\pi/3$	$2\pi/3$
Length (m)	1.8	1.8	2	1.4	2
Gradient at high power test bench(MV/m)	-	50 <sup>[1]</sup>	50.1 <sup>[2]</sup>	36 <sup>[3]</sup>	52 <sup>[4]</sup>
Operating gradient with beam (MV/m)	-	41.7(maximum, private talk)	41.4	36	28


1. W. Fang, et al. THE C-BAND TRAVELING-WAVE ACCELERATING STRUCTURE FOR COMPACT XFEL AT SINAP . NIMA 2016
2. T. Sakurai, et al. C-band disk-loaded-type accelerating structure for a high acceleration gradient and high-repetition-rate operation. PHYSICAL REVIEW ACCELERATORS AND BEAMS 20, 042003 (2017)
3. D. Alesini, et al. HIGH POWER TEST RESULTS OF THE SPARC C-BAND ACCELERATING STRUCTURES. IPAC 2014
4. F. Loehel, et al. STATUS OF THE SWISSFEL C-BAND LINEAR ACCELERATOR. FEL 2013

# C-band accelerating structure


- The R&D of C-band accelerating structure at IHEP
  - The beam dynamics of linac based on this design
  - Constant gradient,  $3\pi/4$  mode, 1.8 meters long (Including mechanical length, Effective length is about 1.7m)
    - Round cavity shape
    - Racetrack symmetrical magnetic coupling
- **No high power test and beam testing**



Cavity shape



The deformation caused by temperature variation



# C-band accelerating structure

- The design parameters between different lab
  - Mode :  $3\pi/4$ ,  $2\pi/3$ ,  $4\pi/5$
  - Length
  - Disc thickness
- Though the phase advance is different, the other key parameters is similar

	IHEP	Spring8	SINAP <sup>1</sup>
Frequency: f (MHz)	5712	5712	5712
No. of Cells	87+2	100 regular cells +2 coupler	89+2
Phase advance	$3\pi/4$	$2\pi/3$	$4\pi/5$
Total length(m)	1.8	2	1.784
Length of cell : d (mm)	19.675	17.495	20.994
Disk thickness: t (mm)	4.5	4	5
Average aperture: 2a (mm)	14.04	15.938~12.107	15
Average diameter : 2b (mm)	45.6	43.196~41.869	-
Shunt impedance(average) : Rs (MΩ/m)	66.05	66	62
Quality factor : Q	11358~11186	9300/8900(measured)	10470
Group velocity: Vg/c (%)	2.8% ~ 0.96%	2.3%(average)	1.7%(average)
Filling time : t <sub>f</sub> (ns)	350	290	330
Attenuation factor : τ	0.56	0.59	0.585
E <sub>peak</sub> /E <sub>0</sub>	2.57	2.6	2.6

1. W. Fang, et al. THE C-BAND TRAVELING-WAVE ACCELERATING STRUCTURE FOR COMPACT XFEL AT SINAP



# C-band RF system-what EDR can do


- The model selection of the pulse compressor(PC)
  - SLAC type (Two cavities)
  - BOC type
  - Spherical type



Two cavities PC



SACLA C-band PC



BOC type PC



Spherical PC (Xband of SLAC)



- **No direct high power experience for us**

# C-band RF system-what EDR can do

- This is a high power test bench of Spring-8 before their mass-production
- We hope we can establish the C-band test bench and test the components. With pulsed compressor, waveguides, directional couplers, loads, bend and straight waveguides, etc.
- It is a complete unit and should cooperate with C-band power source





HIGH-POWER RF TEST ON THE MASS-PRODUCED C-BAND RF COMPONENTS FOR XFEL/SPRING-8



# Damping Ring RF cavity-TDR completed

D. Wang, Y.D. Liu, X.H. Cui



- The total cavity voltage requirement is 2.5MV
- 5 cell cavity aperture is decided by impedance, HOM and instability threshold
  - Taking into account the simulation results for impedance threshold and HOM power, the 5-cell cavity with a 90 mm aperture is considered the best choice




# Damping Ring RF cavity-TDR completed

## ■ The design of the 650MHz 5 cell cavity finished

- RF cavity design
- Input coupler and doorknob design
- Vacuum design
- Mechanical design



Electromagnetic field distribution



Tunner


Coupler



Cavity

Mechanical design


	Unit	Value
Beam tube aperture	mm	90
Cell length	mm	5*230.61
$\pi$ -mode frequency	MHz	650.0
Q0		31633
Shunt impedance	M $\Omega$	32.4
R/Q	$\Omega$	1023
Accelerating voltage per cavity	MV	1.25
Accelerating gradient E0	MV/m	1.08
E <sub>max</sub> /E0	-	4.62
Dissipated cavity power (20% margin)	kW	58 (84*)




Ion pump distribution

# Damping Ring RF cavity-what EDR can do

- Further optimize the 5 cell cavity design
- If possible, we hope have fund to process the DR normal conducting 5 cell cavity. And finished the cold test of the cavity
- After the machining of the cavity completed, use PAPS (a test bench of IHEP at Huairou) test bench to do the high-power test of the DR normal conducting 5 cell cavity



Mechanical design





# 经费需求

## ■ 双束加速实验系统升级 (48.6万元)

	数量 (套)	单价	总价	说明
电子枪及定时	2		18.6	
束测	2	15	30	

## ■ C波段微波系统套 (420万元)

	数量	单价	总价	说明
加速结构及二层支架	2	60	120	含材料费及安装测试费等
脉冲压缩器、波导、功分器、负载等		150	150	
真空设备		40	40	离子泵、真空规, 角阀等
其它辅助设备	1	40	40	支架、水路、线缆、安装
性能诊断	1	70	70	暗电流测试, 打火测试等

## ■ DR 常温腔 (525万元)

	数量 (套)	单价	总价	说明
腔体 (包含耦合器和调谐器)	1	350	350	
波导及环形器	1	90	90	
真空和水冷	1	45	45	
控制	1	40	40	

	数量	总价	说明
pulse发生器	1	11	1kV/1.5ns/50Hz
功率合成器	2	1.5	SMA 500MHz to 2.5GHz
高压同轴馈线	3	0.6	3根SMA连接器
控制和联锁通道	1	0.5	
阴栅高压连接器插件阻抗优化		5	
总计		18.6	

# 主要参加人员

	姓名	主要负责	职称
1	李京祎	双束加速实验	研究员
2	孟才	双束加速实验调束实验	研究员
3	隋艳峰	双束加速束测升级	研究员
4	何大勇	双束加速电子枪升级	高级工程师
5	刘劲东	双束加速电子枪升级及C波段测试台控制	工程师
6	张敬如	C波段加速结构的设计及高功率实验总协调	研究员
7	施华	DR 5 cell腔体的设计加工及高功率实验	副研究员
8	贺祥	微波传输部分的设计及高功率实验	高级工程师
9	马新朋	微波信号源	副研究员
10	甘楠	微波低电平	副研究员
11	肖欧正	DR 5 cell腔体耦合器的设计和高功率实验	副研究员
12	李飞	C波段高功率测试功率源调制器	工程师
13	周祖圣	C波段高功率测试平台功率源	研究员
14	李小平	DR 5 cell腔体的高功率实验	研究员
15	王辉	测试台的总体机械设计	高级工程师
16	邓秉林	C波段和DR高功率测试台的真空及支架	高级工程师

# 时间节点

## ■ 双束加速实验系统升级

- 2024.2-2024.12.31, 完成系统改造并进行实验
- 2025.1.1-2025.12.31

## ■ C波段微波系统

- 2024.2-2024.12.31, 完成系统设计, 加速管和脉冲压缩器的设计, 完成无氧铜材料的采购
- 2025.1.1-2025.12.31, 完成加速管和脉冲压缩器的加工调试, 搭建高功率测试台, 完成高功率测试 (功率源可用的情况下)





## ■ DR 常温腔

- 2024.2-2024.12.31, 细化设计并完成招标, 对厂家的工艺评审, 并完成腔体的加工; 细化耦合器、调谐器的设计并完成加工
- 2025.1.1-2025.12.31, 完成腔体的组装、冷测和调试, 完成高功率测试台搭建并进行高功率实验, 完成测试报告和相关文章

# 低温平行耦合加速结构的现状

- I号在低温试验时遇到各腔频率变化不一致的问题
- II号结构的测试结果


– 调试完成后实验室冷测结果,  $\pm 11\text{kHz}$



整体氦罩10分钟  
检漏, 漏率小于  
 $4E^{-11}\text{Torr}\cdot\text{l/S}$







真空检漏



# 低温平行耦合加速结构的现状

## ■ 低温实验结果

- 在真空状态，温度在77k时，频率稳定在5711.902MHz，驻波比1.07，此时测得的 $Q_0$ 为32116，恢复常温后的 $Q_0$ 为12355
- 恢复常温后测试了极限真空
  - 整个系统抽极限真空48小时，在一台70L离子泵工作的情况下，泵口真空度=2.7E-8 Mbar，离子泵电流 $I_p=35\mu A$ 。
  - 如果用2台100L离子泵抽，真空度低于1.35E-8 Mbar，使加速结构中心真空度维持在 5E-8 Mbar。达到高功率情况下的真空指标




恢复常温后的复测



## 低温恒温器现状

- The test cryostat has been completed and transported to IHEP
- Assembly of the cavity and cryostat has been completed within 15 days





# 低温恒温器现状

序号	工作内容	2.25	2.26	2.27	2.28	2.29	3.1	3.2	3.3	3.4	3.5	3.6	3.7	3.8	3.9	3.10	3.11	3.12
1	出厂运输	■																
2	恒温器零部件检查		■															
3	低温管道真空复测		■															
4	组装腔体滑动工装		■	■														
5	调节铜腔机械位移			■														
6	安装法拉第筒, 适配信号线				■													
7	波导组件安装适配				■													
8	建立腔体真空				■	■												
9	组装液位计, 压力传感器工装					■												
10	安装温度传感器					■												
11	封恒温器内氮池						■	■										
12	氮池负压检漏							■										
13	安装恒温器feedthrough								■									
14	内筒支撑等组装								■	■								
15	绝热材料包扎									■	■							
16	建立恒温器隔热真空									■	■							
17	低温阀门调试										■							
18	模组运输, 真空监测											■	■					
19	控制系统接入														■	■	■	■

# C波段测试平台进展

李晓

- 2023.10开始高功率联调
- 2023.11开始电子枪高功率老练
  - 更换环形器
  - 更换波导窗
- 预计2024.03入腔功率达到15MW



**Thank you for your attention!**