







# Progress of Pixelated readout TPC for CEPC TDR


Huirong Qi, Zhi Deng

Yue Chang, Xin She, Guang Zhao, Lingwu Wu, Gang Li, Liwen Yu, Jian Zhang, Quan Ji Weekly meeting of CEPC Track Group, April 26, 2024

# Easy-to-install modular design of TPC for TDR

- High granularity readout TPC can operate at Higgs run in 3.0T and Tera-Z run in 2.0T
- Easy-to-install modular design: optimized modules in the endcap
  - Coverage of the sensitivity readout area increased to 96%
  - Full-scale modelling and FEA analysis on-going

**Report by Junsong Zhang** 



Optimization of Geometry of TPC detector and the Endplate

### **Cost estimation**


- Cost estimation: ~110
  Million RMB
  (Detector 50 Million + Electronic/DAQ 60 Million)
- Full-size aluminum machining →
  Modular Machining

#### **TPC COST ESTIMATION (Unit: \*10K CNY)**


			Detector concept/ Detector items	Unit	Unit cost (CNY)	Quantity	total cost (CNY
Number			CEPC				
3.2			Time Projection Chamber				11000.00
	3.2.1		Chamber				1300.00
		3.2.1.1	Fieldcage (inner and outer)		400.00	1	400.00
		3.2.1.2	Barrel (inner and outer)		600.00	1	600.00
		3.2.1.3	Cathode and HV crate		200.00	1	200.00
		3.2.1.5	Support board		100.00	1	100.00
	3.2.2		Endplate 2000.00				
		3.2.2.1	Aluminum endcap		400.00	2	
		3.2.2.2	MPGD detector module		400.00	2	800.00
		3.2.2.3	Readout bef. Assembly		100.00	2	200.00
		3.2.2.4	pre/Assemnled board		100.00	2	200.00
	3.2.3		Electronics				6000.00
		3.2.3.1	FEE ASIC readout		0.010	200000	2000.00
		3.2.3.2	Cables		0.03	30000	
		3.2.3.3	Optical link, connectors		1.00	300	
		3.2.3.4	DAQ system		0.30	4000	
		3.2.3.5	Crate and controller		20.00	30	
		3.2.3.6	TPC cooling system		1000.00	1	1000.00
	3.2.4		Alignment and calibration				500.00
		3.2.4.1	Calibration system		500.00	1	500.00
	3.2.5		HV and Gas system 1200.00				
		3.2.5.1	HV and low power		400.00	1	400.00
		3.2.5.2	Gas system		300.00	1	300.00
		3.2.5.3	Slow control system		200.00	1	200.00
		3.2.5.4	Online monitoring system		200.00	1	200.0
		3.2.5.5	Testing bef. Assembly		100.00	1	100.0

# **Beam test at DESY in September**

- Beam test planning and timeline have been discussed and finalized at IHEP.
  - Single Micromegas TPC module + one back-up module
  - Experimental measurements on Large Prototype TPC general beam test platform at DESY








Huirong Oi

## Beam test at DESY in September

- Collaboration meetings of the beam test setup at Tsinghua.
  - Discussions with DESY are already underway as well.



Huirong Oi

# Many thanks!