



# *Progress Towards Completion of the MICE Demonstration of Muon Ionization Cooling*

Daniel M. Kaplan




NuFact 2013  
IHEP Beijing  
21 August 2013

# Outline

- Brief MICE overview
- Magnets & other equipment
- Software & results
- Conclusions

- International **M**uon **I**onization **C**ooling **E**xperiment at UK's Rutherford Appleton Laboratory (RAL)
- Has flexibility to test several absorber materials and optics schemes, incl. first 6D cooling demo



- **Nutshell**: under construction, program complete  $\sim 2020$

# Principle of MICE

## MICE the Muon Ionization Cooling Experiment

Measure input particle  
 $x, x', y, y', t, t' = E/Pz$

→ input emittance  $\epsilon^{\text{in}}$




**COOLING CHANNEL**



Measure output particle  
 $x, x', y, y', t, t' = E/Pz$

→ output emittance  $\epsilon^{\text{out}}$

- Plus PID to achieve 99.9% muon purity




Particle by particle measurement, then accumulate few  $10^5$  muons

$$\rightarrow \Delta[(\epsilon^{\text{in}} - \epsilon^{\text{out}})/\epsilon^{\text{in}}] = 10^{-3}$$




# MICE Collaboration



## MICE Module Key:

- **S**pectrometer **S**olenoid (**SS**)
- **A**bsorber–**F**ocus **C**oil (**AFC**)
- **RF**–**C**oupling **C**oil (**RFCC**)


# Steps of MICE



Provisional MICE SCHEDULE  
update: June 2013




Run date



STEP I

EMR run Oct 2013

- Needed for Step IV: EMR, 2 spectrometers & 1 AFC module



STEP IV


(possibly  
w/o field:  
Q2 2014)

Q1 2015  
to Q1 2016

Under construction:

- Needed for Step VI: above + 2 AFC + 2 RFCC modules

STEP VI







Target date Q3 2019  
Step V run possible 2018



# Electron–Muon Ranger

[Geneva, FNAL, Trieste/Como]

- Final MICE PID detector, under construction at U Geneva
  - totally active scintillator calorimeter in which muons range out
  - prototype already tested at MICE
  - to be installed in Sept., commissioned with beam in Oct.








# SciFi Spectrometers

[US / UK / Japan]


- Trackers complete & tested with cosmic rays
  - installation awaiting Spectrometer Solenoid (SS) delivery




5 stations of  
350  $\mu\text{m}$  SciFi



← Typical  
cosmic  
track





← Light yield  $\approx 10$  p.e.



Cosmic test setup



- Need variable-thickness high-density material in 1st SS to generate required input emittances





- 4 irises with W or brass petals
- W petals have brass backing plate
- ready for installation

# Superconducting Magnets: SS

[LBNL, FNAL]

- Spectrometer Solenoids
  - two 4 T magnets with 0.1% field quality, each with 5 NbTi coils
  - specified by LBNL, built by Wang NMR (CA)
  - initial cryogenic and superconducting-lead problems required significant repair and retrofit effort
  - 1<sup>st</sup> SS now trained & mapped (CERN), shipping soon







# Superconducting Magnets: SS

[LBNL, FNAL]

## ● Spectrometer Solenoids

- two 4 T magnets with 0.1% field quality, each with 5 NbTi coils
- specified by LBNL, built by Wang NMR (CA)
- initial cryogenic and superconducting-lead problems required significant repair and retrofit effort
- 1<sup>st</sup> SS now trained & mapped (CERN), shipping soon
- 2<sup>nd</sup> SS reassembled but requires further repair before training





# Superconducting Magnets: FC

[U Oxford, RAL]

## ● Focus Coils

- three 3 T solenoid pairs operable in both gradient (“flip”) and solenoid modes to provide low beta at absorbers
- specified by U Oxford & RAL, build by Tesla Engineering (UK)
- 1<sup>st</sup> two delivered
  - one needed for Step IV
- 1<sup>st</sup> successfully trained in solenoid mode, flip-mode training going slowly
- 2<sup>nd</sup> FC nearly ready for training







# LH2 Absorbers

[KEK]




- 35 cm long x 30 cm diameter
- 3 required (one for step IV)
  - 2 built so far
- Thin, tapered Al-alloy windows
  - designed by IIT & U Oxford
  - fabricated by U Miss
- Can also use LHe



# LH2 System

[RAL]

- Liquid-hydrogen system successfully tested
  - uses hydride-bed H<sub>2</sub> storage





# LiH Absorbers

[FNAL]



- Fabrication at Y12 (Oak Ridge)

- both disks and wedges (6D test) ordered

- disks done, awaiting approvals for delivery to RAL (CRADA with STFC)

- Other solid absorbers also under consideration:


- C, Al, polyethylene,...



# RFCC Modules

[LBNL, HIT, U Miss]

- One (2) needed for MICE Step V (VI)
- Modules designed, RF cavities built
  - 1<sup>st</sup> cavity at FNAL for tests
  - much work in progress on RF couplers, tuners & assembly procedure
- Coupling Coil fab in China (HIT, Qi Huan, SINAP) led by LBNL
  - 1st CC cold mass delivered, test in progress at FNAL STF
    - working on cryogenics issues









# RFCC Modules

[LBNL, HIT, U Miss]

- More on cavities...



- novel Be cavity windows double the accelerating gradient for a given power level




- shown to work by MuCool



# RF Power

[DL, LBNL, U Miss, U Strathclyde]

- 4 recycled 2 MW triode supplies
  - 2 from LBNL, 2 from CERN
  - refurbishment in progress at DL
  - 1st has been successfully tested at full power
- Installation plan devised
- LLRF design in progress
- “TIARA” test this year



- 4 recycled 2 MW triode supplies
  - 2 from LBNL, 2 from CERN
  - refurbishment in progress at DL
  - 1st has been successfully tested



## ! NEWS FLASH !

Begin forwarded message:

**From:** Andrew Moss <andrew.moss@STFC.AC.UK>

**Subject:** Re: Fwd: 1.5 Megawatt

**Date:** July 5, 2013 5:03:24 PM CDT

**To:** MICE-RF-POWER@JISCMail.AC.UK

**Reply-To:** MICE RF power distribution system <MICE-RF-POWER@JISCMail.AC.UK>

2MW from mice amplifier

Andy


Sent from my Windows Phone



# RF Power


[DL, LBNL, U Miss, U Strathclyde]

- Conceptual layout:






- Some details:



# B-Field Mitigation

- 2 concepts:
  - partial return yoke (PRY)
    - suppress the fringe field at its source
  - “local” shielding
    - shield (or move) each sensitive component
- PRY currently seems favored
  - local solution may be riskier: hard to identify all sensitive devices & assess their degree of sensitivity
  - SS delay leaves more time for PRY implementation
  - decision to be taken this fall






# B-Field Mitigation

## Concept

**BROOKHAVEN**  
NATIONAL LABORATORY

- Partial Return Yoke (a.k.a. “shield”, PRY?)
- Concept presented at MICE CM 2012
- Shielding plates
  - wall thickness >10 cm
  - weight: 35t
- Performance
  - Reduces stray field outside of shield to 5-10 Gauss



H Witte. Step IV & VI: Local Flux Return.  
MICE CM 34, October 2012.

(Note: not to scale)


July 25, 13

3

- Engineering continues; review & decide in Sept.


- G4MICE developed initially by Y.Torun (IIT)
  - used for Step I analysis

## G4MICE






- G4MICE developed initially by Y.Torun (IIT)
  - used for Step I analysis
- Succeeded by MAUS (MICE Analysis User Software) framework
  - simplifies maintenance & use
  - strong emphasis on good documentation & thorough testing
  - making good progress, but much remains to be done




- G4MICE developed initially by Y.Torun (IIT)
  - used for Step I analysis
- Succeeded by MAUS (MICE Analysis User Software) framework
  - simplifies maintenance & use
  - strong emphasis on good documentation & thorough testing
  - making good progress, but much remains to be done






# Step IV Plans

- MICE Step IV “deliverables”:
  - complete particle detector system
  - establish safe and routine  $\text{LH}_2$  absorber operation
  - engineering test of beamline made of several magnetically coupled components
  - understand propagation of (imperfect) beam through the “magnetic bottle”
  - calibration of emittance measurement to  $10^{-3}$
  - measurement of 6D emittance change (normalized-emittance cooling)
  - first test of longitudinal cooling (with wedge absorbers)
  - precision validation of simulation codes and physics models
  - precision measurements of correlated multiple scattering and energy-loss straggling



# Step VI Plans

- MICE Step VI “deliverables”:
  - operation of channel with all magnetic couplings in place
  - routine and safe operation of RF in  $B$  field near  $\text{LH}_2$
  - full cooling cell allowing all optics configurations: flip, non-flip, etc...
  - exact replenishment of energy possible
  - significant and measurable longitudinal heating
  - precise measurement of equilibrium emittance of various optical and absorber configurations
  - detailed and precise verification of simulation codes
  - benchmark for many future cooling-channel options
- (Step V, with 1/2 lattice cell, possible as intermediate step, but not the current baseline)





# Conclusions

- MICE is a major undertaking:
  - thorough demonstration that ionization cooling works as expected and is well understood
  - calibration and validation of Monte Carlo models used to design and characterize ionization cooling channels
- A major step on the way to Neutrino Factories and Muon Colliders
- Given adequate support we will accomplish this by 2020