

WCDA二号水池20吋PMT和时间刻度系统

高博

gaobo@ihep.ac.cn

Outline

- The MCP-PMT work

- MCP-PMT work @ Nanjing
- Transportation
- Retest @ Daocheng
- Installation @ Haizishan
- The “Dry-running”


- The calibration work

- System updates from pool1
- Installation & check
- Calibration work flow

MCP-PMT work




MCP-PMT time table





MCP-PMT work @ Nanjing

- **WCDA requirements**
 - 2270 water-proofed PMTs required, ≥ 240 PMTs / month
 - **900** for 2019, **1370** for 2020
- **Changes**
 - the high-voltage divider circuit design changed, single cable is changed to double cables
- **Other work**
 - PMT test with FEEs should be passed
 - the quality check (PMT / HV circuit / potting)
 - packaging & transportation
- **Man power**
 - one and a half men (You Xiaohao, Gao Bo) from IHEP, with 4 native employees
- **Difficulties**
 - all work must be done in less than **40 m²** space




The potting work



HV circuit check & soldering




Potting



Shirinking tube



Pressure test (sampling test)




Ready for retest @ NNVT

if (retest passed)
go packaging;
else
kept for re-check;



Transportation

- Day from 2019/05/26 to 2019/10/20, **1203** PMTs have been sent to Haizishan, Daocheng.
- **1930** PMTs will be accomplished by the end of 2019.







Retest @ Daocheng

- The storage (500 PMTs in the hall)
- Freezing test (sampling @ -5)
- Water pressure test (all)
- Parameters test with HV









Test flow

- HV value @ Gain = 5×10^6
- Q-T curve



Some results


HV differences



Installation @ Haizishan


- Test speed @ Daocheng is 30 PMTs/day, 30 PMTs send to Haizishan for installation everyday;
- 2 PMTs share 1 HV channel, the difference is controlled within 5V, all PMTs paired work is done in pool2.

PMTID	CableID	HV1	Hv2	testch	ClusterID	Cell id
pc19045187	290	1811	1814	7	C24G1	6
pc19045009	0552	1748	1750	6		8
pc19012525	0101	1723	1750	8		7
pc19045032	0531	1724	1764	2		5
pc19041031	555	1755	1767	11		4
pc19045120	634	1750	1770	8		2
pc19033026	611	1757	1770	15		1
pc19041034	669	1746	1775	1		0
pc19045037	633	1775	1775	9		3
pc19033052	390	1751	1775	12		6
pc19045023	609	1763	1776	6	7	
pc19012539	0348	1756	1780	3	C24G2	5
pc19045049	686	1762	1782	4		8
pc19041033	479	1723	1793	2		3
pc19045028	621	1781	1795	7		4
pc19045179	333	1862	1870	5		1
pc19041021	0675	1859	1870	4		0
pc18103023c	13	1788	1815	10		2




The “Dry-running”


Single counting rate




Shower event without water





A shower event detected by pool1 & pool2




Calibration work



System layout



- **Updates**
- **Cable**
 - Use multi-wired cable, include electric power / 485 signal / trigger signal, from mother board to slave, easy to do installation & maintenance
- LED driver
 - LED driven voltage can be adjusted in 0.1V resolution
- **Slave board**
 - Sealed in an ABS water-proof box, independent of FEE box





Installation & fiber check





- 2 fibers (in/cr) are installed on 1 PMT, 1800 fibers in total;
- After all fibers installed as "in-fiber" mode, than cross fibers between neighbour clusters;
- Check fiber work status & fiber installation;
- Pull up the slave board & LED tube with FEE box.

in-fiber check





cr-fiber check




Time calibration work flow

Run DAQ in "single-counting" mode, get SPE & H/L ratio value for each PMT.




Restart DAQ run in "event" mode, change LED trigger voltage during the test, to get the "Q-T" curve for each PMT.






Restart DAQ run in "stable tcal" mode, at different light intensity (eg. 50 / 200 / 400 PE), now the data for time calibration.

Data analysis : get PMT time offsets, do shower reconstruction, moon shadow, Crab ... check the result



Data analysis

- data selection
 - select LED data
 - get Q/T value
 - get rid of the fiber time offsets on each PMT
- Q-T correction
 - should for every PMT
 - to normalize to a selected PMT charge
- cross algorithm
 - with 8 cross fibers' data between neighbour clusters
 - different path




Conclusion

- **MCP-PMT work**
 - The gain uniformity needs to be adjusted, after that the detail work of time calibration will be carried out ;
 - The water level now is 120 cm, the PMT work status, single rate & shower event will be monitored during water injection.
- **Calibration work**
 - pool2 tcal system has updates from tcal system in pool1, will give more detail calibration result;
 - the “Q-T” curve for each PMT will be used in pool1 & pool2, try to understand time calibration difference under different light intensity and between P-shower & γ -shower.

Thank you !

- cross calibration
 - 2 fibers on 1 PMT
 - 8 fibers between clusters (4 pairs)
 - calculation : $A-C = (A-B)+(B-C)$ (B as jumper)
- neighbour cluster c_i/c_0 , c_0 as reference cluster
- CELL c_i_chi TO $c_0_ch_0$, there are 8 time offsets value
- use cross fiber $c_i_ch_x$, 得到
 - $T_{c_i_chi} - T_{c_0_ch_0}$
 $= (TIN_{c_i_chi} - TIN_{c_i_ch_x}) - (TCR_{c_i_ch_x} - TCR_{c_0_ch_0})$



- the data

- LED signal selection
 - LED triggered seperatly
 - event mode (nhit > 900)
 - LED charge & time
- Q-T recorrection
 - $T(q) = 20 \cdot \text{pow}(q, -1.2) + 10 \cdot \text{pow}(q, -0.8)$
 - normalized to 30 PE

