

## Shin MICHIZONO

### International Development Team (IDT) WG2/ KEK

- ILC250 accelerator overview
- ILC area systems
  - Sources
  - Nano-beam
  - SRF
- International Development Team (IDT)
- Civil engineering
- Summary

### ILC250 accelerator facility

		Item	Parameters
e- Main Linac	Same -	C.M. Energy	250 GeV
		Length	20km
e+ Source		Luminosity	1.35 x10 <sup>34</sup> cm <sup>-2</sup> s <sup>-1</sup>
Beam delivery system (BDS)		Repetition	5 Hz
	Physics Detectors	Beam Pulse Period	0.73 ms
	- Source	Beam Current	5.8 mA (in pulse)
	e+ Main Liinac	Beam size (y) at FF	7.7 nm@250GeV
Damping Ring	<sup>cal</sup> 20.5 km	SRF Cavity G. Q <sub>0</sub>	<b>31.5</b> MV/m ( <b>35</b> MV/m) Q <sub>0</sub> = 1x10 <sup>10</sup>
Key Technologies	s		
damping ring few GeV few GeV few GeV few CeV few CeV	blogy final focus	8,000 SRF cavities wit	ll be used.

2

### Main advantages

- A linear accelerator is more advantageous for accelerating electron and/or positron beams to higher energies.
- The spin of the electron and/or positron beam can be maintained during the acceleration and collision. This can help significantly improve measurement precision.
- The small surface resistance of the SRF accelerating structure (cavity) made of Nb enables the efficient power transfer from the AC power source to the beam.
- Further energy efficiency improvements are considered as part of the of Green ILC concept, which aims to establish a sustainable laboratory.



Circulating beam loses energy by synchrotron radiation. Linear collider can extend its collision energy by longer tunnel/ higher gradient.



### ILC machine parameters



Π

	ILC	electron/positron	ILC250		
Beam Energy		GeV	125 (e-) and 125 (e+)		2/s]
	Peak Luminosity (10^34)	cm-2 s-1	1.35		t /cm^2
	Int. Luminosity	ab-1/yr	0.24* * 5,000-hour operation at peak luminos	ity	[x10^3
	Beam dE/E at IP		0.188% (e-), 0.150% (e+)		nosity
	Transv. Beam sizes at IP x/y	nm	515/7.66		k Lumi
	Rms bunch length /	cm	0.03 (σ <sub>z</sub> )		Pea
	beta*	mm	bx*=13mm, by*=0.41mm		
	Crossing angle	mrad	14		
	Rep./Rev. frequency	Hz	5		0.7
	Bunch spacing	ns	554		
	# of bunches		1,312		
	Length/Circumference	km	20.5		
	Facility site power	MW	111		_
	Cost (value) range	\$B US	~5 (tunnel and accelerator)		
	Timescale till operations	years	(~1) + 4(prep.) + 9(construction)		





### Potential for upgrades



The ILC can be upgraded to higher energy and luminosity.

			Z-Pole [4]			Higgs [2,5]		500GeV [1*]		TeV [1*]	
			Baseline	Lum. Up	Baseline	Lum. Up	L Up.10Hz	Baseline	Lum. Up	case B	
Center-of-Mass Energy	E <sub>CM</sub>	GeV	91.2	91.2	250	250	250	500	500	1000	Energy
Beam Energy	E <sub>beam</sub>	GeV	45.6	45.6	125	125	125	250	250	500	
Collision rate	f	Hz	3.7	3.7	5	5	10	5	5	4	
Pluse interval in electron main linac		ms	135	135	200	200	100	200	200	200	
Number of bunches	n <sub>b</sub>		1312	2625	1312	2625	2625	1312	2625	2450	
Bunch population	Ν	<b>10</b> <sup>10</sup>	2	2	2	2	2	2	2	1.737	
Bunch separation	$\Delta t_{ m b}$	ns	554	554	554	366	366	554	366	366	
Beam current		mA	5.79	5.79	5.79	8.75	8.75	5.79	8.75	7.60	
Average beam power at IP (2 beams)	$\mathbf{P}_{B}$	MW	1.42	2.84	5.26	10.5	21.0	10.5	21.0	27.3	
RMS bunch length at ML & IP	σz	mm	0.41	0.41	0.30	0.30	0.30	0.30	0.30	0.225	
Emittance at IP (x)	γe <sup>*</sup> ∗	μm	6.2	6.2	5.0	5.0	5.0	10.0	10.0	10.0	
Emittance at IP (y)	γe <sup>*</sup> y	nm	48.5	48.5	35.0	35.0	35.0	35.0	35.0	30.0	
Beam size at IP (x)	$\sigma^*_{\times}$	μm	1.118	1.118	0.515	0.515	0.515	0.474	0.474	0.335	
Beam size at IP (y)	$\sigma^*_{\scriptscriptstyle Y}$	nm	14.56	14.56	7.66	7.66	7.66	5.86	5.86	2.66	
_uminosity	L	10 <sup>34</sup> /cm <sup>2</sup> /s	0.205	0.410	1.35	2.70	5.40	1.79	3.60	5.11	Lumi.
Luminosity enhancement factor	HD		2.16	2.16	2.55	2.55	2.55	2.38	2.39	1.93	
Luminosity at top 1%	$L_{0.01}/L$	%	99.0	99.0	74	74	74	58	58	45	
Number of beamstrahlung photons	n <sub>g</sub>		0.841	0.841	1.91	1.91	1.91	1.82	1.82	2.05	
Beamstrahlung energy loss	$\delta_{BS}$	%	0.157	0.157	2.62	2.62	2.62	4.5	4.5	10.5	
AC power [6]	Psite	MW			111	138	198	173	215	300	
Site length	Lsite	km	20.5	20.5	20.5	20.5	20.5	31	31	40	

5



### Shin MICHIZONO International Development Team (IDT) WG2/ KEK

- ILC250 accelerator overview
- ILC area systems
  - Sources
  - Nano-beam
  - SRF
- International Development Team (IDT)
- Civil engineering
- Summary

### Area systems of the ILC





### Beam sources -electron/positron-









### Electron driven positron source

Extra 3GeV linac is used for the positron generation. High energy electrons are not necessary. (Electron independent commissioning is possible.



125 GeV e-, 230 m long undulator @ILC

 $\wedge \wedge$ 

CEPC workshop ILC acc.

### Nano-beam R&D at ATF2

ROYAL HOLLOWAY

**Goal 1:** Establish the ILC final focus method with same optics and comparable beamline tolerances

Institute of High Energy Physics

Chinese Academy of Sciences

東京大学 SLAC NATIONAL ACCELERATOR LABORATORY

**‡** Fermilab

ATF2 Goal : **37** nm  $\rightarrow$  ILC **7.7** nm (ILC250); achieved **41** nm (2016)

#### Goal 2: Develop the position stabilization for the ILC collision

FB latency 133 nsec achieved (target: < 366 nsec)</p>

UNIVERSITY OF

**DXFORD** 

D

Laboratoire d'Annecy-le-Vieux

de Physique des Particules

DE L'ACCÉLÉRATEUR L I N É A I R E



### **FONT\*** Bunch train feedback at final focus





## Shin MICHIZONO

### International Development Team (IDT) WG2/ KEK

- ILC250 accelerator overview
- ILC area systems
  - Sources
  - Nano-beam
  - SRF
- International Development Team (IDT)
- Civil engineering
- Summary

### Matured SRF technologies





CEPC workshop ILC acc.

### Worldwide large scale SRF accelerators





### ILC Cost-Reduction R&D in US-Japan Cooperation

international development learn

Based on recent advances in technologies;

• Nb material/sheet preparation

- w/ optimum Nb purity and clean surface



• Surface treatments for high-Q and high-G











## Shin MICHIZONO

### International Development Team (IDT) WG2/ KEK

- ILC250 accelerator overview
- ILC area systems
  - Sources
  - Nano-beam
  - SRF
- International Development Team (IDT)
  - Civil engineering
  - Summary

### International Development Team (IDT)





#### **ILC International Development Team**

#### **Executive Board**

Americas Liaison Andrew Lankford (UC Irvine) Working Group 2 Chair Shinichiro Michizono (KEK) Working Group 3 Chair Hitoshi Murayama (UC Berkeley/U. Tokyo) Executive Board Chair and Working Group 1 Chair Tatsuya Nakada (EPFL) KEK Liaison Yasuhiro Okada (KEK) Europe Liaison Steinar Stapnes (CERN) Asia-Pacific Liaison Geoffrey Taylor (U. Melbourne)

#### IDT: to prepare for smooth transition to the ILC Pre-lab

- Prepare a proposal for the organization and governance of the ILC Pre-Lab
- Prepare the work and deliverables of the ILC Prelaboratory and workout a scenario for contributions with national and regional partners

Working Group 1 Pre-Lab Setup Working Group 2 Accelerator Working Group 3 Physics & Detectors

### Accelerator activities at ILC Pre-lab phase

#### Technical preparations & SRF R&D for cost reduction [shared across regions]

- SRF performance R&D, quality testing of a large number of cavities (~100), fabrication and shipping of cryomodules from North America and Europe (for validating shipping) **Technical preparation**
- Positron source final design and verification
- Nanobeams (ATF3 and related): Interaction region: beam focus, control; and Damping ring: fast kicker, feedback
- Beam dump: system design, beam window, cooling water circulation
- Other technical developments considered performance critical

#### Final technical design and documentation [central office in Japan with a support from other labs]

Engineering design and documentation, WBS

**Review office** 

- Cost confirmation/estimates, tender and purchase preparation, transport planning, mass-production planning and QA plans, schedule follow up and construction schedule preparation
- Site planning including environmental studies, CE, safety and infrastructure (see below for details)

**Engineering Design Report (EDR)** 

Planning and preparation of Hub lab.

Resource follow up and planning (including human resources)

#### Preparation and planning of deliverables [distributed across regions coordinated by the central office]

- Prototyping and qualification in local industries and laboratories, from SRF production lines to individual WBS items
- Local infrastructure development including preparation for the construction phase (including Hub.Lab)
- Financial follow up, planning and strategies for these activities

#### *Civil engineering, local infrastructure and site [mainly by the Japanese institutions]*

- Engineering design including cost confirmation/estimate
- Environmental impact assessment and land access
- Specification update of the underground areas including the experimental hall
- Specification update for the surface building for technical scientific and administrative needs

**Civil engineering** 





## Shin MICHIZONO

### International Development Team (IDT) WG2/ KEK

- ILC250 accelerator overview
- ILC area systems
  - Sources
  - Nano-beam
  - SRF
- International Development Team (IDT)
- Civil engineering
- Summary

### Civil Engineering related Schedule for ILC-250GeV

250GeV



References; (1) TDR, (2) Recommendations on ILC Project Implementation, 2019.

### Geological Surveys for ILC: Kitakami Mountains





Scale of the ILC-250GeV





Laser Straight Section

- BDS: "laser straight" in vertical
- ML: Cryomodule will be aligned to the geoid.





 ILC optics DECK has been updated to incorporate corrections for geoid and straight sections around the IP.

### Asymmetric straight sections

- The e- side is longer to include undulator and dog-leg.
- If e+ and e- MLs are at the same altitude, the IP is tilted by 0.1 mrad.
- If e- ML is placed 0.6 m higher than e+, the IP has no tilt and BDSs are symmetrically sloped to the IP.

### Main Linac (ML) tunnel



- 66 kV distribution cables
- Colling water pipes
- Fan Coil Units
- Low power and signal cables
- RF klystrons and modulators
  - **Electric** Power Stations

- 15 km in (e+e-) total
- follow the geoid in vertical
- Kamaboko 9.5m X 5.5m
- 1.5m central radiation shield
- Further optimization will be done.





- ML Cryomodules
- RTML
- Low power and signal cables

N.Terunuma, AWLC2020

#### CEPC workshop ILC acc.



### **Damping Ring**

international development learn

Circumference: 3.2kmStart with two rings

N.Terunuma, AWLC2020

Arc section: single tunnel, no central shield.
 Straight section: Kamaboko with a central shield (3.5m in TDR).



### Interaction Point (IP)

N.Terunuma, AWLC2020



### Cavern for Main Beam Dump





### Three big caverns

- Two main beam dumps
- e- dump for undulator, low energy collision (5 x 5 Hz)
- The main beam dump has been designed for 1 TeV collisions.
  - 5 m thick concrete shield in all directions
  - 17 MW power cooling (wider utility hall)
  - ¼ volume of detector hall
  - The civil engineering design is updating with experts from Industry (AAA).



## Shin MICHIZONO

### International Development Team (IDT) WG2/ KEK

- ILC250 accelerator overview
- ILC area systems
  - Sources
  - Nano-beam
  - SRF
- International Development Team (IDT)
- Civil engineering
- Summary

Summary

- ILC250 accelerator is 20 km long e-/e+ collider for the Higgs factory.
- The ILC is upgradable in energy and luminosity.
- *Key technologies at the ILC are superconducting rf (SRF) and nano-beam.* 
  - *SRF* technology has been widely adopted at XFELs such as European XFEL.
  - Nano-beam technology has been demonstrated at ATF hosted by KEK
- We assume 4-year preparation and 9-year construction.(now we are at pre-preparation phase (IDT))
- Preparation phase activities are
  - Technical preparation
  - Final engineering design
  - Planning and preparation of Hub lab.
  - Human resources for ILC construction ...



# Thank you for your attention

