

CEPC Booster and Collider RF Power Distribution System Design

Zusheng Zhou

Jun.15 2020


Outline

- ① Collider ring
- ② Booster
- ③ Key components R&D Progress
- ④ Future plan



For Collider ring

RF Power Distribution System

From **Klystron output window** to **SC cavity coupler**



For Collider ring



System components

1 SET SYSTEM including:

Name		Parameters	QTY	China-made
W.G.	Straight	WR1500, 800kW/400kW	Some segments	Mature
	Miter Bend	WR1500, 800kW/400kW	Some segments	Mature
	Flexible	WR1500, 800kW/400kW	Some segments	To be developed
	Directional coupler	Directivity>25dB	Some segments	Mature
Circulator		Isolation>26	1	Under development
Load		800kW	2	Under development
Magice Tee		800kW	1	Mature
Phase Shifter		360degree	1	Mature

120 SET at CEPC collider ring

Key components cover space

Circulator

(2.5m X 2.5m)

Load




(4.0m X 2.0m)

Phase shifter

(2.3m X 1.1m)

Magic Tee



(1.3m X 1.1m)



For Booster

RF Power Distribution System

From **Solid State Amplifier** to **SC cavity coupler**



System components

1 SET SYSTEM including:


Name		Parameters	QTY	China-made
W.G.	Straight	WR650, 25kW	Some segments	Mature
	Miter Bend	WR650, 25kW	Some segments	Mature
	Flexible	WR650, 25kW	Some segments	To be developed
	Directional coupler	Directivity>25dB	Some segments	Mature
Circulator		Isolation>26dB	1	Mature
Load		25kW	1	Mature

96 SET at CEPC Booster

Key components R&D progress

650MHz/800kW **Circulator**

- High power conditioning and test for 1st single layer is completed.
- 160kW full reflected power operation well.
- No arcing happened.
- The another 3 layers processing is going well.
- High power test for circulator will be done on this August.



Key components R&D progress

650MHz/800kW **Load**

- The 800kW load includes 4x200kW branches, the first branch(200kW) load is completed assembly and waiting for high power test.
- Other 3x200kW branches will be completed fabrication at the end of this month and then deliver to IHEP for high power test.



Future plan

- Development on circulator and load will be completed this year.
- Mechanical design for distribution system will be detailed and updated. **(need more mechanical designers' help)**

Thank you for your attention