

**THE 2021 INTERNATIONAL WORKSHOP
ON THE HIGH ENERGY CIRCULAR ELECTRON POSITRON COLLIDER
ONLINE BY ZOOM, CHINA**

STUDY ON THE PROCESS SIMULATION ALGORITHM OF CEPC ENGINEERING PROJECT


Wang Jiabin (王佳斌)

Huaqiao University, Quanzhou, China

Nov. 2021


PROCESS SIMULATION SYSTEM DESIGN OF CEPC

- CEPC installation and store is a problem of three stage supply chain




PROCESS SIMULATION SYSTEM DESIGN OF CEPC

- The block diagram and data model of this system



- System flow chart



ALGORITHMIC MODEL

Production processes:

$$\sum_{m=1}^M N_{mi}^k \cdot Z_{mt}^k \geq F_i^k, \quad \forall i, k, t$$

$$a_m^k \cdot (N_{mi}^k / L_m^k +) \leq tt_{mt}^k, \quad \forall i, k, t, m$$

$$\sum_{j=1}^J Nw_{jt}^k \cdot W_{jt}^k = U_{jmt}^k, \quad \forall k, t$$

ALGORITHMIC MODEL

Logistics warehouse link:

$$S_k \cdot Nw_{jt}^k \leq Ws_{jt} \quad (we_k \geq 1000), \quad \forall k, t, j \quad (4)$$

$$Nw_{jt}^k \leq Wn_{jt} \quad (we_k < 1000), \quad \forall k, t, j \quad (5)$$

$$\sum_{j=1}^J U_{jrt}^k \geq Cn_{jt}^k, \quad \forall k, t \quad (6)$$

$$C_{rt}^k + U_{jrt}^k + \sum_{j=1}^J (Cy_{jt}^k + Cn_{jt}^k) \geq F_i^k, \quad \forall k, t \quad (7)$$

$$\sum_{k=1}^K P_t^k \cdot S_k \cdot C_{rt}^k \leq Cs_{rt}, \quad \forall t \quad (8)$$

$$\sum_{j=1}^J Cy_{jt}^k \geq Sa_k, \quad \forall t, k \quad (9)$$

ALGORITHMIC MODEL

The combined effected factor

$$u_{ij} = \frac{f_{ij}}{\sqrt{\lambda_j}} \quad (i=1,2,\dots,m; j=1,2,\dots,n) \quad (10)$$

$$v_i = \sum_{j=1}^n u_{ij} s_j \quad (11)$$

$$w_i = \frac{V_i}{\sum_{i=1}^n V_i} \quad (12)$$

$$x'_{ij} = \frac{\max(x_j) - x_{ij}}{\max(x_j) - \min(x_j)} \quad (13)$$

$$y_{ij} = \frac{x'_{ij}}{\sum_{i=1}^m x'_{ij}} \quad (i=1,2,\dots,m; j=1,2,\dots,n) \quad (14)$$

$$h_j = -\left(\sum_{i=1}^m y_{ij} \ln y_{ij} \right) / \ln n \quad (15)$$

$$w_j = \frac{1 - h_j}{\sum_{j=1}^m 1 - h_j} \quad (16)$$

$$w1_j = \frac{(w1_j)^\alpha (w2_j)^{1-\alpha}}{\sum_{j=1}^n (w1_j)^\alpha (w2_j)^{1-\alpha}} \quad (17)$$

$$\sum_{j=1}^n w1_j = 1 \quad (18)$$

$$f = \sum_{j=1}^n w1_j \cdot r_{jt}, \quad \forall t \quad (19)$$

DESIGN OF TIMELINE

- In order to construct the simulation process, a virtual timeline models must be designed. The timeline simulate the passage of time to control the entire simulation process. The timeline is designed to be scalable, which means that the relationship between virtual time and real time can be adjusted. Following is the algorithm:

$$t_v = kt_r$$

t_v Virtual time t_r real time k Scaling factor $0 < k \leq 1$.

- The value of the scaling factor k is too large, it will take a lot of time. If it is too small, the simulation accuracy will be reduced, and even make error during the simulation process. Here we take $k=1/3600$ here.

DESIGN OF TIMELINE

Simulation visualization parameter

$$tv = sf.tr, sf \in (0,1) \quad (20)$$

$$Tr_{it} = Ts_{it} \cdot (1 + 0.01f), \quad \forall t, i \quad (21)$$

$$Ts_{it} = 1 / Tr_{it} \cdot Ts_{i(t-1)}, \quad \forall t \quad (22)$$

$$Status_{it} = Status_{i(t-1)} + 1 / Tr_{it} \cdot (1 - Status_{i(t-1)} \cdot 0.01), \quad \forall t \quad (23)$$

INSTANCE OF THE 12.5 KM TEST SECTION

- Following list is equipments needed in this instance
- Parameter 1:
- 1、A test section is 12.5 km long
- 2、Start time of simulation: 2020-08-07
- 3、70 manufacturers


要仿真的装配订单的零件列表:

装配订单编号 (<u>assOrderID</u>)	设备类型 (<u>equcategoryID</u>)	数量	所属装配标段	安装开始启动时间
ass0001	主环标准周期二极铁	1400	1	2028/3/01
ass0002	主环标准周期二极铁	1400	2	2028/4/25
ass0003	主环标准周期二极铁	1400	3	2028/6/18
ass0004	主环标准周期二极铁	1400	4	2028/8/10
ass0005	主环标准周期四极铁	280	1	2028/10/1
ass0006	主环标准周期四极铁	280	2	2028/10/6
ass0007	主环标准周期四极铁	280	3	2028/10/11
ass0008	主环标准周期四极铁	280	4	2028/10/16
ass0009	主环标准周期六极铁 1	56	1	2028/10/23
ass0010	主环标准周期六极铁 1	56	2	2028/10/24
ass0011	主环标准周期六极铁 1	56	3	2028/10/25
ass0012	主环标准周期六极铁 1	56	4	2028/10/26
ass0013	主环标准周期校正铁	280	1	2028/11/1
ass0014	主环标准周期校正铁	280	2	2028/11/5
ass0015	主环标准周期校正铁	280	3	2028/11/8
ass0016	主环标准周期校正铁	280	4	2028/11/11
ass0017	主环标准周期 BPM	280	1	2028/11/16
ass0018	主环标准周期 BPM	280	2	2028/11/20
ass0019	主环标准周期 BPM	280	3	2028/11/24
ass0020	主环标准周期 BPM	280	4	2028/12/28
ass0021	主环恒温器	20	1	2028/12/1
ass0022	主环超导四极铁	4	3	2028/12/1

ass0064	booster 标准周期 BPM	200	2	2029/2/3
ass0065	booster 标准周期 BPM	200	3	2029/2/6
ass0066	booster 标准周期 BPM	200	4	2029/2/9
ass0067	booster 恒温器	6	1	2029/2/12
ass0068	booster 切割铁	16	1	2029/2/12
ass0069	boosterkicker	4	1	2029/2/12
ass0070	booster 非标准周期二极铁	40	13	2029/2/12
ass0071	booster 非标准周期二极铁	40	2	2029/2/14
ass0072	booster 非标准周期二极铁	40	3	2029/2/16
ass0073	booster 非标准周期二极铁	40	4	2029/2/18
ass0074	booster 非标准周期四极铁	54	1	2029/2/20
ass0075	booster 非标准周期四极铁	54	2	2029/2/21
ass0076	booster 非标准周期四极铁	55	3	2029/2/23
ass0077	booster 非标准周期四极铁	55	4	2029/2/24
ass0078	booster 非标准周期六极铁	37	1	2029/2/26
ass0079	booster 非标准周期六极铁	38	2	2029/2/26
ass0080	booster 非标准周期六极铁	38	3	2029/2/27
ass0081	booster 非标准周期六极铁	37	4	2029/2/28
ass0082	主环标准周期六极铁 2	56	1	2028/10/27
ass0083	主环标准周期六极铁 2	56	2	2028/10/28
ass0084	主环标准周期六极铁 2	56	3	2028/10/29
ass0085	主环标准周期六极铁 2	56	4	2028/10/30
ass0086	主环非标准周期六极铁 2	30	1	2029/1/28
ass0087	主环非标准周期六极铁 2	30	2	2029/1/29
ass0088	主环非标准周期六极铁 2	30	3	2029/1/30
ass0089	主环非标准周期六极铁 2	30	4	2029/1/31

INSTANCE OF THE 12.5 KM TEST SECTION

- Parameter 2:
- 1、 Layout of the warehouse in right
- 2、 Specifications of warehouse: 100m*50m
- 3、 warehouse type1 (only stacking area) , the areas is about 4000m².
- 4、 warehouse type2 (with shelf) , the areas is about 3000m² , the number of shelf is 264.



INSTANCE OF THE 12.5 KM TEST SECTION

- Warehouse model




Figure 4 warehouse layout (1)




Figure 5 warehouse layout (2)

INSTANCE OF THE 12.5 KM TEST SECTION

- Equipment parameters (part of)

Equipment name	quantity	External dimension	Equipment weight / kg	Calibration / installation sequence	Note: is it possible to calibrate / install in parallel
Standard Period Diode Iron of Main Ring	5600	5.67*0.53*0.14	3000	1	yes
Main ring standard period <u>quadrupole iron</u>	1120	2*0.7*0.56	6500	2	yes
Main ring standard period <u>hexapole iron</u>	448	1.4*0.34*0.345	1400	3	yes
Main ring standard period correction iron	1120	0.9*0.5*0.5	1900	4	no


INSTANCE OF THE 12.5 KM TEST SECTION

- Process timetable (part of)

Equipment name	Calibration start time	Calibration end time	Calibration speed: set / day	Installation start time	Installation end time	<u>Install-ation speed:</u> set / day
Standard Period Diode Iron of Main Ring	2024/1/7	2025/11/9	10	2028/3/1	2028/9/30	32
Main ring standard <u>period quadrupole iron</u>	2025/11/9	2026/1/16	20	2028/10/1	2028/10/22	64
Main ring standard <u>period hexapole iron</u>	2026/1/16	2026/2/12	20	2028/10/23	2028/10/31	64
Main ring standard <u>period correction iron</u>	2026/2/12	2026/3/18	40	2028/11/1	2028/11/15	96


SIMULATION RESULTS

- The combined effects of factors












SIMULATION RESULTS

- T_r & T_s



SIMULATION RESULTS


- Warehouse utilization (part of)



MODEL VALIDATION TESTS

- Change the number of Manufacturer


Number of production companies/warehouse number	1	2	3	4	5	6	7	8	9	Delay days of construction period
70	70	93	81	98	99	98	98	93	99	3
60	85	96	98	99	98	88	98	71	91	8
55	81	98	98	69	85	99	83	98	99	4
50	82	99	83	84	92	95	92	63	98	15
47	74	95	98	98	99	82	99	95	89	7



MODEL VALIDATION TESTS

- Change the start time of the production order

Number of manufacturing enterprises / warehouse number	1	2	3	4	5	6	7	8	9	Delay days of construction period
70	75	89	93	99	95	83	96	98	99	13
60	81	98	89	97	85	99	83	98	99	167
55	85	99	97	87	92	98	97	98	93	180
47	78	92	99	98	70	95	95	99	98	230



INSTANCE OF THE 12.5 KM TEST SECTION

Interface of simulation system

CEPC仓库规划仿真计算

2020-12-8

重置

装配订单进程:

装配订单ass0001的进度: 10% | 10/100 [00:00<00:00, 9962.72it/s]
主环标准周期二极铁

生产过程:

生产订单pro09的进度 (ass0001): 22% | 22/100 [00:00<?, ?it/s]
主环标准周期二极铁

生产订单pro08的进度 (ass0001): 23% | 23/100 [00:00<?, ?it/s]
主环标准周期二极铁

生产订单pro07的进度 (ass0001): 21% | 21/100 [00:00<?, ?it/s]
主环标准周期二极铁

生产订单pro06的进度 (ass0001): 23% | 23/100 [00:00<?, ?it/s]
主环标准周期二极铁

生产订单pro05的进度 (ass0001): 23% | 23/100 [00:00<00:00, 23012.64it/s]
主环标准周期二极铁

物流过程:

仓库状态:

仓库9 (标段1)的利用率: 0% | 0/100 [00:00<?, ?it/s]

仓库8 (标段1)的利用率: 0% | 0/100 [00:00<?, ?it/s]

仓库7 (标段1)的利用率: 0% | 0/100 [00:00<?, ?it/s]

仓库6 (标段1)的利用率: 0% | 0/100 [00:00<?, ?it/s]

仓库5 (标段1)的利用率: 0% | 0/100 [00:00<?, ?it/s]

仓库40 (标段8)的利用率: 0% | 0/100 [00:00<?, ?it/s]

仓库4 (标段1)的利用率: 0% | 0/100 [00:00<?, ?it/s]

仓库39 (标段7)的利用率: 0% | 0/100 [00:00<?, ?it/s]

激活 Windows
转到设置以激活 Windows。


INSTANCE OF THE 12.5 KM TEST SECTION

Interface
of
simulation
system



INSTANCE OF THE 12.5 KM TEST SECTION

- Warehouse layout



INSTANCE OF THE 12.5 KM TEST SECTION

- Simulation result:
- the number of warehouses at each horizontal cave entrance is 2 in this test section , one of the warehouse with shelf.
- simulation start time: 2020-8-7
- schedule end time: 2029-2-28
- actual end time: 2029-3-2, delay 3 days。
- The running time of the computer: 26h25m31s。
- Numbers of Warehouse:36
- Numbers of Calibration Warehouse:1



WAREHOUSE SIMULATION PROCESS OUTPUT TO BIM

- The simulation process is combined and sharing the database with BIM, use BIM for 3D modeling , and to display warehouse usage rate . This make the process intuitive. The table in right is the data shared with BIM.
- Inventory out also can be displayed by BIM in 3D model。






字段	字段类型	说明
设备编号	Vchar(20)	设备编号
设备类名称	Vchar(30)	设备类名称
仓库组X坐标	int	X坐标
仓库组Y坐标	int	Y坐标
仓库X坐标	int	X坐标
仓库Y坐标	int	Y坐标
堆货区X坐标	int	X坐标
堆货区Y坐标	int	Y坐标
堆货单元X坐标	int	X坐标
堆货单元Y坐标	int	Y坐标
堆放规则	int	0表示横放, 1表示竖放
货架X坐标	int	X坐标
货架Y坐标	int	Y坐标
货架单元X坐标	int	X坐标
货架单元Y坐标	int	Y坐标
货架单元Z坐标	int	Z坐标

WAREHOUSE SIMULATION PROCESS OUTPUT TO BIM

- The result of warehouse 3D model display.



WAREHOUSE SIMULATION PROCESS OUTPUT TO BIM



THANKS !

- Nov. 2021
- Online by Zoom, China.