



中国科学院高能物理研究所
Institute of High Energy Physics, Chinese Academy of Sciences

Lithium vapour

Wakefield
acceleration

The strategic planning for the PBA-TF and the corresponding team

Ion channel

Dr. Dazhang Li, et al.

On behalf of the CEPC Plasma Injector team

Pulse electron



Outlines





- **Motivations and goals**
- **Current status and timetable**
- **Preliminary progress and growing team**

PWFA TF: for FEL and for Future Collider




2020 ULTRAHIGH INTENSITY LASER FACILITIES



Electron Beam Parameter	Baseline Design	Operational Ranges	Positron Beam Parameter	Baseline Design	Operational Ranges
Final Energy [GeV]	10	4.0-13.5	Final Energy [GeV]	10	4.0-13.5
Charge per pulse [nC]	2	0.7-5	Charge per pulse [nC]	1	0.7-2
Repetition Rate [Hz]	30	1-30	Repetition Rate [Hz]	5	1-5
Norm. Emittance $\gamma\epsilon_{x,y}$ at S19 [μm]	4.4, 3.2	3-6	Norm. Emittance $\gamma\epsilon_{x,y}$ at S19	10, 10	6-20
Spot Size at IP $\sigma_{x,y}$ [μm]	18, 12	5-20	Spot Size at IP $\sigma_{x,y}$ [μm]	16, 16	5-20
Min. Bunch Length σ_z (rms) [μm]	1.8	0.7-20	Min. Bunch Length σ_z (rms)	16	8
Max. Peak current I _{pk} [kA]	72	10-200	Max. Peak current I _{pk} [kA]	6	12

Affiliations/institutes on PWFA Study





CPI TF: not only for PBA, but also for conv. acc.



Key issues		Preliminary study/ Conceptual design	Detailed and convincing simulations / designs	Experiment test / Prototype
e- PWFA	HTR	√	√	×
	Beam quality preservation	√	√	×
	Error analysis	√	×	×
e+ PWFA	High quality practical scheme	√	√	×
	More schemes, HTR etc.	√	×	×
	High efficiency	√	×	×
Conv. acc. physics and techniques	High charge L-band RF Gun	√	×	×
	Beam profile preservation	√	×	×
	Beam merging	√	×	×
	Instrumentation	√	×	×
	Timing synchronization	√	×	×
	Positron beamline	√	√	×
Plasmas source and beam manipulation	Plasma dechirper	√	√	√
	Plasma lens	×	×	×
	Plasma sources	√	√	×
	Staging	√	×	×



Principles of CPI TF: unique and cost-effective



Beam Parameters of FACET-II

Electron Beam Parameter	Baseline Design	Operational Ranges	Positron Beam Parameter	Baseline Design	Operational Ranges
Final Energy [GeV]	10	4.0-13.5	Final Energy [GeV]	10	4.0-13.5
Charge per pulse [nC]	2	0.7-5	Charge per pulse [nC]	1	0.7-2
Repetition Rate [Hz]	30	1-30	Repetition Rate [Hz]	5	1-5
Norm. Emittance $\gamma\epsilon_{x,y}$ at S19 [μm]	4.4, 3.2	3-6	Norm. Emittance $\gamma\epsilon_{x,y}$ at S19	10, 10	6-20
Spot Size at IP $\sigma_{x,y}$ [μm]	18, 12	5-20	Spot Size at IP $\sigma_{x,y}$ [μm]	16, 16	5-20
Min. Bunch Length σ_z (rms) [μm]	1.8	0.7-20	Min. Bunch Length σ_z (rms)	16	8
Max. Peak current I_{pk} [kA]	72	10-200	Max. Peak current I_{pk} [kA]	6	12

Beam Parameters of FLASHForward


Beam type	e- only
Beam energy	1.25 GeV
Transverse emittance (nor.)	2 mm·mrad
Peak current	2.5 kA
Bunch charge	0.1~3 nC
Focal spot	~ 7 μm
Energy spread	0.1%

Principles of CPI TF

1. MUST including e+ beamline
2. High charge L-band RF needed
3. Staging of different types of accelerators
4. As low energy as possible
5. PWFA-based FEL studies included
6. Scheme 1: based on BEPC-II linac
7. Scheme 2: a new dedicated TF based on a SC linac for high rep. rate and high average power EUV source studies
8. $I_{\text{peak}} \geq 3\text{kA}$; $n_b \geq n_p (10^{16}\text{cm}^{-3}) \rightarrow$
3kA @ 10 $\mu\text{m} \times 10\mu\text{m}$



Preliminary design for a plasma acceleration TF






Outlines



- Motivations and goals
- **Current status and timetable**
- **Preliminary progress and growing team**



BEPC-II linac and Hall 10



Beam Parameters before AM3 magnet

	e-	e+ (not accurate)
Beam energy	$\leq 2.5 \text{ GeV}$	$\leq 2.5 \text{ GeV}$
Geo. Emittance	$0.1 \text{ mm}\cdot\text{mrad}$	$0.4 \text{ mm}\cdot\text{mrad}$
Peak current	0.5 kA	$\sim 0.01 \text{ kA}$
Bunch charge	2 nC	$< 0.1 \text{ nC}$
Focal spot	$1.1 \text{ mm} \times 1.1 \text{ mm}$	$2 \text{ mm} \times 2 \text{ mm}$
Energy spread	0.5%	0.5%



Hall 10 upgrade proposals and beam qualities



- **Phase I (1-2 years):**
 - Overall lattice and light path design
 - New transport beamline installation & commissioning
 - Final Focus installation in Hall 10
 - Clean room + laser system installation
 - L-band RF gun design
- **Phase II (3-5 years):**
 - L-band RF gun fabrication and test
 - Instrumentation installation
 - Laser system and beamline combination
- **Phase III (~ 5 years):**
 - L-band RF installation and BEPC-II linac upgrade
 - e+ beamline installation
 - PBA based FEL studies

Phase I	e0	e1	p1	eL
Energy	≤ 2.5 GeV	/	≤ 2.5 GeV	≤ 0.5 GeV
Peak current	0.5 kA	~ 2 kA	~ 0.1 kA	≥ 5kA
Bunch charge	2 nC	2nC	< 0.1nC	0.2nC
Focal spot	1.1mm	50μm	50μm	1μm
Energy spread	0.5%	0.5%	0.5%	< 5%
Profile	Gaussian	Gaussian	Gaussian	Gaussian
Phase II & III	e1	e2	p2	eL
Energy	/	≤ 2.5 GeV	0.4~0.6 GeV	≤ 0.5 GeV
Peak current	~ 2 kA	≥ 6 kA	~ 3 kA	≥ 5kA
Bunch charge	2nC	10 nC	~ 1nC	0.2nC
Focal spot	50μm	< 10μm	50μm	1μm
Energy spread	0.5%	/	/	< 5%
Profile	Gaussian	triangle	Gaussian	Gaussian



Beam requirement for different studies



Research		driver	trailer	Phase I	e0	e1	p1	eL
e- PWFA	① blowout acc.	e1 or eL		Energy	≤ 2.5 GeV	/	≤ 2.5 GeV	≤ 0.5 GeV
	③ HTR acc.	e2	e1 or eL	Peak current	0.5 kA	~ 2 kA	~ 0.1 kA	≥ 5kA
e+ PWFA	① acc. structure	e1	/	Bunch charge	2 nC	2nC	< 0.1nC	0.2nC
	① preliminary acc.	eL	p1	Focal spot	1.1mm	50μm	50μm	1μm
	③ High quality acc.	e2	p2	Energy spread	0.5%	0.5%	0.5%	< 5%
Conv. acc. physics and techniques	② L-band RF gun test	/	/	Profile	Gaussian	Gaussian	Gaussian	Gaussian
	③ Beam profile	e2	/	Phase II & III	e1	e2	p2	eL
	① Beam merging	e1/eL		Energy	/	≤ 2.5 GeV	0.4~0.6 GeV	≤ 0.5 GeV
	② Instrumentation	eL	/	Peak current	~ 2 kA	≥ 6 kA	~ 3 kA	≥ 5kA
	② Synchronization	eL	e1/e2	Bunch charge	2nC	10 nC	~ 1nC	0.2nC
	③ e+ beamline	p2	/	Focal spot	50μm	< 10μm	50μm	1μm
Plasms source and beam manipulation	① Dechirper	e1/eL	/	Energy spread	0.5%	/	/	< 5%
	② Plasma lens	/	/	Profile	Gaussian	triangle	Gaussian	Gaussian
	① Plasma sources	/	/	<ul style="list-style-type: none"> • 2022.12: Phase I conceptual design (physics) • 2023.02: Phase I technical design (engineering drawing) and Phase II and III conceptual design (physics) • 2022.04: Phase II and III technical design (engineering drawing) 				
	③ Staging	e1, e2, eL						

- 2022.12: Phase I conceptual design (physics)
- 2023.02: Phase I technical design (engineering drawing) and Phase II and III conceptual design (physics)
- 2022.04: Phase II and III technical design (engineering drawing)




Outlines



- Motivations and goals
- Current status and timetable
- **Preliminary progress and growing team**





Transport Line from AM3 to Hall 10



- **Main function of the new transport line:**
 - Dispersion correction (since the energy spread is large)
 - Bunch length compression from 1.2mm to ≤ 0.3 mm
 - Similar twiss parameters before AM3 and after B3
- **Boundary condition:**
 - Space limit, especially around AM3, B1
 - Same deflect angle for AM3, B1 and B2, B3
 - AM3 to Hall 10: ~ 18 -20 meters
 - Quadruple ≤ 30 T/m, Dipole ≤ 1.4 T (for large beam pipe)
 - Gap between magnets should be larger than 30cm
- **Basic method:**
 - Local dispersion correction (B+Q+B)
 - Add chicane for bunch length compression




Space limit: AM3, B1 and Q1








Preliminary optimization results




磁铁参数	AM3/B1/B2/B3	B	QF1	QD1	QF2	QF3	QD2/QD3	QF4
Length[m]	0.98	1.1	0.5					
Strength	1.22 T	1.2 T	23 T/m	12 T/m	11 T/m	23 T/m	21.4 T/m	23 T/m



by Dr. Xueyan Shi, Haisheng Xu and Weibin Liu





Conceptual design for BEPC-II main Linac upgrade



1. e+ beamline
2. e- L-band RF gun
3. e- beam line (for RF gun)



Main Linac upgrade -- e+ beamline -- extraction




• 限制条件 (需要实际查看)

- 两个四极磁铁之间距离350mm, 四极磁铁长度100/200mm, 四极磁铁与下游加速结果长度307mm (可能有BCT?)

• 布局1

- 二极磁铁放在Q2与Q1B之间
- 正电子400MeV→磁刚度1.334T-m
 - 偏转半径1.2m, 磁场强度1.2T
- 偏转角度13°
 - 在加速结构处, 偏离约130mm, 估计基本满足要求
 - Q1B处孔径太大, 需要重新设计





Main Linac upgrade -- e+ beamline -- through wall



• 正电子束线过墙 (需要明确过墙尺寸限制)

• 要求过屏蔽墙只能小孔过, 不能放四极磁铁

• 需要在直线隧道内完成局部消色散

• 方案1: 采用~270°弯铁系统, 两个~135°偏转铁+四极磁铁 (×)




➢ 【√】可以在过墙之前放置triplet, 长漂移段

➢ 【×】横向空间要求占用人行道侧大于2.4m, 超过直线隧道横向空间

• 方案2: 采用<90°弯铁系统, 比如两个35°偏转铁+四极磁铁


➢ 横向空间要求 $\rho \left(1 - \cos \theta + \frac{1}{2 \cos \theta}\right) + L \sin \theta$, 占用内测空间, 需要确认空间是否满足要求

➢ 偏转系统之前放置四极磁铁





400MeV e+ DR (600 MeV DR under consideration)



	DR
Energy (Mev)	400
Circumference (m)	33
Number of bunches	1
Bunch charge (nC)	1.0
Bending radius (m)	1.0
Dipole strength B_0 (T)	1.3
U_0 (kev/turn)	2.6
Damping time x/y/z (ms)	33.5/33.5/16.9
Phase/cell (degree)	60/60
Momentum compaction	0.088
Storage time (ms)	∞ ?
δ_0 (%)	0.039
ϵ_0 (mm.mrad)	35
injection σ_z (mm)	3.1
Extract σ_z (mm)	2.65
ϵ_{inj} (mm.mrad)	2500
$\epsilon_{ext\ x/y}$ (mm.mrad)	35/49
$\delta_{inj}/\delta_{ext}$ (%)	0.3%/0.039%
Energy acceptance by RF(%)	2.8
f_{RF} (MHz)	500
V_{RF} (MV)	2.4
Longitudinal tune	0.068

e+ DR 基础方案设计参数



Manpower distribution (IHEP team & THU team)



- **In charge: Prof. Yuhui Li and Prof. [Wei Lu](#) (take regular meeting fortnightly)**
- **Overall lattice design:**
 - Transport line: [Weibin Liu](#), Xueyan Shi, Haisheng Xu;
 - Final Focus in Hall 10: [Yiwei Wang](#), Cai Meng, Dou Wang; Zhi Song, Hengyuan Xiao
 - BEPC-II main Linac: [Cai Meng](#), Xiaoping Li, Lei Du;
 - L-band RF Gun: [Xiaoping Li](#), Guan Shu; [Zhi Song](#)
 - e+ beamline: [Dou Wang](#), Lei Du, Xiaohao Cui, Zhe Duan (polarization)
 - Instrumentation: [Huizhou Ma](#), Yanfeng Sui (may need more people)
 - Beam dump and radiation protection: [Zhongjian Ma](#)
 - FEL related: [Yuhui Li](#)
 - Other supporter from AC: Xiang He, Dayong He (AC-Linac); Jianli Wang (AC-Mechanical).....
- **Laser installation and optics path design:**
 - 40TW, 200TW and 1PW Laser system: [Desheng Hong](#), Fei Li
 - Clean room and Hall 10 decoration: [Dazhang Li](#), Jianfei Hua
 - Laser system and beamline combination: [Dazhang Li](#), Caimeng; [Jianfei Hua](#), Fei Li
 - Plasma source and fs e- probe: [Fei Li](#), [Shuang Liu](#)

