

CEPC control designs and studies

Presented by Gang Li Accelerator Division, Control Group



中國科學院為能物昭和完備 Institute of High Energy Physics Chinese Academy of Sciences

23-27. Oct. 2023, Nanjing, the 2023 international workshop on the high energy CEPC



•Scope and Performance of the CEPC control system

•Requirement information of controlled devices

Control system and sub-system



Scope of the Control System

Global control

- Center Control System: Control Platform, computers, servers, database, etc
- Control network System
- Timing System
- Machine Protection System
- Video monitoring system
- Local control
 - Power Supply Control System
 - Vacuum Control System
 - Temperature Monitoring System
 - Linac Control System
- Integration of sub-systems
 - LLRF, Cryogenic system, Injection/Extraction system etc.
- Interface to other systems
 - Detector(Experimental physics), beamline and conventional facility

Performance of the Control System

5*bility+RT

- Stability
- Availability
- Flexibility
- Scalability
- Reliability
- Real Time

Requirement information of controlled devices

Bilingual requirement table


🖬 CEPC-TDR控制需求信息调查表2018-低温 (2)-Requirement from Cryo.xlsx

CEPC-TDR控制需求信息调查表2018-低温-Requirement from Cryo.xlsx

	¢ ∓		CEPC	3源与控制接口(信息-20190618-E	· ·	1			v		
文件 开始	插入 页 imes New Ron	瓦面布局 公式 数据 nan v 8 v A A A			福昕PDF (ab 常规	2 告诉我你想要	2	Type/Affiliations	Quantity	Location	Precision	Interface
· · · · ·	B I ∐	• 🔄 • 🖄 • 🗛 • 💥		€ →	↔ .	% 9 .0	3	Collider	8160			
剪贴板 🕞		字体	. 对矛	下方式	F5	数字	4	Dipole-Double	8	8 Power Supply Hall	100ppm	以太网
4 -	: × ✓	fx					5	Dipole-Singular	162	96 Auxiliary Tunnel unit	100ppm	以太网
А	В	С	D	Е	F	G	6	Quadrupole-Double	192	96 Auxiliary Tunnel unit	100ppm	以太网
							7	Quadrupole-Singular	920	96 Auxiliary Tunnel unit	100ppm	以太网
位置	电源数量	安装位置	精度	接口类型			8		80	96 Auxiliary Tunnel unit	100ppm	以太网
Collider	816	50					9		22	96 Auxiliary Tunnel unit	100ppm	以太网
Dipole双		8 均匀分布在地上8个电源		以太网			10	Sextupole	896	96 Auxiliary Tunnel unit	100ppm	以太网
Dipole单 Quadrupole双		62 均匀分布在地下96个辅助92 均匀分布在地下96个辅助		以太网			11		72	96 Auxiliary Tunnel unit	100ppm	以太网
Quadrupole单	9.	20 均匀分布在地下96个辅助		以太网			12	Corrector	2904	96 Auxiliary Tunnel unit	500ppm	以太网
		80 均匀分布在地下96个辅助22 均匀分布在地下96个辅助		以太网			13		2904	96 Auxiliary Tunnel unit	500ppm	以太网
Sextupole		 96 均匀分布在地下96个辅助 		以太网			14					
		72 均匀分布在地下96个辅助	遂道 100ppm	以太网								
Corrector	29	04 均匀分布在地下96个辅助	遂道 500ppm	以太网			15					
	29	04 均匀分布在地下96个辅助	遂道 500ppm	以太网			16					
							-	Tom - / A COlt - 41-	Orrentite	T (1)	D · · ·	T
							17	Type/Affiliations	Quantity	Location	Precision	Interfac
位置	电源数量	安装位置	精度	接口类型								
▶ 与控制	接口信息 In	terface information of	PS (+)									

Characteristic of CEPC


- Super scale
 - Linac: 1.8km
 - Ring: 100km circumference (booster and collider)
- A large number of Controlled Equipments
 - Discrete distributed in the Linac and Ring
- Quantity of PVs
 - Millions of PVs



Overall architecture of the CEPC control system

Standardization of CEPC Control system

- Software Platform
 - EPICS : open source, free SCADA/DCS, toolkits
 - Modern industry standards/ technology to manage EPICS (IOC/Driver/GUI)
 - Docker, Kubernetes, and Sumo etc.
- Hardware Platform
 - Standardization, Modularity and COTS (Commercial-Off-the-Shelf)
 - Workstations and servers
 - ATCA/uTCA
 - PLC
 - Motion controller/Driver
 - etc.



Central Control System

- Control Rooms
- Management and operation of IOCs/OPIs
- Server and management of High level software
- CA/PVA Gateway
- OPI tools--CSS, caQtDM, PyDM etc
- Data Archiver
- Alarming system
- Elog
- Issue information of machine via instant message(weChat)
- Machine status summary on Web
- Etc


Control Rooms(While construction, commissioning at the same time)

– One central control room for whole CEPC

One temporary Linac control room for commissioning at initial stage of CEPC
 Dozens of local control room (mini console) for the site commissioning




CCR Renderings of CSNS





HEPS-LINAC (Temporary)

- OPI/GUI tools
 - edd/dm(2k),medm,edm,CSS, caQtDM, PyDM, etc
 - Update, 5~10 years
 - Keep up with OPI technological progress



BTS VACUUM TIMING STATUS WATER ACIS IWSYA RF-SY RF-5


caQtDM Examples

BOOSTER SYNCHROTRON




Go Dark Form

ciliset: 00000 Step:



Data Archiver -- Archiver Appliance (AA)

- Archive millions of PVs
- Cluster



Multiple appliances sending data into different long term stores

Data retrieval request for PV in other appliance

Alarming system

- Monitor PVs
- Track alarms
- Acknowledgement


Alarm Area Pa	1074916 I	= 0				10
BeamPermit	(CF)	HPRF_PLC_Check				
RF	PPS	Tunnels				
Water Plamp	IonSource&LEBT	REQ				
MEBT	DTL	CCL				
SCL	HEBT	RID				
Ring .	RTBT	Thirget				
Tinst	Instrument Hall	CER				
Veccom	CHL	Operations				
HVCM	RF Transmitters	Fomentum Dum				
Test HVCM	m Test Facility (st RF Transmitte				
	Klystron Gallery	Contraction of the second second				
and share to be the second second second	get Service Build					
Alarm Tree 13		= 0	Alarm Table [CCR] 12			
CCR +		* 1 1 E	I service the service the		Sala <u>n</u>	
Area: Beam			Current Alarms (2)	Se	lect	*
SAme CF Lundefines ack adding Connectional			PV	Description	Alarm Time	Current Seven Current Status
Area: HPRF_PLC_Check			ICS_Opr:RFQ:VacuumAlarm	Attention. R F Q vacuum alarm	2018-05-30 08:45:40	OK NO_ALARM
Area: RF			CF_RN DIWS_AIT46D18:Rs	Hebbit Ring RTBT Magnets DI water polishing log	op 2018-05-30 03:28:11	MAJOR HIGH_ALARM
Area: PPS				05:55:17 Check Ring DI Water Cooling Lo.		
Area: Tunnel	İs			Contact water group personnel		
Area: Water	Pump			Cooling Overview Screen		
Area: JonSou	urce&LEBT			12 rationale_guidance		
Area: RFQ				HEBT/Ring/RTBT Magnets DI Wate		
Area: MEBT				Copy to clip-board		
Area: DTL		-		Acknowledge		
Area: CCL			cir	7 Configure Item		1
Area: SCL			<u>(</u>	U Disable Alarms		
🖌 🖕 Area: HEBT			Acknowledged Alarms (13)	III Alarm Perspective	and the second	and the second sec
Area: RID			PV	De Create Log Entry	Alarm Time	Current Severi Current Status
Area: Ring ()	MAJOR/HIGH_ALAR	M	Test_LLRF:Cav_RFQ1:OK	A X Process Variable	2018-05-17 01:59:54	MARTA STATE_ALARM
Area: RTBT			Test_HPRF.Xmtr101:RP_Fit	BTF rf transmitter fault	2018-05-25 10:24:11	MAJOR STATE_ALARM
🖉 🖪 Area: Target			Test_HPRF:PPSSwitch_RFQ:Sum	Attention. Attention. BTF RFQ PP5 is inhibited	2018-05-23 15:36:30	MAKIN HIHLALARM
Area: Target						
Area: Target Area: Test			SpRFQ_Cool:TestStand:WaterLe	a Attention. B T F Water Leak Alarm	2018-05-29 12:13:48	INVALID READ_ALARM

Electronic log system

- Server for operators, engineers, and users of large scientific facilities
- Online digital logbook service
- Create log entries
 - Meta-data
 - Attachments
- Search
- Authentication

9			Clog × +								
			← → C △ O localhost:8080/logbook/62f5c30af257854d94c551af							Q 🖻 🛧 🌒 🗤	🙁 🖈 🔲 🕕 Paused Update
			Clog a mn 🖌 mm -			e 浏览器	 ◆ 设置 ~ ① 关于 ● 浏览器语言 ● Controls 				🔺 wanglin 🚿
			← 18101	+ mix		❷ 多语言	O 简体中 O Englisi				10数 𞥕/5/收, 后部, 内容, 按许
IOF								« « 1 »	>> Showing 1 to 17 of 17 logs	25 ~	
ICE			座明	esatelan actor ∨	ft At 210	PEREAR PAR	美別 请法师	移送 清洗将 〜	标理 关键词	内容	R144
BOOK			1	2022-08-29	王林	wanglin©ihe	p.ac.cn Info		JWT Token 11111222 🕐	33344555	13
just for you. It all the time.			2	2022-09-07	王林	wanglin©ihe	p.ac.cn Info		111	222	
			3	2022-08-29	王林	wanglin@ihe	p.ac.cn Info			33333333333333333444	8.7
			4	2022-08-30	33356	wanglin111@	hep.ac.cn Info	Testing222. 345678	11212121 🧿	343434345555 6666	
		Olog Now L	5	2022-08-30	王林	wanglin@ihe	p.ac.cn Info		OAuth12333444 🧿	456667778899	
		v1.0.6	6	2022-08-29	王林	wanglin©ihe	p.ac.cn Info		OAuth12333444	45666777	
			7	2022-08-29	王林	wanglin@ihe	p.ac.cn Info		LDAP12333444	45666777	
		< No search string	8	2022-08-29	王林	wanglin@ihe	p.ac.cn Info		LDAP12333444	45666777	
		周四上午9点,新	9	2022-08-29	王林	wanglin©ihe	p.ac.cn Info		12333444	45666777	
		线控制技术讨论	10	2022-08-25	王林	wanglin@ibe	p.ac.cn Info		12333	45666	
		ligang	11	2022-08-19	王林	wanglin©ihe	p.ac.cn Info	Testing222	12345566 🧿	678900	¥ 5
	60 % Brows2017 Gruengdo /* 14	m system调 进(需要… 学科大村 F发介绍(刘 压电运动控	109 网络线螺数运 试卸署 监控系统 (新) 2. 机	R 202 斑疽 大 202	36 23-04-19 21:21:02 35 23-02-21 20:35-31	4、IHEP-ACS联 5、运动控制 6、针对即将安 7、B7线站"飞去	Normal detector开发介 展 (雪薇) 电运动控制与升 合培训及下一次 后相核心板卡延 调BE, 各子系统 3"实验在BSRF/3	、栅尺回采数值不一致 、内部培训(宗仰,小 期及其解决方案(宗f 的准备(所有人) WW1的验证测试(爱王	印) E, 刘玙等)		
		 1、机房装修(装修公司、 玙、张群)3、B6实验站 ++++=====+++++= 	控制任务讨		表-	34	✓ Attachments	204175201T0151	费核算,设备采购,)	нага -магад /	
							No Attachmente				

- Issue information of machine based on weChat or Apps
 - Get to know information of CEPC complex anytime, anywhere
 - PVs and another information







Control system & sub-system: Control Network

Data rate/traffic/congestion in the network

- Low latency switch
- Vlan Technology
- PVA/CA Gataway



EPICS Gataway




Control Network System: three layers

Machine Protection System (MPS)

- Stop beam or steer beam to dump, when key device or sub-system is a fault or abnormal
- Tightly related to the accelerator design


Generally, the structure of MPS=EPS (PLC)+FPS (FPGA)



PLC for slow inputs, a response time of tens of ms is defined

- The actuators are RF power ramp down and shutdown of electron gun
- Preliminary name : Equipment Protection System (EPS)
- FPGA for fast inputs, a response time of tens of us is defined
 - The actuators are RF power off and shutdown of electron gun.
 - Preliminary name : Fast Protection System (FPS).
- Individual systems for loose coupling, easy implementation and debug

18







Instance of HEPS' MPS

Video Surveillance System

- Record the device installation process as an image archive
- Monitoring equipment status and on-site scenarios
- Fixed-position camera and mobile camera







镜头选配表								
镜头毫米数	2.8mm	3.6mm	6mm	8mm	12mm	16mm		
建议照射距离	0-5m	0-5m	5-10m	10-20m	20-35m	30-50m		
1/3 感光度	85°	75°	50°	38°	26°	20°		



Control system & sub-system: Timing system

Preliminary timing signal statistics of controlled devices

Destination	Quantity	Specification	Supplementary Notes
BI(TTL信号)	10664	Jitter<50ps	BPM、profile、DCCT、Tuning、 BCM and BLM
BI(RF信号)	5030	Jitter<0.5ps, <1ps, <5ps	BPM、Profile、DCCT、Tuning、 BCM and BLM
PS	860	Jitter<5ns	Booster 、 Dipole 、 Quadrupole 、 Sextupole 、 Corrector and so on
RF	883	Jitter<50fs, <100fs, <50ps	

Control system & sub-system: Timing system

TS-MS: Timing System Main Station

TS-sSL/IE: Timing System sub Station

TS-sSL: Timing System sub Station for Linac

TS-sS: Timing System sub Station

for Injection and extraction

TS-sSO: other sub Station,....

sSIF

TS-MS

ſS-

The basic structure of Timing System


- Event system and RF transmission system
- Event system: Trigger signal and Low frequency clock signal
- RF transmission system: Transmit high stability RF signal

TS-MS: In CCR or RF-station
TS-sS: Close to the controlled devices in subtunnels or other hall

Control system and sub-system: Vacuum CS


Vacuum equipments

- Vacuum Gauge: 7574
- Ion pump: 22607
- Valve: 1620
- Monitor
- Interlock policy
 - Voting scheme: Close Valve
 - Closed state of NO Contact: OK



Control System and sub-system: Vacuum CS

Example of HEPS' vacuum CS




Instance of HEPS' Vacuum CS


Control system and sub-system: TM

Temperature Monitoring(TM)

- Quantity: 100,000+(Vacuum devices)
- ADAM4015/6015, Temperature paperless recorder
- Others:



- Power Supply control system (PSCS)
 - Accelerate from 30GeV to 120GeV (Linac to Booster ring)
 - Magnets' power supply co-ramping within an accuracy of tens of μs



ASOL22 Open

Redundant IOCs for PSCS – (DPSCM)



Instance of HEPS' PSCS

0.0250 A 0.0253 /


LBCV1 Open 0.0250 A

LBO05

LBO06


Control System & sub-system: Cabinet Layout

- Control Cabinet layout of Vacuum CS, PSCS, TM, etc
 - Be close to controlled devices(vacuum controller, power supply and so on)
 - Mainly distributed in 96 sub-tunnels along the ring



Control System and sub-system: Integration

- Integration of subsystems and other systems
 - LLRF, Cryogenic system, Injection/Extraction system etc
 - Detector (Experimental physics), beamline and conventional facility
- The following rules must be followed
 - Agree with standards of CEPC control system
 - Consistent with software (EPICS)
 - Unified hardware



Database Management of CEPC

Parameter Database Magnet Database Lattice and Model Database Log and trouble tracking Management of Cable and device Configuration of Security database

Naming Convention Database MPS and interlock database Management of File Alignment Database Alarm database Etc..

More and more Database will be designed with the progress of the Project

Next Step--EDR

Time deterministic system (Timing system and MPS)

- Build the prototypes
- Deterministic time
- Longest transmission distance
- The application of the state-of-art technologies
 - Video Surveillance System: Robot
 - Communication: 5G/6G (wire cables/optical fibers)
 - Etc
- Optimize the layout of the control local sub-station
 - Balance/compromise: cost, performance and ease of maintenance

Summary

More detailed requirements should be further clarified, with the progress of CEPC project

EPICS: Cooperate closely with EPICS community and company

New technique (IoT/AI/ML, etc) used in control system

Thanks a lot!