



ESS
bilbao



QVS
added value solutions

OC
cadinox®

The final design and manufacturing process for the ESS Monolith Vessel

F. Sordo¹, J. Osoro², I. Arrillaga², A. Andersson⁴, M. Pérez¹, S. Ghatnekar⁴

Consorcio ESS-BILBAO¹, AVS+CADINOX², European Spallation Source ERIC⁴

November 1th, 2023

Table of contents

- 1 Introduction
- 2 Lower and medium Vessel
- 3 Welding to the neutron ports
- 4 Connection Ring
- 5 Head of the vessel
- 6 Conclusions

Introduction

Introduction

ESS project

ESS is an going project to build a 5 MW spallation source in Lund (Sweden) with a total budget $\sim 1800Me$. There is 17 Eu countries that take part in the project. Spain contributes with 3% of the total construction cost.

ESS construction site




ESS-BILBAO Consortium

Role and functions


- ESS-Bilbao is public consortium between Spanish Central Government and regional government of Vase Country region.
- ESS-BILBAO has been nominated as Spanish representing entity for ESS operational phase.
- Staff of 50 scientists & engineers.
- The collaboration between ESS-Bilbao and IFN started on 2009. ESS-bilbao Target division is working at IFN facilities in Madrid.
- On December 2014, ESS-Bilbao was chosen as ESS partner for Monolith Vessel.
- KO meeting held on December 2015.
- **On February 2017, Critical design review for the Lower and medium vessel.**
- Contract for LMV manufacturing awarded on September 2018 to AVS+CADINOX.
- Manufacturing is on going.

Introduction

ESS Monolith Vessel on ESS target station



ESS Target Station





Monolith Vessel

Monolith Vessel

- Helium compatible
- Vacuum compatible
- 40 year life time
- Safety related equipment
- RCC-MR_x N3Rx
- ϕ 6 x 12 m
- 75000 kg mass

Introduction

ESS Monolith Vessel on ESS target station




Lower and medium vessel

Critical design review proposal

Design analysis

The design proposed on CDR (July 2017) was optimized according to several load cases (vacuum, 2 bar overpressure, seismic events ...). The CDR was approved on late 2017 but due to administrative reasons the Call for tender was not published until Summer 2018.

Buckling elastoplastic analysis for a 20 mm predeformed geometry



Manufacturing process

Raw material provided by Outokumpu

The raw material is composed by ~ 45 tonnes of plates with thicknesses from 25 to 90 mm and more than 4 tonnes of filled material for TIG and Submerged arc welding processes. The production takes more 20 weeks an the material was delivery in July 2019.

Raw material and filled material (~ 4 tones) delivery



Plates delivery



Dimensional control

Manufacturing process Lower Vessel

Complex welding process based on submerged arc (121) + TIG (141)

WMAP	WPS	Welding detail according Boiler drawing N053.010.001_SHEET 1-4
WMAP-5078/18-1	100.18	
	Joint design 	
	Welding sequence 	


**WS1-WS4 Submerged arc (121)
WS5 TIG semiautomatic (141)**



Bottom plate welding completed


Manufacturing process Lower Vessel

Complex welding process based on submerged arc (121) + TIG (141)



Manufacturing process Lower Vessel


Complex welding process based on summerged arc (121) + TIG (141)



Lower vessel Frame



Lower body with rear window tack welded




Lower body with front window tack welded

Manufacturing process Lower Vessel

Complex welding process based on submerged arc (121) + TIG (141)

2020-02



Lower part in positioner



Inner view



Manufacturing process Lower Vessel

Complex welding process based on submerged arc (121) + TIG (141)



Lower part with covers



Supports for dimensional control to be moved




Pressure and vacuum test

Vacuum test held on *May 15th*, 2020



Leak rate: $6.6\text{E-}9 \text{ mbar l s}^{-1}$
 Vac. Level: $1\text{E-}6 \text{ mbar}$



Final machining



Windows final machined extended for 2 months





Dimensional Control (ESS metrology team post process)

Final dimensional control

3 – Neutron Windows: Front side



Nominal to Actuals in
[DS1]



Welding to the neutron ports


Welding to the neutron ports

Scope of the work

The LMV has to be welded to the port blocks. The ports are ESS scope (design and manufacturing). ESS awarded the contract for manufacturing to Ensa and Asturfeito. The ports are laser welded and machined thus, extremely good tolerances after alignment are expected. ESS Bilbao was responsible of the welding between the vessel and the ports.


Welding to the neutron ports

Neutron ports (ESS scope)



Welding to the neutron ports

Requirements



Welding to the neutron ports

Welding plan






Fig. 20 – Complete weld of remaining Port Tubes.

Manual TIG (141) in 4 layers
–8 mm thickness

VALUES FOR DIMENSION "A" (mm)	
CONDITION	"A" VALUE
POST-WELD	8 ± 3 (THEORETICAL DIMENSION)
AFTER TACK-WELDING	40 MIN (REFERENCE DIMENSION)
AFTER ASSEMBLY	0 ± 0.5 MAX.



- Tack weld 20-30 mm
- Spacer blocks 20-30 mm.

12 SECTORS 100-150mm

Welding to the neutron ports

Modifications of the welding scheme on site



Welding to the neutron ports

Dimensional control during welding

N6 PT11


PORTTUBE INSTALLATION MONITORING

Porttube Position N6

Identification **#11-Type B**

Dimensional monitoring according to 020-2424394
 ESS activity on root face, actual activity on clear face

performed	
Arrived at site	2021/09/06
Released for installation	2021/09/16
Lifted to Microturb	2021/10/08
Aligned	2021/10/13



Dimensional monitoring before Tack-weld	Value	[Go]	[Stop]	
Dimension #01a	2021/10/13 1.10	2.75	2.75	Mandatory
Dimension #01b	2021/10/13 0.76	1.75	1.75	Mandatory
Dimension #02	2021/10/13 0.51	1.75	1.75	Mandatory
Dimension #03	2021/10/13 -1.50	0.00	0.00	Mandatory
Dimension #04	2021/10/13 11.54	15.50	17.00	Mandatory

X-direction Gauge	2021/10/15	Pass
Y/Z direction Gauge	2021/10/15	Pass

Tackweld	2021/10/15	
Y/Z direction Gauge	yyy-mm-dd	Pass/All


Dimensional monitoring after Tack-weld	Value	[Go]	[Stop]		Change
Dimension #01a	2021/10/20 1.45	2.85	2.85	If selected	-0.35
Dimension #01b	2021/10/20 0.94	1.80	1.80	If selected	-0.18
Dimension #02	2021/10/20 0.78	1.85	1.85	If selected	-0.27
Dimension #03	2021/10/20 0.85	1.00	1.00	If selected	1.73
Dimension #04	2021/10/20 12.88	15.50	17.00	If selected	-0.84

Root-weld	2021/11/16	
VT Root-weld	yyy-mm-dd	Pass/All
PT Root Weld	yyy-mm-dd	Pass/All
Section Gauge inspection	yyy-mm-dd	Pass/All

Dimensional monitoring after root weld	Value	[Go]	[Stop]		Total Change	from tack change
Dimension #01a	yyy-mm-dd 1.00	2.95	2.95	If selected	0.10	-0.45
Dimension #01b	yyy-mm-dd 0.97	1.95	1.95	If selected	0.21	-0.03
Dimension #02	yyy-mm-dd 0.94	2.00	2.00	If selected	0.63	-0.16
Dimension #03	yyy-mm-dd 1.22	4.30	4.30	If selected	2.52	0.77
Dimension #04	yyy-mm-dd 12.58	-	-	If selected	1.04	-0.20


Deviation after root weld
 Dim #1a #1b #2

Note: White vectors after tack weld



Deviation after root weld
 Dim #4

Note: White vectors after tack weld



Connection Ring





Connection Ring

Design considerations




The CR is the section of the monolith vessel prepared to include all the connections of the in vessel equipment (> 100). To minimize the deformation produced by the nozzle welding, we introduce Nozzle thickness transitions to reduce the welding volume.

Lessons learned on the LMV applied to CR

Equivalent Stress
Type: Equivalent (von-Mises) Stress
Unit: MPa




Manufacturing review




Connection Ring

Manufacturing process completed on May 2023



Connection Ring

Pressure test, leak test and metrology completed on June-July 2022




Head of the vessel

Head of the Vessel

HoV design completed and manufacturing on going

The HoV is based on stainless steel vessel and carbon steel ribs. It also includes two beams decoupled from vacuum structure to avoid target movement when vacuum is made in the monolith vessel. Also includes a layer of 25 cm of “borated concrete” to provide neutron shielding.

HoV design completed and manufacturing on going





Head of the Vessel

HoV design completed and manufacturing on going

The HoV is based on stainless steel vessel and carbon steel ribs. It also includes two beams decoupled from vacuum structure to avoid target movement when vacuum is made in the monolith vessel. Also includes a layer of 25 cm of “borated concrete” to provide neutron shielding.

HoV design completed and manufacturing on going



Head of the Vessel


Pressure test, leak test and metrology completed on June-July 2022



Head of the Vessel

Pressure test, leak test and metrology completed on June-July 2022

Carbon steel ribs assembly Q1 2023



Borated concrete installation Auguts 2023



Head of the Vessel

Pressure test, leak test and metrology completed on June-July 2022



Conclusions

Conclusions

Main remarks

- LMV manufacturing, FAT and SAT completed on 2020.
- Welding of the LMV to the neutron ports completed on 2022
- CR and HoV manufacturing, FAT and SAT completed on 2022
- HoV manufacturing completed, FAT and SAT schedule for Q4 2023