

# CEPC Accelerator from TRD to EDR

Jie Gao

IHEP



On behalf of the CEPC accelerator group

14th France China Particle Physics Laboratory Workshop  
Nov. 6-10, 2023, Zhuhai, China



# Contents

---

- **Introduction**
- **CEPC accelerator system design and optimizations in TDR**
- **CEPC accelerator key hardware R&D progresses in TDR**
- **SppC compatibility with CEPC**
- **CEPC site preparations and civil engineering**
- **CEPC accelerator TDR review (+cost) and IAC meeting**
- **CEPC EDR goals, plans and scope**
- **CEPC industrial preparation and international collaboration**
- **Summary**



# Physics Goals of CEPC-SppC

## • Circular Electron-Positron Collider (CEPC) as a Higgs Factory (91, 160, 240, 360 GeV)

### – Higgs Factory ( $>10^6$ Higgs) :

- Precision study of Higgs( $m_H$ , JPC, couplings), Similar & complementary to ILC
- Looking for hints of new physics, DM...

### – Z & W factory ( $>10^{10}$ Z0) :

- precision test of SM
- Rare decays ?

### – Flavor factory: b, c, t and QCD studies

## • Super proton-proton Collider(SppC) (~100 TeV)

### – Directly search for new physics beyond SM


### – Precision test of SM

- e.g.,  $h_3$  &  $h_4$  couplings


**Precision measurement + searches for new physics:**

**Complementary with each other !**

CEPC-SppC was proposed by Chinese scientists in Sept. 2012 after Higgs Boson was discovered on July 4, 2012 at CERN



Cross sections for major SM physics processes at the electron positron collider



Anticipated accuracy on Higgs properties at CEPC and at LHC/HL-LHC



# CEPC Operation Plan

Particle	$E_{c.m.}$ (GeV)	Years	SR Power (MW)	Lumi. per IP ( $10^{34}cm^{-2}s^{-1}$ )	Integrated Lumi. per year ( $ab^{-1}$ , 2 IPs)	Total Integrated L ( $ab^{-1}$ , 2 IPs)	Total no. of events
$H^*$	240	10	50	8.3	2.2	21.6	$4.3 \times 10^6$
			30	5	1.3	13	$2.6 \times 10^6$
Z	91	2	50	192**	50	100	$4.1 \times 10^{12}$
			30	115**	30	60	$2.5 \times 10^{12}$
W	160	1	50	26.7	6.9	6.9	$2.1 \times 10^8$
			30	16	4.2	4.2	$1.3 \times 10^8$
$t\bar{t}$	360	5	50	0.8	0.2	1.0	$0.6 \times 10^6$
			30	0.5	0.13	0.65	$0.4 \times 10^6$


\* Higgs is the top priority. The CEPC will commence its operation with a focus on Higgs.

\*\* Detector solenoid field is 2 Tesla during Z operation, 3Tesla for all other energies.


\*\*\* Calculated using 3,600 hours per year for data collection.

# CEPC Higgs Factory and SppC in TDR (EDR)

CEPC as a Higgs Factory: **H, W, Z**, upgradable to **tt-bar**, followed by a SppC (a Hadron collider)  $\sim 125\text{TeV}$   
 30MW SR power per beam (upgradable to 50MW), high energy gamma ray 100Kev $\sim$ 100MeV






CEPC collider ring (100km)




CEPC booster ring (100km)

## CEPC TDR S+C-band 30GeV linac injector



CEPC Civil Engineering



# CEPC TDR Accelerator System Parameters

## Linac

Parameter	Symbol	Unit	Baseline
Energy	$E_e/E_{e+}$	GeV	<b>30</b>
Repetition rate	$f_{rep}$	Hz	100
Bunch number per pulse			1 or 2
Bunch charge		nC	1.5 (3)
Energy spread	$\sigma_E$		$1.5 \times 10^{-3}$
Emittance	$\varepsilon_r$	nm	6.5


## Booster

		<i>tt</i>		<i>H</i>		<i>W</i>		<i>Z</i>	
		Off axis injection	Off axis injection	On axis injection	Off axis injection	Off axis injection			
Circumfer.	km	<b>100</b>							
Injection energy	GeV	<b>30</b>							
Extraction energy	GeV	<b>180</b>	<b>120</b>		<b>80</b>	<b>45.5</b>			
Bunch number		35	268	261+7	1297	3978	5967		
Maximum bunch charge	nC	0.99	0.7	20.3	0.73	0.8	0.81		
Beam current	mA	0.11	0.94	0.98	2.85	9.5	14.4		
SR power	MW	0.93	0.94	1.66	0.94	0.323	0.49		
Emittance	nm	2.83	1.26		0.56	0.19			
RF frequency	GHz	1.3							
RF voltage	GV	9.7	2.17		0.87	0.46			
Full injection from empty	h	0.1	0.14	0.16	0.27	1.8	0.8		

## Collider

	Higgs	Z	W	<i>t</i> $\bar{t}$
Number of IPs	2			
Circumference (km)	<b>100.0</b>			
SR power per beam (MW)	<b>30</b>			
Energy (GeV)	<b>120</b>	<b>45.5</b>	<b>80</b>	<b>180</b>
Bunch number	268	11934	1297	35
Emittance $\varepsilon_x/\varepsilon_y$ (nm/pm)	0.64/1.3	0.27/1.4	0.87/1.7	1.4/4.7
Beam size at IP $\sigma_x/\sigma_y$ (um/nm)	14/36	6/35	13/42	39/113
Bunch length (natural/total) (mm)	2.3/4.1	2.5/8.7	2.5/4.9	2.2/2.9
Beam-beam parameters $\xi_x/\xi_y$	0.015/0.11	0.004/0.127	0.012/0.113	0.071/0.1
RF frequency (MHz)	650			
Luminosity per IP ( $10^{34} \text{ cm}^{-2} \text{ s}^{-1}$ )	<b>5.0</b>	<b>115</b>	<b>16</b>	<b>0.5</b>

## Transport line



# CEPC Collider Ring Daynamic Apertures

Dynamic apertures with errors at Higgs, W/Z and ttbar energies satisfy design goals

## Effects included in tracking

Synchrotron motion

Radiation loss in all magnets






Tapering

Crab waist sextupole

Maxwellian fringes

Kinematic terms

Finite length of sextupole




Component	$\Delta x$ (mm)	$\Delta y$ (mm)	$\Delta\theta_z$ (mrad)	Field error
Dipole	0.10	0.10	0.10	0.01%
Arc Quadrupole	0.10	0.10	0.10	0.02%
IR Quadrupole	0.10	0.10	0.10	0.02%
Sextupole	0.10*	0.10*	0.10	0.02%

- w/o error
- mean value
- statistic errors
- seeds
- requirement




# Studies of Beam-Beam Effects in CEPC

## Luminosity simulations w/ZL



## Transverse size simulations



Beam-beam simulation results are **consistent** with the TDR parameter tables.

- **Luminosity & Lifetime** is evaluated by strong-strong simulation
- **X-Z instability** is well suppressed even considering Potential Well Distortion
- **Lifetime optimization** with both beam-beam/lattice nonlinearity is done






# Parameters of CEPC Booster

Injection		<i>tt</i>	<i>H</i>	<i>W</i>	<i>Z</i>	
Beam energy	GeV	30				
Bunch number		35	268	1297	3978	5967
Bunch charge	nC	1.1	0.78	0.81	0.87	0.9
Single bunch current	μA	3.4	2.3	2.4	2.65	2.69
Beam current	mA	0.12	0.62	3.1	10.5	16.0
Energy spread	%	0.025				
Synchrotron radiation loss/turn	MeV	6.5				
Momentum compaction factor	10 <sup>-5</sup>	1.12				
Emittance	nm	0.076				
Natural chromaticity	H/V	-372/-269				
RF voltage	MV	761.0	346.0	300.0		
Betatron tune $\nu_x/\nu_y$		321.23/117.18				
Longitudinal tune		0.14	0.0943	0.0879		
RF energy acceptance	%	5.7	3.8	3.6		
Damping time	s	3.1				
Bunch length of linac beam	mm	0.4				
Energy spread of linac beam	%	0.15				
Emittance of linac beam	nm	6.5				




Extraction		<i>tt</i>	<i>H</i>		<i>W</i>	<i>Z</i>	
		Off axis injection	Off axis injection	On axis injection	Off axis injection	Off axis injection	
Beam energy	GeV	180	120		80	45.5	
Bunch number		35	268	261+7	1297	3978	5967
Maximum bunch charge	nC	0.99	0.7	20.3	0.73	0.8	0.81
Maximum single bunch current	μA	3.0	2.1	61.2	2.2	2.4	2.42
Beam current	mA	0.11	0.56	0.98	2.85	9.5	14.4
Bunches per pulse of Linac		1	1		1	2	
Time for ramping up	s	7.1	4.3		2.4	1.0	
Injection duration for top-up (Both beams)	s	29.2	23.1	31.8	38.1	132.4	
Current decay in Collider		3%					
Energy spread	%	0.15	0.099		0.066	0.037	
Synchrotron radiation loss/turn	GeV	8.45	1.69		0.33	0.034	
Emittance	nm	2.83	1.26		0.56	0.19	
Betatron tune $\nu_x/\nu_y$		321.27/117.19					
RF voltage	GV	9.7	2.17		0.87	0.46	
Longitudinal tune		0.14	0.0943		0.0879		
RF energy acceptance	%	1.78	1.59		2.6	3.4	
Damping time	ms	14.2	47.6		160.8	879	
Natural bunch length	mm	1.8	1.85		1.3	0.75	
Full injection from empty ring	h	0.1	0.14	0.16	0.27	1.8	0.8



# CEPC Booster Design



- TME like structure (cell length=78m)
- Interleave sextupole scheme
- Emittance@120GeV=1.26nm



- 30 GeV injection energy, Maximum extraction energy @ 180GeV
- Lattice design with TME structure, lower emittance than CDR
- Sufficient Dynamic Aperture for all energies with errors

# CEPC SRF System Design and Upgrade Plan


## Collider 650MHz Parameters

	ttbar 30/50 MW		Higgs 30/50 MW	W 30/50 MW	Z 30/50 MW
	New cavities	Higgs cavities			
Luminosity / IP [ $10^{34} \text{ cm}^{-2} \text{ s}^{-1}$ ]	0.5 / 0.8		5 / 8.3	16 / 26.7	115 / 192
RF voltage [GV]	10 (6.1 + 3.9)		2.2	0.7	0.12 / 0.1
Beam current / beam [mA]	3.4 / 5.6		16.7 / 27.8	84 / 140	801 / 1345
Bunch charge [nC]	32		21	21.6	22.4 / 34.2
Bunch length [mm]	2.9		4.1	4.9	8.7 / 10.6
650 MHz cavity number	192	336	192/336	96 / 168 / ring	30 / 50 / ring
Cell number / cavity	5	2	2	2	1
Gradient [MV/m]	27.6	25.2	24.9 / 14.2	15.9 / 9.1	17.4 / 8.7
$Q_0$ @ 2 K at operating gradient	3E10	3E10	3E10	3E10	2E10
HOM power / cavity [kW]	0.4 / 0.68	0.16 / 0.26	0.4 / 0.67	0.93 / 1.54	2.9 / 6.2
Input power / cavity [kW]	188 / 315	71 / 118	313 / 298	313 / 298	1000
Optimal $Q_0$	1E7 / 8E8	9E6 / 5.4E6	1.6E6 / 9.5E5	8E5 / 2.7E5	1.5E5 / 3.8E4
Optimal detuning [kHz]	0.01 / 0.02	0.02 / 0.03	0.1 / 0.2	0.7 / 2	6.7 / 21.7
Cavity number / klystron	4 / 2	2	2	2	1
Klystron power [kW]	800	800	800	800	1200
Klystron number	48 / 96	168	96 / 168	96 / 168	60 / 100
Cavity number / cryomodule	4	6	6	6	1
Cryomodule number	48	56	32 / 56	32 / 56	60 / 100
Total cavity wall loss @ 2 K [kW]	12.1	7.1	3.9 / 2.3	1.6 / 0.9	0.45 / 0.2


## Booster 1.3GHz Parameters

	ttbar 30/50 MW		Higgs 30/50 MW	W 30/50 MW	Z 30/50 MW
	New cavities	Higgs cavities			
Extraction beam energy [GeV]	180		120	80	45.5
Extraction average SR power [MW]	0.05		0.5 / 0.67	0.02 / 0.04	0.05 / 0.1
Bunch charge [nC]	1.1		0.78 (20.3)	0.73	0.81
Beam current [mA]	0.12 / 0.19		0.63 (1) / 1 (1.4)	3.1 / 5.3	16 / 30
Injection RF voltage [GV]	0.761		0.346	0.3	0.3
Extraction RF voltage [GV]	9.7 (7.53 + 2.17)		2.17	0.87	0.46
Extraction bunch length [mm]	1.8		1.86	1.3	0.75
Cavity number (1.3 GHz 9-cell)	256	96	96	96	32
Module number (8 cavities / module)	32	12	12	12	4
Extraction gradient [MV/m]	28.3	21.8	21.8	8.7	13.8
$Q_0$ @ 2 K at operating gradient	2E10	3E10	3E10	3E10	3E10
$Q_0$	4E7	4E7	1.2E7	7.3E6 / 4.4E6	1.2E7 / 6.3E6
Cavity bandwidth [Hz]	33	33	110	178 / 296	111 / 208
Peak HOM power per cavity [W]	0.5 / 0.8		~ 75 / ~ 100	11.8 / 19.6	148 / 272
Average HOM power per cavity [W]	0.2 / 0.32		~ 10 / ~ 15	3.8 / 6.3	80 / 150
Input peak power per cavity [kW]	8.3 / 9.2	5.1 / 5.9	22 / 32	10.9 / 18.1	17 / 32
Input average power per cavity [kW]	0.3	0.2	6.5 / 9.2	0.3 / 0.5	2.5 / 4.5
SSA power [kW] (1 GHz)	25	25	25 / 30	25 / 30	25 / 40
Total cavity wall loss @ 2 K [kW]	0.36	0.05	0.5	0.02	0.08

## H/W/Z/ttbar bypass scheme



## SRF power supply auxiliary tunnel




- CEPC TDR SRF layout and parameters are designed to **meet physics requirements**;
- RF system design optimized for Higgs 30/50 MW. Power and energy upgrade by adding cavities, RF power sources and cryogenic plants and other systems are compatible;
- Use dedicated high current 1-cell cavity for 10-50 MW Z. Solve the FM & HOM CBI problems.



# CEPC MDI Design



MDI Layout



General Parameters

Parameter	Value	Length	Beam stay clear region	Min. distance between apertures	Beam pipe inner diameter	Beam pipe outer diameter	Critical energy (Hor.)	Critical energy (Vert.)	SR power (Hor.)	SR power (Vert.)
L*	0~1.9m	1.9m								
Crossing angle	33mrad									
MDI length	±7m									
Acc. components in opening angle	8.11°									
QDa/QDb	3.5/1.8T 142/85T/m	1.21m	14.9/18.2mm	62.71/105.2mm	20/23mm	26/29mm	724.7/663.1keV	396.3/263keV	212.2/239.23W	99.9/42.8W
QF1	3.3T 96.7T/m	1.5m	24.48mm	155.11mm	32mm	38mm	575.2keV	489.4keV	472.9W	135.1W
Lumical	0.65~1.11m	0.16m								
Anti-solenoid before QD0	8.6T	1.1m								
Anti-solenoid QD0	3T	2.5m								
Anti-solenoid QF1	3T	1.5m								
Beryllium pipe		±85mm			20mm					
Last B upstream	64.9°-153.5m	0.77mrad	88.5m				33.3keV			
First B downstream	44.4°-102m	1.17mrad	57.6m				77.9keV			
Beam pipe within QDa/QDb		1.21m							1.19/1.3W	
Beam pipe within QF1										


SR Calculation




2023-Nov.-10 J. Gao

Radiation background

Radiative barrier, Beam-Gas, beam thermal photon scattering




Injection background




The 2023 FCPPL, Zhuhai, China

Radiation Mitigation Masks, collimators, shielding






# CEPC Electron and Positron Injection Linac Designs




Parameter	Symbol	Unit	Design value
Energy	$E$	GeV	30
Repetition rate	$f_{rep}$	Hz	100
Number of bunches per pulse			1 or 2
Bunch charge		nC	1.5
Energy spread	$\sigma_E$		$1.5 \times 10^{-3}$
Emittance	$\epsilon_r$	nm	6.5
Electron energy at target		GeV	4
Electron bunch charge at target		nC	10
Tunnel length	$L$	m	1800


e- in linac



e+ in linac




Phase space @ SAS exit





- Linac energy increases to 30 GeV, with S+C band Accelerator;
- Start-to-end simulations were conducted for both electron/positron beams, with quality satisfying requirements.

# CEPC Polarized Beam Studies(alternative option)



## Spin rotator design

solenoids: 240 T m,  $L_{sol} = 40m @ 6T$




## Key issues of study:

- Energy calibration in collider ring with transverse polarization (self polarization & inj. polarization)
- Longitudinal polarization for collision
- Polarization beam injection, positron polarization and ramping in booster

# CEPC Plasma Injector (alternative option) and TF Plan


CEPC injector's baseline was changed:  
 10 GeV  $\rightarrow$  30 GeV  $\rightarrow$  **TR  $\geq 2$**



CEPC IARC, 2022.06


Parameters	Driver	Trailer
plasma density $n_p (\times 10^{16} cm^{-3})$	0.50334	
Driver energy $E(GeV)$	12	12
Normalized emittance $\epsilon_N (\mu m rad)$	20	10
Length $L (\mu m)$	350	90
(matched) Spot size $\sigma_r (\mu m)$	3.72	2.63
Charge $Q$ (nC)	4.0	1.2
Beam distance $d (\mu m)$	155	

Parameters	Trailer
Accelerating distance (m)	7.3 (97300 $w_p^{-1}$ )
Trailer energy $E(GeV)$	<b>30</b>
Normalized emittance $\epsilon_n (mm mrad)$	10
Charge(nC)	<b>1.2</b>
Energy spread $\delta_E (\%)$	<b>0.58</b>
R	1.8
Efficiency(%) (driver $\rightarrow$ trailer)	55





# CEPC Key Technology R&D



Key technology R&D spans all component lists in CEPC TDR





# CEPC SRF Facilities and Components




Mid-T (medium temperature furnace baked) cavities have higher gradient and Q than Nitrogen doped cavities with **less EP process (1 vs 3)**

IHEP PAPS is in full operation since 2021


CEPC 650 MHz 2-cell Cavity

CEPC 650 MHz 1-cell Cavity

1.3 GHz High Q Mid-T Cavity Horizontal Test




3E10@20MV/m.




High G High Q 650 MHz 1-cell Cavity

EP treated: **2.3E10@41.6 MV/m@2 K**  
 Mid-T treated: **6.3E10@31 MV/m@2 K**



Mid-T 1.3 GHz 9-cell vertical test  
 avg. **4.3E10@ 31 MV/m**




Mid-T 1.3 GHz 9-cell horizontal test (SEL)  
 3.1E10@21 MV/m, avg. **24.6 MV/m**



# CEPC Collider 650 MHz 2 x 2-cell Test Cryomodule



- DC photo-cathode gun voltage conditioned up to 400 kV
- Cavity frequency, HOM coupler double notch filter, tuner, vacuum, cryogenics perform well
- Cavity magnetic field at 2 K  $< 2$  mG (large beam pipe North to South)
- **LLRF system commissioning and high power test ongoing**
  - Optimizing the outer conductor helium gas cooling of the input coupler. Cavity early quench if with poor coupler cooling.





- Module automatic cool-down experiment**
1. 300 to 150 K:  $< 10$  K/hr. Cavity top and bottom  $\Delta T < 20$  K
  2. 150 to 4.5 K: Cavity surface  $> 1$  K/min
  3. 4.5 to 2 K



# CEPC Booster 1.3 GHz 8 x 9-cell High Q Cryomodule

CEPC booster 1.3 GHz SRF R&D and industrialization in synergy with CW FEL projects.

Parameters	Horizontal test results	CEPC Booster Higgs Spec	LCLS-II, SHINE Spec	LCLS-II-HE Spec
Average usable CW $E_{acc}$ (MV/m)	23.1	$3.0 \times 10^{10}$ @ 21.8 MV/m	$2.7 \times 10^{10}$ @ 16 MV/m	$2.7 \times 10^{10}$ @ 20.8 MV/m
Average $Q_0$ @ 21.8 MV/m	$3.4 \times 10^{10}$			





# CEPC High Efficiency High Power Klystron Development and RF Power Distribution


## Klystron R&D



Klystron No. 1  
Efficiency 65%  
(2020)




Klystron No. 2  
Efficiency 77%  
(2021)




Klystron No. 3 (MB)  
Efficiency 80.5%  
(under fabrication)

## Power Step Module







Pulsed RF Mode (30% duty factor, 60ms/5Hz)

High Voltage vs. Power&Efficiency



70.5% @ 630kW


2022



- Three prototypes of the 650MHz 800KW CW klystrons are developed. The efficiency reaches 70%
- PSM is developed with the industrial collaboration
- RF tunnel distribution was planed

# CEPC Collider Ring Full-scale Dual-aperture Magnets


Full-length 5.67m Dual aperture dipole



High harmonics @120GeV (units:1e-4)

n	bn_A	bn_B
2	0	0
3	3.92	3.88
4	1.03	-1.22
5	0.47	0.54
6	0.08	-0.46




Dual aperture QUAD



E(GeV)	GL(T)-A	GL(T)-B	difference
45	-3.36	3.35	0.40%
80	-5.91	5.88	<b>0.59%</b>
120	-8.89	8.85	0.49%
148	-10.93	10.89	0.40%
175	-12.77	12.73	0.30%
182.5	13.27	13.21	0.40%

Two apertures differ <0.1%, transfer function in two apertures are consistent.


High harmonics are nearly the same at four energies and all less than 5 units, which can meet the requirements.



- **Large quantities of dual-aperture dipoles (69km) and quad. (10km) are required;**
- **Full length dual-aperture dipole and dual aperture QUAD (short length) have been fabricated, under test;**
- **Dipole/QUAD prototypes meet the requirements.**

# CEPC Full-scale Weak Field Dipole for Booster

Magnet name	BST-63B-Arc	BST-63B-Arc-SF	BST-63B-Arc-SD	BST-63B-IR
Quantity	10192	2017	2017	640
Aperture [mm]	63	63	63	63
Dipole Field [Gs] @180 GeV	564	564	564	549
Dipole Field [Gs] @120 GeV	376	376	376	366
Dipole Field [Gs] @30 GeV	95	95	95	93
Sextupole Field [T/m <sup>2</sup> ] @180 GeV	0	16.0388	19.1423	0
Sextupole Field [T/m <sup>2</sup> ] @120 GeV	0	10.6925	12.7615	0
Sextupole Field [T/m <sup>2</sup> ] @30 GeV	0	2.67315	3.19035	0
Magnetic length [mm]	4700	4700	4700	2350
GFR [mm]	±22.5	±22.5	±22.5	±22.5
Field errors	±1×10 <sup>-3</sup>	±1×10 <sup>-3</sup>	±1×10 <sup>-3</sup>	±1×10 <sup>-3</sup>





- Booster requires **~19k** pieces of magnets (**68km**);
- Booster dipoles are required to work at the low field of **95 Gs** (**30GeV**) with an error smaller than **1 × 10<sup>-3</sup>** ;
- Full length (4.7m) dipole was developed, and it meets the field specification;





# CEPC Final Focus Superconducting Quadrupoles

SCQ Specifications	Q1a	Q1b	Q2	
Field gradient	142.3	85.4	96.7	T/m
Magnetic length	1210	1210	1500	mm
Reference radius	7.46	9.085	12.24	mm
Mini. distance between aperture center	62.71	105.28	155.11	mm
High order field harmonics	$\leq 5 \times 10^{-4}$	$\leq 5 \times 10^{-4}$	$\leq 5 \times 10^{-4}$	
Dipole field	$\leq 3$	$\leq 3$	$\leq 3$	mT



- CCT and Cos2θ type SCQs were modeled, and their fields were calculated; the CEPC specifications have been met;
- A 0.5-m single aperture SCQ using Cos2θ technology has been developed. The electro-magnet excitation test showed the highest current reached 2500A (176 T/m), which exceeds the CEPC requirement (142T/m)




2023 Nov 10 J. Gao



# CEPC Vacuum System

New round pipe of Copper (3mm) with NEG coating (200nm) for collider ring in TDR  
SEY<1.2




6 m vacuum pipe have been installed on the NEG coating setup

- ✓ 180°C/24h activation  $4.5 \times 10^{-10}$  Torr
- ✓ 200°C/24h activation  $2.5 \times 10^{-10}$  Torr




Vacuum pipes and RF shielding bellows



Vacuum chamber prototypes, copper & aluminum, with different shape/length were fabricated;

- NEG coating technology were developed;
- RF shielding bellow manufactured
- Vacuum technology applied and was tested at HEPS







Facility of pumping speed test have been finished in Dongguan



# CEPC Linac Injector Key Technology R&D

- ◆ Flux concentrator for positron source
- ◆ RF pulse compressor
- ◆ High perform. S/C-band Acc. Struc.



R&D of the solid state      Test result of the peak



IHEP C-band SLED




Test results of IHEP C-band SLED



SACLAL C-band SLED



IHEP C-band BOC




PSI BOC

- Positron pulsed magnetic field of 6 T to 0.5 T
- 15kA/15kV/50Hz solid state pulse source



2023-Nov.-10 J. Gao



The 2023 FCPPL, Zhuhai, China



High power test bench



The input power with SLED



# Power Consumption of CEPC - Higgs

SN	System	Higgs 30MW							Higgs 50MW						
		Collider	Booster	Linac	BTL	IR	Surface building	Total	Collider	Booster	Linac	BTL	IR	Surface building	Total
1	RF Power Source	96.90	1.40	11.10				109.40	161.60	1.73	14.10				177.40
2	Cryogenic system	9.72	1.71			0.14		11.57	9.17	1.77			0.14		11.08
3	Vacuum System	5.40	4.20	0.60				10.20	5.40	4.20	0.60				10.20
4	Magnet Power Supplies	44.50	9.80	2.50	1.10	0.30		58.20	44.50	9.80	2.50	1.10	0.30		58.20
5	Instrumentation	1.30	0.70	0.20				2.20	1.30	0.70	0.20				2.20
6	Radiation Protection	0.30		0.10				0.40	0.30		0.10				0.40
7	Control System	1.00	0.60	0.20				1.80	1.00	0.60	0.20				1.00
8	Experimental devices					4.00		4.00					4.00		4.00
9	Utilities	37.80	3.20	1.80	0.60	1.20		44.60	46.40	3.80	2.50	0.60	1.20		54.50
10	General services	7.20		0.30	0.20	0.20	12.00	19.90	7.20		0.30	0.20	0.20	12.00	19.90
	<b>Total</b>	204.12	21.61	16.80	1.90	5.84	12.00	<b>262.27</b>	276.87	22.60	20.50	1.90	5.84	12.00	<b>339.71</b>



# SppC Collider Parameters in TDR

-Parameter list (updated Feb. 2022)


## Main parameters

Circumference	100	km
Beam energy	62.5	TeV
Lorentz gamma	66631	
Dipole field	20.00	T
Dipole curvature radius	10415.4	m
Arc filling factor	0.780	
Total dipole magnet length	65442.0	m
Arc length	83900	m
Total straight section length	16100	m
Energy gain factor in collider rings	19.53	
Injection energy	3.20	TeV
Number of IPs	2	
Revolution frequency	3.00	kHz
Revolution period	333.3	$\mu$ s


## Physics performance and beam parameters

Initial luminosity per IP	4.3E+34	$\text{cm}^{-2} \text{s}^{-1}$
Beta function at initial collision	0.5	m
Circulating beam current	0.19	A
Nominal beam-beam tune shift limit per	0.015	
Bunch separation	25	ns
Bunch filling factor	0.756	
Number of bunches	10080	
Bunch population	4.0E+10	
Accumulated particles per beam	4.0E+14	


## Lattice of SPPC




Whole ring



Collimation



IP



Dynamic Aperture

**Ecm=125TeV  
with dipole  
field of 20T**





# SppC HF Magnet Development

**16 T Model Dipole: Nb<sub>3</sub>Sn 12~13 T + HTS 3~4 T; To be tested in Sep-Dec 2023**



Picture of LPF1-U



Dual aperture superconducting dipole achieves 12.47 T at 4.2 K  
Entirely fabricated in China. The next step is reaching 16-20T



# CEPC Site Preparations (three examples)



2034

⑧



ject is

48




# CEPC Conventional Facility and Civil Engineering

## Electrical Equipment General Layout in Auxiliary



Cables installed!






# CEPC Accelerator International TDR Review and Cost Review June 12-16, and Sept. 11-15, 2023, in HKUST-IAS, Hong Kong





CEPC Accelerator TDR Review  
June 12-16, 2023



CEPC Accelerator TDR Cost Review  
Sept. 11-15, 2023



Domestic Civil Engineering  
Cost Review, June 26, 2023



CEPC TDR cost distribution

**CEPC accelerator TDR to be released formally soon in 2023**



# CEPC Accelerator TDR International Review Report

## Phase 1 CEPC TDR Review Report

CEPC TDR Technical Review Committee

Chaired by Frank Zimmermann

15 July 2023

### 1 Executive Summary

Five years after the completion of the CDR, the draft TDR for the CEPC accelerator has been prepared. The TDR will be completed taking into account the feedback from this Committee. The key technologies for CEPC have been developed. Prototypes meeting or exceeding the specifications are available. The CEPC team is on track to launch an engineering-design effort. After a site has been selected, the construction of the CEPC could start in 2027 or 2028. The Committee endorses this plan.

The Committee wishes to congratulate the CEPC team on the excellent progress. The Committee is impressed by the amount and quality of the work performed and presented.

The next section provides answers to the different charge questions, the following sections contain comments and recommendations related to the individual presentations.

CEPC Accelerator International TDR Review was held June 12-16, 2023, in HKUST-IAS, Hong Kong

<https://indico.ihep.ac.cn/event/19262/timetable/>





## CEPC Accelerator TDR Cost Review

Chaired by Loinid Rivkin

The CEPC Accelerator TDR Cost Review committee examined the cost estimate of the TDR of accelerator systems for the first stage of the CEPC project operated as a Higgs factory with synchrotron radiation power up to 30 MW per beam (including all infrastructure that is not easily upgradeable and is already designed to operate up to the ttbar energy and at 50 MW). The cost estimate under review does not include the civil engineering, the detectors at the IPs with their technical services, and the central computing services.

In the opinion of the committee the cost estimate presented is sufficiently complete to form a proper basis for the next iteration that will be done during the EDR stage.

The responses to the Charge are set out below, followed by some general observations, and then some specific issues on which we have more to say.

CEPC Accelerator International TDR Cost Review was held Sept. 11-15, 2023, in HKUST-IAS, Hong Kong

<https://indico.ihep.ac.cn/event/19262/timetable/>



# CEPC Engineering Design Report (EDR) Goal

<b>2012.9</b> CEPC proposed	<b>2015.3</b> Pre-CDR	<b>2018.11</b> CDR	<b>2023.10</b> TDR	<b>2027</b> EDR	<b>15<sup>th</sup> five year plan</b> Start of construction
--------------------------------	--------------------------	-----------------------	-----------------------	--------------------	--



## CEPC EDR Phase General Goal: 2024-2027

After completion CEPC accelerator TDR in 2023, CEPC accelerator will enter into the Engineering Design Report (EDR) phase (2024-2027), which is also the preparation phase with the aim for CEPC PROPOSAL to be presented to and selected by Chinese government around 2025 for the construction start during the "15th five year plan (2026-2030)" (for example, around 2027) and completion around 2035 (the end of the 16th five year plan).



# CEPC Accelerator EDR Plan and Scope-1

- (A) Based on the CEPC TDR accelerator design, demonstrate **a complete and coherent feasibility EDR design**, which will guarantee the construction, commissioning, operation, and upgrade possibilities .
- (B) The CEPC EDR accelerator design should guarantee the physics goals with required energies (**Higgs, W and Z pole, with ttbar as upgrade possibility**) and corresponding required luminosities with **30MW** synchrotron radiation power/beam as a baseline, and **50MW** as upgrade possibility.
- (C) Based on the CEPC TDR accelerator key technology R&D achievement, complete the accelerator engineering design and necessary EDR R&D to be **ready for industrial fabrications**.
- (D) Complete a practical **procurement strategy and logistics** with both **domestic** and **international suppliers**.



# CEPC Accelerator EDR Plan and Scope-2

(E) In collaboration with local government, CAS and MOST (central government), CEPC sites converge from several candidates to a **EDR construction site** satisfying the required geological conditions, electric power and water resources, social and environment conditions, domestic and international transportation network conditions, international science city, and sustainable development , etc.

(F) Complete detailed **construction site geological studies** and corresponding site dependent civil engineering design and general utility facility design.

(G) Complete the **radiation, security, environment assessment studies** and necessary documents –so called CEPC PROPOSAL, around 2025 ready for the application to the central government to get the **formal approval of construction in the “15th five year plan”**

(H) Make detailed analysis and preparation for the **human resources** needed for the completion of CEPC construction.



# CEPC Accelerator EDR Plan and Scope-3

- (I) In the Engineering Design Phase, create and maintain a complete database, such as cost items with information regarding technology maturity (TRL), design completeness, and cost basis, to identify and prioritize areas for R&D, prototyping and industrialization.
- (J) Work out a detailed construction time line and plan in relation with industrial fabrications, measurements, transportations, storage warehouses, installation, human resource evolution, etc.
- (K) Workout details on 3% installation and 3% commissioning items of the total accelerator cost.
- (L) Improve design maturity of several systems (particularly MDI and cryogenics) and develop system integration.
- (M) Implement the risk-mitigation plan in the production and procurement plans to eliminate major risk during the mass production, providing multiple vendors and multiple production lines (for example, demonstrate automatic magnets production line and NEG coated vacuum chambers mass production facility ).



# CEPC Accelerator EDR Plan and Scope-4

- (N) Consider re-optimizing the technical design of components and systems with large electricity consumption taking into account both capital and operational expenditure
- (O) Define unambiguously what constitutes the end of the construction project.
- (P) For labour-intensive, high-volume activities, in particular the components of the collider and booster, refine and review the production model to check the availability of in-house resources.
- (Q) Risk assessment and risk management
- (R) Based on TDR cost estimate, make an updated EDR cost estimate.
- (S) Carefully consider the recommendations from CEPC accelerator TDR review and TDR cost review committees, IARC and IAC, etc.
- (T) Continues efforts in green collider and sustainable development with energy saving technologies, waste heat reuse, energy recovery, and green energy utilization, etc.



# CEPC Accelerator EDR Plan and Scope-5

(U) Establish more international collaborations, international involvement, and industrial preparations both from domestic and international companies and suppliers.

(V) Refine the CEPC management structure in relation with host lab.

(W) Refine the CEPC construction funding modes.

(X) Obtain the necessary EDR plan and scope related fundings.

(Y) Complete “CEPC Proposal” around 2025 ready for application of final selection of the 15th 5-year plan, and complete EDR around 2027 before the construction.

(Z) With aim of start the construction around 2027~2028 and complete the construction and put CEPC in to commissioning around 2035.

The total CEPC EDR funding requirement (including site selection, civil engineering design, accelerator, detector, computing, management, etc. is about **1Billion RMB**.

According to the CEPC EDR general goal and CEPC Accelerator EDR plan and scope (**A to Z**) described above, CEPC accelerator key subsystems working plans and goals (2024 - 2027), each year **to do list** (items) and **deliverables, milestones**, etc. are briefly described in the breakdown **35 WGs with a detailed working plan of a document of 20 pages**.



# CEPC EDR Goal, Plan and Scope

## CEPC Accelerator EDR Phase Working Plan (preliminary) 2024 - 2027 (Oct. 16, 2024 draft)

### CEPC EDR general goals:

According to the general CEPC plan, CEPC Conceptual Design Report (CDR) was completed in Nov. 2018, after the completion of CEPC accelerator TOR in 2023. CEPC accelerator will enter into the Engineering Design Report (EDR) phase (2024-2027), which is also the preparation phase with the aim for CEPC to be presented to and selected by Chinese government for the construction start during the "15th five year plan" (under way).  
-Work closely with CAS and MOST and to prepare CEPC to be put in the "15th five year plan" (under way).  
-Work closely with local governments towards a construction site (under way).  
-Work closely with local government, CAI and MOST on EDR-related funds (under way).

### CEPC Accelerator EDR Plan and Scope:

According to the general CEPC plan, CEPC Conceptual Design Report (CDR) was completed in Nov. 2018, and the CEPC accelerator Technical Design Report (TDR) will be formally released in 2026 after international review(s) (including a CEPC accelerator cost review). Therefore, CEPC accelerator will enter into the EDR phase (2024-2027), which is also the preparation phase with the aim for CEPC to be presented to and selected by Chinese government for the construction start during the "15th five year plan" (under way).  
-Work closely with local governments towards a construction site (under way).  
-Work closely with local government, CAI and MOST on EDR-related funds (under way).


- (A) Based on the CEPC TDR accelerator design, demonstrate a complete and coherent feasibility EDR design, which will guarantee the construction, commissioning, operation, and upgrade possibilities.
- (B) The CEPC EDR accelerator design should guarantee the project goals with required energies (pulsed, W and 2 pole, with 110m in upgrade possibility) and corresponding required luminosities with 30MW synchrotron radiation power/beam as a baseline and 50MW as upgrade possibility.
- (C) Based on the CEPC TDR accelerator key technology R&D achievement, complete the accelerator engineering design and necessary EDR R&D to be ready for industrial fabrications.
- (D) Complete a practical procurement strategy and logistics with both domestic and international suppliers.
- (E) In collaboration with local government, CAI and MOST (central government), CEPC also converge from several candidates to a EDR construction site satisfying the natural geological conditions, electric power and water resources, social and environment conditions, domestic and international transportation relevant conditions, international science city and sustainable development, etc.
- (F) Complete detailed construction site geological studies and corresponding site dependent cost engineering design and general utility facility design.
- (G) Complete the radiation, security, environment assessment studies and necessary documents (including EDR report) ready for the application to the central government to get the formal approval of construction.

**Accelerator EDR Phase Working Plan (preliminary) of 35 WGs is a documents of 20 pages**






# Automatic Production Lines of the CEPC Magnets in EDR



Conceptual design type-I




Conceptual design type-II

To reduce the fabrication cost of the magnets of CEPC, automatic magnet production lines will be demonstrated in EDR and used during construction



# Massive Production Line of NEG Coating Vacuum Chambers in EDR


- The coating device A: Vacuum chambers are connected in parallel to 6 groups, each group of vacuum chambers length should be lower than 3.5m, outer diameter is about 0.47m;
- The coating device B: Antechamber are connected in parallel to 4 groups, each group of vacuum chambers length should be lower than 1.5m, due to its discharge difficulty.
- Two setups of NEG coating have been built for vacuum pipes of HEPS at IHEP Lab. And a lot of test vacuum pipes have been coated, which shows that NEG film has good adhesion and thickness distribution.
- **In EDR phase a dedicated CEPC NEG coated vacuum chamber production line is planned**





# CEPC Planning and Schedule

**TDR (2023), EDR(2027), start of construction (2027-8)**





# CEPC Site Implementation and Construction Plans

## CEPC site implementation plan in EDR

## CEPC construction plan



### In-depth study of the Zhejiang Huzhou Site

#### 3. Analysis of the Construction Plan






# CEPC Evolution Milestones with Human Resources

Year	2015	2018	2023	2025	2027	2030	2035
Human resource FTE	~50	~100	~200	~300	~500	~2800	~2500


Year	Accelerator human resource	Accumulated spending Billion RMB
2015	50	-
2018	100	-
2023	200	0.2
2025	300	0.3
2027	500	0.4
2031	2800	9
2035	2500	20





# 9<sup>th</sup> CEPC IAC 2023 Meeting (important!)

9<sup>th</sup> CEPC IAC 2023 Meeting  
Oct. 30-31, 2023, IHEP, China



<https://indico.ihep.ac.cn/event/20107>

The CEPC accelerator TDR status and EDR plan have been reported to IAC and the report (draft) from the IAC:

- IAC endorse the CEPC TDR Review Report including recommendations in the report.
- Another key conclusion in the TDR Review Report , supported by the IAC, is that the accelerator team is well prepared to enter EDR phase
- The CEPC accelerator will be ready for construction after the successful completion...outlined in TDR Review Report, the engineering, and industrial preparation work and site studies being addressed in the EDR phase.



# Participating and Potential Collaborating Companies in China (CIPC) and Worldwide

	System
1	Magnet
2	Power supplier
3	Vacuum
4	Mechanics
5	RF Power
6	SRF/ RF
7	Cryogenics
8	Instrumentation
9	Control
10	Survey and alignment
11	Radiation protection
12	e-e+Sources

## CEPC Industrial Promototion Consortium (CIPC, established in Nov. 2017)



## Potential international collaborating suppliers worldwide



# CEPC International Collaboration -1




The first CEPC-SppC international Collaboration Workshop  
Nov 6-8, 2017, IHEP, Beijing

<http://indico.ihep.ac.cn/event/6618>




Workshop on the Circular Electron Positron Collider-EU edition  
May 24-26, 2018, Università degli Studi Roma Tre, Rome, Italy

<https://agenda.infn.it/conferenceDisplay.py?ovw=True&confId=14816>



3rd CEPC IAC, Nov 8-9, 2017,  
IHEP, Beijing



IAS High Energy Physics Workshop  
(Since 2015)

<http://iasprogram.ust.hk/hep/2018>



CEPC Workshop-EU , 2019 Sep 2019, Oxford,UK

<https://agenda.infn.it/conferenceDisplay.py?ovw=True&confId=14816>



CEPC Workshop, 22-23 April 2020, USA

<https://indico.cern.ch/event/863751/>

CEPC Workshop, EU-Edition, 3-6 July 2023, Edinburg,

The 2023 FCPPL, Zhuhai, China

UK

More than  
20 MoUs  
have been  
signed with  
international  
institutions  
and  
universities





# CEPC International Collaborations-2

## HKIAS23 HEP Conference Feb. 14-16, 2023

<https://indico.cern.ch/event/1215937/>



The 2024 HKUST IAS Mini workshop and conference will be held from Jan. 18-9, and Jan. 22-25, 2024, respectively.

## The 2023 International Workshop on Circular Electron Positron Collider, EU-Edition, University of Edinburgh, July 3-6, 2023

<https://indico.ph.ed.ac.uk/event/259/overview>



The 2024 international workshop of CEPC, EU-Edition is planned to be held in France



# CEPC International Collaborations-3

**International workshop CEPC 2023**  
**Oct. 23-27, 2023, Nanjing, China**



<https://indico.ihep.ac.cn/event/19316/>

**FCPPL2023**  
**Nov. 6-10, 2023, Zhuhai, China**



<https://indico.ihep.ac.cn/event/20622/>



# Invitation to sign up CEPC TDR

CEPC TDR preparation is currently in its final stage and is scheduled to be published soon. **We invite you to read the latest version of CEPC TDR draft**: ( [https://docs.ihep.ac.cn/anyshare/zh-cn/link/AA9FC882F906714CE1BC59DAF3BB048A60?\\_tb=none&expires\\_at=2023-12-30T15%3A28%3A28%2B08%3A00&item\\_type=&password\\_required=false&title=CEPC-TDR-draft-v4.pdf&type=anonymous](https://docs.ihep.ac.cn/anyshare/zh-cn/link/AA9FC882F906714CE1BC59DAF3BB048A60?_tb=none&expires_at=2023-12-30T15%3A28%3A28%2B08%3A00&item_type=&password_required=false&title=CEPC-TDR-draft-v4.pdf&type=anonymous) )

(This version is almost converged to the final one, but we will make the necessary adjustments and polishing later.)

**We sincerely inquire if you would be willing to sign the TDR authorship.** Your continued support and recognition would greatly contribute to the future development of the CEPC.

- **If you agree to sign, please fill in your information in TDR Authorship Collection** ( <https://indico.ihep.ac.cn/event/20817/registrations/1668/> ) **page.**
- **We will also appreciate if you could kindly help to invite people from your institutes or collaboration group, please also update information in TDR Authorship Collection** ( <https://indico.ihep.ac.cn/event/20817/registrations/1668/> ) **page.**
- **The Deadline for collection is Nov. 20<sup>th</sup>.**

Thanks for your cooperation. We greatly appreciate your support and dedication to CEPC Project.



# Summary

- The CEPC TDR parameter and design optimizations with high luminosity (30MW and 50MW) operations, for all four energies (Higgs, W/Z and ttbar) have been studied. The results demonstrate that the physics design satisfies the scientific goals.
- A comprehensive key technology R&D program has been carried out in TDR with CEPC key technologies in hands ready for industrialization preparation in EDR.
- CEPC accelerator **TDR international review and cost review** were held from June 12-16, 2023 and Sept. 11-15, 2023, respectively, and TDR will be released formally soon in 2023.
- Detailed preparation of CEPC accelerator EDR phase (2024-2027) before construction working plan and beyond have been established (preliminary), with the aim of starting the construction in “15<sup>th</sup> five-year-plan” (2026-2030), and completing the construction around 2035.
- **International collaboration and participation are warmly welcome.**



# Acknowledgements

---

Thanks go to CEPC-SppC accelerator team's hard works,  
international and CIPC collaborations

Special thanks to CEPC, IAC, IARC and TDR review (cost) committee's  
critical comments, suggestions and encouragement


**Thanks**



---

# Backup Slides

# Main Timelines of CEPC Accelerator Development




Pre-CDR in 2015

- 1) CEPC CDR Vol. I, Accelerator  
[http://cepc.ihep.ac.cn/CEPC\\_CDR\\_Vol1\\_Accelerator.pdf](http://cepc.ihep.ac.cn/CEPC_CDR_Vol1_Accelerator.pdf)
- 2) CEPC CDR Vol. II, Physics and Detector  
[http://cepc.ihep.ac.cn/CEPC\\_CDR\\_Vol2\\_Physics-Detector.pdf](http://cepc.ihep.ac.cn/CEPC_CDR_Vol2_Physics-Detector.pdf)
- 3) CEPC Accelerator white paper to Snowmass21, arXiv:2203.09451

## CEPC Video (BIM design)

- 1) [http://cepc.ihep.ac.cn/Qinhuang\\_Island.mp4](http://cepc.ihep.ac.cn/Qinhuang_Island.mp4)
- 2) <http://cepc.ihep.ac.cn/Huzhou.mp4>
- 3) <http://cepc.ihep.ac.cn/Changsha.mp4>



Progress report in 2016



CEPC CDR Released (2018.11)



CDR Accelerator and Detector/Exp. in 2028

# CEPC Accelerator IARC Meeting 2019-2022

## International Accelerator Review Committee (IARC) under IAC

The 2019 CEPC International Accelerator Review Committee

Review Report

December 8, 2019

### The 2021 CEPC International Accelerator Review Committee

Review Report

May 19, 2021

### 2021 Second CEPC IARC Meeting

IARC Committee

October 20th, 2021

### 2022 First CEPC IARC Meeting

IARC Committee

June 17th, 2022



Nov. 2019: <https://indico.ihep.ac.cn/event/9960/>

May, 2021: <https://indico.ihep.ac.cn/event/14295/>

October, 2021: <https://indico.ihep.ac.cn/event/15177/>

June, 2022: <https://indico.ihep.ac.cn/event/16801/>

After the completion of CEPC CDR in Nov. 2018, since the first CEPC IARC meeting in **2019**, there has been **toally 4 IARC meetings till 2022**, with each meeting a carefully written IARC report, which are very helpful for CEPC accelerator in TDR phase and beyond.

All IARC reports (**2019-2022**) on IAC2022 Meeting Indico:

<https://indico.ihep.ac.cn/event/17996/page/1415-materials>

The Committee congratulates the CE last months and presented at this meeting the table of parameters for the high-luminosity and components for all accelerator systems.

A total of 24 talks were presented on a variety of topics. The charges to CEPC IARC for this meeting are:

1. For the TDR, how are the accelerator design and the technology R&D progress towards the TDR completion at the end of 2022. Are there any important missing points in the accelerator design and optimization?
2. based on CEPC TDR design, the CEPC dedicated key technology R&D status and the technologies accumulated from the other IHEP responsible large-scale accelerator facilities, such as HEPs, could the CEPC accelerator group start the TDR editorial process and EDR preparation?
3. with the new progresses between CEPC and FCCee possible synergy and the continuing collaboration with SuperKEKB, are there more suggestions on the next steps of international collaborations?





# CEPC IAC Meeting 2022

<https://indico.ihep.ac.cn/event/17996/>

## The Eighth Meeting of the CEPC-SppC International Advisory Committee

IAC Committee

B. Barish, M. Biagini, Yuan-Hann Chang, A. Cohen, M. Davier,  
M. Demarteau, B. Foster (Chair), R. Godbole, D. Gross,  
B. Heinemann, K. Jakobs, L. Linssen, L. Maiani, M. Mangano,  
T. Nakada, I. Shipsey, S. Stapnes, G. Taylor,  
A. Yamamoto, Hongwei Zhao

November 4th, 2022

### 1 Overview

The eighth meeting of the CEPC-SppC International Advisory Committee took place virtually on October 31, November 1,2 and 4, 2022. The appendices to this report contain the charge for the meeting (Appendix A), the members of the IAC (Appendix B), and the agenda of the meeting (Appendix C). Due to different time zones, this meeting was necessarily much shorter than previous in-person meetings and missed informal exchanges of opinions. The IAC considers it essential to have some form of person-to-person meetings with more detailed materials at its next meeting in 2023, even if such a meeting has to take place outside China.

The IAC recommends that the project management presents a path to site selection, necessary for many aspects of the Engineering Design (ED) Phase, at the next IAC meeting.


**According to the recommendation of IAC, CEPC Accelerator Engineering Design Report phase planning has been started.**



# CEPC Project Development

X. Lou

- **TDR has been completed** (review + revision) to be released in 2023
- CAS is planning for the 15<sup>th</sup> 5-years plan for large science projects, and a steering committee has been established, chaired by the president of CAS
- **High energy physics**, as one of the 8 groups, has been working on this for a year:
  - Setting up rules and the standard(based on scientific and technological merits, strategic value and feasibility, R&D status, team and capabilities, etc.), established domestic and international advisory committees
  - Collected 15 proposals and selected 9, based on the above-mentioned standard
  - Evaluations and ranking by committees after oral presentations by each project
- **CEPC is ranked No. 1, with the smallest uncertainties, by every committee**
- A final report will be submitted to CAS for consideration





# IHEP International Assessment Sept.20-24, 2023)

## International Assessment of the Institute of High Energy Physics

### Preliminary Draft Report

September 20-24, 2023, IHEP, Beijing, China

Ursula Bassler, Roger Blandford, Andrew Glen Cohen, Cristinel Diaconu, Georges El Fakhri, Angeles Faus-Golfe, Wolfgang Parak, Harald Reichert, Yang Ren, Ian Shipsey, W. Michael Snow, Hans Weise, Harry Westfahl Jr., Frank Zimmermann.

### 6. CEPC Accelerators

	A+	A	B	C	D
<b>Overall ranking</b>	X				
Is the scientific goal(s) well defined, significant, and credible?	X				
Is there a clear and credible research and R&D plan to realize the scientific goal(s)?	X				
How has the program performed over the last 5 years?	X				
Is the progress of research, R&D and personnel development going according to the plan?		X			
Are the research resources, e.g. funding and laboratories, adequate to support the R&D?		X			