

CEPC Accelerator General Status: -from TRD to EDR

Jie Gao

IHEP

On behalf of the CEPC accelerator group

11th IHEP-KEK SCRF Collaboration Meeting

Nov. 20-21, 2023, IHEP, Beijing



Contents

- **Introduction**
- **CEPC accelerator system design and optimizations in TDR**
- **CEPC accelerator key hardware R&D progresses in TDR**
- **SppC compatibility with CEPC**
- **CEPC site preparations and civil engineering**
- **CEPC accelerator TDR review (+cost) and IAC meeting**
- **CEPC EDR goals, plans and scope**
- **CEPC industrial preparation and international collaboration**
- **Summary**



A Brief Historical Review

IHEP-KEK ILC 1.3GHz SC Technology related Collaboration started in 2005

- 1) 1th IHEP-KEK SCRF Collaboration Meeting, June 2009, IHEP
- 2) 2th IHEP-KEK SCRF Collaboration Meeting, December 2009, IHEP
- 3) 3th IHEP-KEK SCRF Collaboration Meeting, December 2010, IHEP
- 4) 4th IHEP-KEK SCRF Collaboration Meeting, December 2011, IHEP
- 5) 5th IHEP-KEK SCRF Collaboration Meeting, January 2013, IHEP
- 6) 6th IHEP-KEK SCRF Collaboration Meeting, July 15, 2017, IHEP
- 7) 7th IHEP-KEK SCRF Collaboration Meeting, September 22, 2018, IHEP
- 8) 8th IHEP-KEK SCRF Collaboration Meeting, Dec. 2-3, 2019, KEK
- 9) 9th IHEP-KEK SCRF Collaboration Meeting, Dec. 9, 2020, (Online)
- 10) 10th IHEP-KEK SCRF Collaboration Meeting, Feb. 16, 2022, (Online)
- 11) 11th IHEP-KEK SCRF Collaboration Meeting, Nov. 20-21, 2023, IHEP




9th and 10th IHEP-KEK SCRF Collaboration Meetings were held online in 2020 and 2022, and finally, 11th IHEP-KEK SCRF Collaboration Meeting is held in person at IHEP successfully. You are welcome to come to IHEP again in person after CoVid19.


Our collaborations on SCRF is very fruitful in last ~20 years, and wish a good and successful continuation!

CEPC Higgs Factory and SppC in TDR (EDR)

CEPC as a Higgs Factory: **H, W, Z**, upgradable to **tt-bar**, followed by a SppC (a Hadron collider) $\sim 125\text{TeV}$
 30MW SR power per beam (upgradable to 50MW), high energy gamma ray 100Kev \sim 100MeV






CEPC collider ring (100km)




CEPC booster ring (100km)

CEPC TDR S+C-band 30GeV linac injector



CEPC Civil Engineering



CEPC TDR Accelerator System Parameters

Linac

Parameter	Symbol	Unit	Baseline
Energy	E_e/E_{e+}	GeV	30
Repetition rate	f_{rep}	Hz	100
Bunch number per pulse			1 or 2
Bunch charge		nC	1.5 (3)
Energy spread	σ_E		1.5×10^{-3}
Emittance	ε_r	nm	6.5


Booster

		<i>tt</i>		<i>H</i>		<i>W</i>		<i>Z</i>	
		Off axis injection	Off axis injection	On axis injection	Off axis injection	Off axis injection			
Circumfer.	km	100							
Injection energy	GeV	30							
Extraction energy	GeV	180	120		80	45.5			
Bunch number		35	268	261+7	1297	3978	5967		
Maximum bunch charge	nC	0.99	0.7	20.3	0.73	0.8	0.81		
Beam current	mA	0.11	0.94	0.98	2.85	9.5	14.4		
SR power	MW	0.93	0.94	1.66	0.94	0.323	0.49		
Emittance	nm	2.83	1.26		0.56	0.19			
RF frequency	GHz	1.3							
RF voltage	GV	9.7	2.17		0.87	0.46			
Full injection from empty	h	0.1	0.14	0.16	0.27	1.8	0.8		

Collider

	Higgs	Z	W	<i>t</i> \bar{t}
Number of IPs	2			
Circumference (km)	100.0			
SR power per beam (MW)	30			
Energy (GeV)	120	45.5	80	180
Bunch number	268	11934	1297	35
Emittance $\varepsilon_x/\varepsilon_y$ (nm/pm)	0.64/1.3	0.27/1.4	0.87/1.7	1.4/4.7
Beam size at IP σ_x/σ_y (um/nm)	14/36	6/35	13/42	39/113
Bunch length (natural/total) (mm)	2.3/4.1	2.5/8.7	2.5/4.9	2.2/2.9
Beam-beam parameters ξ_x/ξ_y	0.015/0.11	0.004/0.127	0.012/0.113	0.071/0.1
RF frequency (MHz)	650			
Luminosity per IP ($10^{34} \text{ cm}^{-2} \text{ s}^{-1}$)	5.0	115	16	0.5

Transport line



1. Injection/Extraction to the Damping ring (e^+)
2. Injection to the Booster ring from Linac (e^+/e^-)
3. Booster ring extraction system (e^+/e^-)
4. Collider off-axis injection system (e^+/e^-)
5. collider on-axis swap-out injection (e^+/e^-)
6. Collider swap-out extraction (e^+/e^-)
7. beam dump system (e^+/e^-)

CEPC Collider Ring Daynamic Apertures

Dynamic apertures with errors at Higgs, W/Z and ttbar energies satisfy design goals

Effects included in tracking

Synchrotron motion

Radiation loss in all magnets






Tapering

Crab waist sextupole

Maxwellian fringes

Kinematic terms

Finite length of sextupole



Component	Δx (mm)	Δy (mm)	$\Delta\theta_z$ (mrad)	Field error
Dipole	0.10	0.10	0.10	0.01%
Arc Quadrupole	0.10	0.10	0.10	0.02%
IR Quadrupole	0.10	0.10	0.10	0.02%
Sextupole	0.10*	0.10*	0.10	0.02%

—w/o error

—mean value

—statistic errors


—seeds

—requirement




Studies of Beam-Beam Effects in CEPC

Luminosity simulations w/ZL



Beam-beam simulation results are **consistent** with the TDR parameter tables.

Transverse size simulations



- **Luminosity & Lifetime** is evaluated by strong-strong simulation
- **X-Z instability** is well suppressed even considering Potential Well Distortion
- **Lifetime optimization** with both beam-beam/lattice nonlinearity is done




Parameters of CEPC Booster

Injection		<i>tt</i>	<i>H</i>	<i>W</i>	<i>Z</i>	
Beam energy	GeV	30				
Bunch number		35	268	1297	3978	5967
Bunch charge	nC	1.1	0.78	0.81	0.87	0.9
Single bunch current	μA	3.4	2.3	2.4	2.65	2.69
Beam current	mA	0.12	0.62	3.1	10.5	16.0
Energy spread	%	0.025				
Synchrotron radiation loss/turn	MeV	6.5				
Momentum compaction factor	10 ⁻⁵	1.12				
Emittance	nm	0.076				
Natural chromaticity	H/V	-372/-269				
RF voltage	MV	761.0	346.0	300.0		
Betatron tune ν_x/ν_y		321.23/117.18				
Longitudinal tune		0.14	0.0943	0.0879		
RF energy acceptance	%	5.7	3.8	3.6		
Damping time	s	3.1				
Bunch length of linac beam	mm	0.4				
Energy spread of linac beam	%	0.15				
Emittance of linac beam	nm	6.5				




Extraction		<i>tt</i>	<i>H</i>		<i>W</i>	<i>Z</i>	
		Off axis injection	Off axis injection	On axis injection	Off axis injection	Off axis injection	
Beam energy	GeV	180	120		80	45.5	
Bunch number		35	268	261+7	1297	3978	5967
Maximum bunch charge	nC	0.99	0.7	20.3	0.73	0.8	0.81
Maximum single bunch current	μA	3.0	2.1	61.2	2.2	2.4	2.42
Beam current	mA	0.11	0.56	0.98	2.85	9.5	14.4
Bunches per pulse of Linac		1	1		1	2	
Time for ramping up	s	7.1	4.3		2.4	1.0	
Injection duration for top-up (Both beams)	s	29.2	23.1	31.8	38.1	132.4	
Current decay in Collider		3%					
Energy spread	%	0.15	0.099		0.066	0.037	
Synchrotron radiation loss/turn	GeV	8.45	1.69		0.33	0.034	
Emittance	nm	2.83	1.26		0.56	0.19	
Betatron tune ν_x/ν_y		321.27/117.19					
RF voltage	GV	9.7	2.17		0.87	0.46	
Longitudinal tune		0.14	0.0943		0.0879		
RF energy acceptance	%	1.78	1.59		2.6	3.4	
Damping time	ms	14.2	47.6		160.8	879	
Natural bunch length	mm	1.8	1.85		1.3	0.75	
Full injection from empty ring	h	0.1	0.14	0.16	0.27	1.8	0.8



CEPC Booster Design



- TME like structure (cell length=78m)
- Interleave sextupole scheme
- Emittance@120GeV=1.26nm



- 30 GeV injection energy, Maximum extraction energy @ 180GeV
- Lattice design with TME structure, lower emittance than CDR
- Sufficient Dynamic Aperture for all energies with errors

CEPC SRF System Design and Upgrade Plan


Collider 650MHz Parameters

	ttbar 30/50 MW		Higgs 30/50 MW	W 30/50 MW	Z 30/50 MW
	New cavities	Higgs cavities			
Luminosity / IP [$10^{34} \text{ cm}^{-2} \text{ s}^{-1}$]	0.5 / 0.8		5 / 8.3	16 / 26.7	115 / 192
RF voltage [GV]	10 (6.1 + 3.9)		2.2	0.7	0.12 / 0.1
Beam current / beam [mA]	3.4 / 5.6		16.7 / 27.8	84 / 140	801 / 1345
Bunch charge [nC]	32		21	21.6	22.4 / 34.2
Bunch length [mm]	2.9		4.1	4.9	8.7 / 10.6
650 MHz cavity number	192	336	192/336	96 / 168 / ring	30 / 50 / ring
Cell number / cavity	5	2	2	2	1
Gradient [MV/m]	27.6	25.2	24.9 / 14.2	15.9 / 9.1	17.4 / 8.7
Q_0 @ 2 K at operating gradient	3E10	3E10	3E10	3E10	2E10
HOM power / cavity [kW]	0.4 / 0.68	0.16 / 0.26	0.4 / 0.67	0.93 / 1.54	2.9 / 6.2
Input power / cavity [kW]	188 / 315	71 / 118	313 / 298	313 / 298	1000
Optimal Q_0	1E7 / 8E8	9E6 / 5.4E6	1.6E6 / 9.5E5	8E5 / 2.7E5	1.5E5 / 3.8E4
Optimal detuning [kHz]	0.01 / 0.02	0.02 / 0.03	0.1 / 0.2	0.7 / 2	6.7 / 21.7
Cavity number / klystron	4 / 2	2	2	2	1
Klystron power [kW]	800	800	800	800	1200
Klystron number	48 / 96	168	96 / 168	96 / 168	60 / 100
Cavity number / cryomodule	4	6	6	6	1
Cryomodule number	48	56	32 / 56	32 / 56	60 / 100
Total cavity wall loss @ 2 K [kW]	12.1	7.1	3.9 / 2.3	1.6 / 0.9	0.45 / 0.2


Booster 1.3GHz Parameters

	ttbar 30/50 MW		Higgs 30/50 MW	W 30/50 MW	Z 30/50 MW
	New cavities	Higgs cavities			
Extraction beam energy [GeV]	180		120	80	45.5
Extraction average SR power [MW]	0.05		0.5 / 0.67	0.02 / 0.04	0.05 / 0.1
Bunch charge [nC]	1.1		0.78 (20.3)	0.73	0.81
Beam current [mA]	0.12 / 0.19		0.63 (1) / 1 (1.4)	3.1 / 5.3	16 / 30
Injection RF voltage [GV]	0.761		0.346	0.3	0.3
Extraction RF voltage [GV]	9.7 (7.53 + 2.17)		2.17	0.87	0.46
Extraction bunch length [mm]	1.8		1.86	1.3	0.75
Cavity number (1.3 GHz 9-cell)	256	96	96	96	32
Module number (8 cavities / module)	32	12	12	12	4
Extraction gradient [MV/m]	28.3	21.8	21.8	8.7	13.8
Q_0 @ 2 K at operating gradient	2E10	3E10	3E10	3E10	3E10
Q_0	4E7	4E7	1.2E7	7.3E6 / 4.4E6	1.2E7 / 6.3E6
Cavity bandwidth [Hz]	33	33	110	178 / 296	111 / 208
Peak HOM power per cavity [W]	0.5 / 0.8		~ 75 / ~ 100	11.8 / 19.6	148 / 272
Average HOM power per cavity [W]	0.2 / 0.32		~ 10 / ~ 15	3.8 / 6.3	80 / 150
Input peak power per cavity [kW]	8.3 / 9.2	5.1 / 5.9	22 / 32	10.9 / 18.1	17 / 32
Input average power per cavity [kW]	0.3	0.2	6.5 / 9.2	0.3 / 0.5	2.5 / 4.5
SSA power [kW] (1 cavity / SSA)	25 / 30		25 / 30	25 / 30	25 / 40
Total cavity wall loss @ 2 K [kW]	0.36	0.05	0.5	0.02	0.08

H/W/Z/ttbar bypass scheme



SRF power supply auxiliary tunnel




- CEPC TDR SRF layout and parameters are designed to **meet physics requirements**;
- RF system design optimized for Higgs 30/50 MW. Power and energy upgrade by adding cavities, RF power sources and cryogenic plants and other systems are compatible;
- Use dedicated high current 1-cell cavity for 10-50 MW Z. Solve the FM & HOM CBI problems.



CEPC MDI Design


MDI Layout



General Parameters


Parameter	Value	Length	Beam stay clear region	Min. distance between apertures	Beam pipe inner diameter	Beam pipe outer diameter	Critical energy (Hor.)	Critical energy (Vert.)	SR power (Hor.)	SR power (Vert.)
L*	0~1.9m	1.9m								
Crossing angle	33mrad									
MDI length	±7m									
Acc. components in opening angle	8.11°									
QDa/QDb	3.5/1.8T 142/85T/m	1.21m	14.9/18.2mm	62.71/105.2mm	20/23mm	26/29mm	724.7/663.1keV	396.3/263keV	212.2/239.23W	99.9/42.8W
QF1	3.3T 96.7T/m	1.5m	24.48mm	155.11mm	32mm	38mm	575.2keV	489.4keV	472.9W	135.1W
Lumical	0.65~1.11m	0.16m								
Anti-solenoid before QD0	8.6T	1.1m								
Anti-solenoid QD0	3T	2.5m								
Anti-solenoid QF1	3T	1.5m								
Beryllium pipe		±85mm			20mm					
Last B upstream	64.97~153.5m	0.77mrad	88.5m				33.3keV			
First B downstream	44.4~102m	1.17mrad	57.6m				77.9keV			
Beam pipe within QDa/QDb		1.21m							1.19/1.3W	
Beam pipe within QF1										

SR Calculation




Radiation background


Radiative barrier, Beam-Gas, beam thermal photon scattering



Injection background




Radiation Mitigation Masks, collimators, shielding






CEPC Electron and Positron Injection Linac Designs




Parameter	Symbol	Unit	Design value
Energy	E	GeV	30
Repetition rate	f_{rep}	Hz	100
Number of bunches per pulse			1 or 2
Bunch charge		nC	1.5
Energy spread	σ_E		1.5×10^{-3}
Emittance	ϵ_r	nm	6.5
Electron energy at target		GeV	4
Electron bunch charge at target		nC	10
Tunnel length	L	m	1800


e- in linac



e+ in linac




Phase space @ SAS exit




- Linac energy increases to 30 GeV, with S+C band Accelerator;
- Start-to-end simulations were conducted for both electron/positron beams, with quality satisfying requirements.


CEPC Polarized Beam Studies(alternative option)



Self polarization (energy calibration)



Spin rotator design




Key issues of study:

- Energy calibration in collider ring with transverse polarization (self polarization & inj. polarization)
- Longitudinal polarization for collision
- Polarization beam injection, positron polarization and ramping in booster

CEPC Plasma Injector (alternative option) and TF Plan


CEPC injector's baseline was changed:
 10 GeV \rightarrow 30 GeV \rightarrow **TR ≥ 2**



CEPC IARC, 2022.06


Parameters	Driver	Trailer
plasma density $n_p (\times 10^{16} cm^{-3})$	0.50334	
Driver energy $E(GeV)$	12	12
Normalized emittance $\epsilon_N (\mu m rad)$	20	10
Length $L (\mu m)$	350	90
(matched) Spot size $\sigma_r (\mu m)$	3.72	2.63
Charge Q (nC)	4.0	1.2
Beam distance $d (\mu m)$	155	

Parameters	Trailer
Accelerating distance (m)	7.3 (97300 w_p^{-1})
Trailer energy $E(GeV)$	30
Normalized emittance $\epsilon_n (mm mrad)$	10
Charge(nC)	1.2
Energy spread $\delta_E (\%)$	0.58
R	1.8
Efficiency(%) (driver \rightarrow trailer)	55





CEPC Key Technology R&D



Key technology R&D spans all component lists in CEPC TDR



CEPC SRF Facilities and Components




Mid-T (medium temperature furnace baked) cavities have higher gradient and Q than Nitrogen doped cavities with **less EP process (1 vs 3)**

IHEP PAPS is in full operation since 2021


CEPC 650 MHz 2-cell Cavity

CEPC 650 MHz 1-cell Cavity

1.3 GHz High Q Mid-T Cavity Horizontal Test




3E10@20MV/m.




High G High Q 650 MHz 1-cell Cavity

EP treated: **2.3E10@41.6 MV/m@2 K**
Mid-T treated: **6.3E10@31 MV/m@2 K**



Mid-T 1.3 GHz 9-cell vertical test
avg. **4.3E10@ 31 MV/m**




Mid-T 1.3 GHz 9-cell horizontal test (SEL)
3.1E10@21 MV/m, avg. **24.6 MV/m**



CEPC Collider 650 MHz 2 x 2-cell Test Cryomodule



- DC photo-cathode gun voltage conditioned up to 400 kV
- Cavity frequency, HOM coupler double notch filter, tuner, vacuum, cryogenics perform well
- Cavity magnetic field at 2 K < 2 mG (large beam pipe North to South)
- **LLRF system commissioning and high power test ongoing**
 - Optimizing the outer conductor helium gas cooling of the input coupler. Cavity early quench if with poor coupler cooling.





- Module automatic cool-down experiment**
1. 300 to 150 K: < 10 K/hr. Cavity top and bottom $\Delta T < 20$ K
 2. 150 to 4.5 K: Cavity surface > 1 K/min
 3. 4.5 to 2 K



CEPC Booster 1.3 GHz 8 x 9-cell High Q Cryomodule

CEPC booster 1.3 GHz SRF R&D and industrialization in synergy with CW FEL projects.

Parameters	Horizontal test results	CEPC Booster Higgs Spec	LCLS-II, SHINE Spec	LCLS-II-HE Spec
Average usable CW E_{acc} (MV/m)	23.1	3.0×10^{10} @ 21.8 MV/m	2.7×10^{10} @ 16 MV/m	2.7×10^{10} @ 20.8 MV/m
Average Q_0 @ 21.8 MV/m	3.4×10^{10}			





CEPC High Efficiency High Power Klystron Development and RF Power Distribution


Klystron R&D



Klystron No. 1
Efficiency 65%
(2020)



Klystron No. 2
Efficiency 77%
(2021)




Klystron No. 3 (MB)
Efficiency 80.5%
(under fabrication)

Power Step Module







Pulsed RF Mode (30% duty factor, 60ms/5Hz)

High Voltage vs. Power&Efficiency




70.5% @ 630kW



- Three prototypes of the 650MHz 800KW CW klystrons are developed. The efficiency reaches 70%
- PSM is developed with the industrial collaboration
- RF tunnel distribution was planed

CEPC Collider Ring Full-scale Dual-aperture Magnets


Full-length 5.67m Dual aperture dipole



High harmonics @120GeV (units:1e-4)

n	bn_A	bn_B
2	0	0
3	3.92	3.88
4	1.03	-1.22
5	0.47	0.54
6	0.08	-0.46




Dual aperture QUAD



E(GeV)	GL(T)-A	GL(T)-B	difference
45	-3.36	3.35	0.40%
80	-5.91	5.88	0.59%
120	-8.89	8.85	0.49%
148	-10.93	10.89	0.40%
175	-12.77	12.73	0.30%
182.5	13.27	13.21	0.40%

Two apertures differ <0.1%, transfer function in two apertures are consistent.


High harmonics are nearly the same at four energies and all less than 5 units, which can meet the requirements.



- **Large quantities of dual-aperture dipoles (69km) and quad. (10km) are required;**
- **Full length dual-aperture dipole and dual aperture QUAD (short length) have been fabricated, under test;**
- **Dipole/QUAD prototypes meet the requirements.**

CEPC Full-scale Weak Field Dipole for Booster

Magnet name	BST-63B-Arc	BST-63B-Arc-SF	BST-63B-Arc-SD	BST-63B-IR
Quantity	10192	2017	2017	640
Aperture [mm]	63	63	63	63
Dipole Field [Gs] @180 GeV	564	564	564	549
Dipole Field [Gs] @120 GeV	376	376	376	366
Dipole Field [Gs] @30 GeV	95	95	95	93
Sextupole Field [T/m ²] @180 GeV	0	16.0388	19.1423	0
Sextupole Field [T/m ²] @120 GeV	0	10.6925	12.7615	0
Sextupole Field [T/m ²] @30 GeV	0	2.67315	3.19035	0
Magnetic length [mm]	4700	4700	4700	2350
GFR [mm]	±22.5	±22.5	±22.5	±22.5
Field errors	±1×10 ⁻³	±1×10 ⁻³	±1×10 ⁻³	±1×10 ⁻³






- Booster requires $\sim 19k$ pieces of magnets (68km);
- Booster dipoles are required to work at the low field of 95 Gs (30GeV) with an error smaller than 1×10^{-3} ;
- Full length (4.7m) dipole was developed, and it meets the field specification;



CEPC Final Focus Superconducting Quadrupoles

SCQ Specifications

	Q1a	Q1b	Q2	
Field gradient	142.3	85.4	96.7	T/m
Magnetic length	1210	1210	1500	mm
Reference radius	7.46	9.085	12.24	mm
Mini. distance between aperture center	62.71	105.28	155.11	mm
High order field harmonics	$\leq 5 \times 10^{-4}$	$\leq 5 \times 10^{-4}$	$\leq 5 \times 10^{-4}$	
Dipole field	≤ 3	≤ 3	≤ 3	mT




- CCT and Cos2θ type SCQs were modeled, and their fields were calculated; the CEPC specifications have been met;
- A 0.5-m single aperture SCQ using Cos2θ technology has been developed. The electro-magnet excitation test showed the highest current reached 2500A (176 T/m), which exceeds the CEPC requirement (142T/m)



CEPC Vacuum System

New round pipe of Copper (3mm) with NEG coating (200nm) for collider ring in TDR
SEY<1.2




6 m vacuum pipe have been installed on the NEG coating setup

- ✓ 180°C/24h activation 4.5×10^{-10} Torr
- ✓ 200°C/24h activation 2.5×10^{-10} Torr



Vacuum pipes and RF shielding bellows



Vacuum chamber prototypes, copper & aluminum, with different shape/length were fabricated;





- NEG coating technology were developed;
- RF shielding bellow manufactured
- Vacuum technology applied and was tested at HEPS




Facility of pumping speed test have been finished in Dongguan

CEPC Linac Injector Key Technology R&D

- ◆ Flux concentrator for positron source
- ◆ RF pulse compressor
- ◆ High perform. S/C-band Acc. Struc.



R&D of the solid state Test result of the peak



IHEP C-band SLED



Test results of IHEP C-band SLED



SACLAL C-band SLED



IHEP C-band BOC




PSI BOC

- Positron pulsed magnetic field of 6 T to 0.5 T
- 15kA/15kV/50Hz solid state pulse source



Nov. 20-21, 2023, J. Gao



11th IHEP-KEK SCRF Collaboration Meeting, IHEP



High power test bench



The input power with SLED



Power Consumption of CEPC - Higgs

SN	System	Higgs 30MW							Higgs 50MW						
		Collider	Booster	Linac	BTL	IR	Surface building	Total	Collider	Booster	Linac	BTL	IR	Surface building	Total
1	RF Power Source	96.90	1.40	11.10				109.40	161.60	1.73	14.10				177.40
2	Cryogenic system	9.72	1.71			0.14		11.57	9.17	1.77			0.14		11.08
3	Vacuum System	5.40	4.20	0.60				10.20	5.40	4.20	0.60				10.20
4	Magnet Power Supplies	44.50	9.80	2.50	1.10	0.30		58.20	44.50	9.80	2.50	1.10	0.30		58.20
5	Instrumentation	1.30	0.70	0.20				2.20	1.30	0.70	0.20				2.20
6	Radiation Protection	0.30		0.10				0.40	0.30		0.10				0.40
7	Control System	1.00	0.60	0.20				1.80	1.00	0.60	0.20				1.00
8	Experimental devices					4.00		4.00					4.00		4.00
9	Utilities	37.80	3.20	1.80	0.60	1.20		44.60	46.40	3.80	2.50	0.60	1.20		54.50
10	General services	7.20		0.30	0.20	0.20	12.00	19.90	7.20		0.30	0.20	0.20	12.00	19.90
	Total	204.12	21.61	16.80	1.90	5.84	12.00	262.27	276.87	22.60	20.50	1.90	5.84	12.00	339.71



SppC Collider Parameters in TDR

-Parameter list (updated Feb. 2022)


Main parameters

Circumference	100	km
Beam energy	62.5	TeV
Lorentz gamma	66631	
Dipole field	20.00	T
Dipole curvature radius	10415.4	m
Arc filling factor	0.780	
Total dipole magnet length	65442.0	m
Arc length	83900	m
Total straight section length	16100	m
Energy gain factor in collider rings	19.53	
Injection energy	3.20	TeV
Number of IPs	2	
Revolution frequency	3.00	kHz
Revolution period	333.3	μ s


Physics performance and beam parameters

Initial luminosity per IP	4.3E+34	$\text{cm}^{-2} \text{s}^{-1}$
Beta function at initial collision	0.5	m
Circulating beam current	0.19	A
Nominal beam-beam tune shift limit per	0.015	
Bunch separation	25	ns
Bunch filling factor	0.756	
Number of bunches	10080	
Bunch population	4.0E+10	
Accumulated particles per beam	4.0E+14	


Lattice of SPPC




Whole ring



Collimation



IP



Dynamic Aperture

**Ecm=125TeV
with dipole
field of 20T**





SppC HF Magnet Development

16 T Model Dipole: Nb₃Sn 12~13 T + HTS 3~4 T; To be tested in Sep-Dec 2023



Picture of LPF1-U



Dual aperture superconducting dipole achieves 12.47 T at 4.2 K
Entirely fabricated in China. The next step is reaching 16-20T





CEPC Site Preparations (three examples)




2034
⑧
ject is

CEPC Conventional Facility and Civil Engineering

Electrical Equipment General Layout in Auxiliary



Cables installed!





CEPC Accelerator International TDR Review and Cost Review June 12-16, and Sept. 11-15, 2023, in HKUST-IAS, Hong Kong






CEPC Accelerator TDR Review
June 12-16, 2023



CEPC Accelerator TDR Cost Review
Sept. 11-15, 2023



Domestic Civil Engineering
Cost Review, June 26, 2023



CEPC TDR cost distribution

CEPC accelerator TDR to be released formally soon in 2023



CEPC Accelerator TDR International Review Report

Phase 1 CEPC TDR Review Report

CEPC TDR Technical Review Committee

Chaired by Frank Zimmermann

15 July 2023

1 Executive Summary

Five years after the completion of the CDR, the draft TDR for the CEPC accelerator has been prepared. The TDR will be completed taking into account the feedback from this Committee. The key technologies for CEPC have been developed. Prototypes meeting or exceeding the specifications are available. The CEPC team is on track to launch an engineering-design effort. After a site has been selected, the construction of the CEPC could start in 2027 or 2028. The Committee endorses this plan.

The Committee wishes to congratulate the CEPC team on the excellent progress. The Committee is impressed by the amount and quality of the work performed and presented.

The next section provides answers to the different charge questions, the following sections contain comments and recommendations related to the individual presentations.

CEPC Accelerator International TDR Review was held June 12-16, 2023, in HKUST-IAS, Hong Kong

<https://indico.ihep.ac.cn/event/19262/timetable/>



CEPC Accelerator TDR Cost Review

Chaired by Loinid Rivkin

The CEPC Accelerator TDR Cost Review committee examined the cost estimate of the TDR of accelerator systems for the first stage of the CEPC project operated as a Higgs factory with synchrotron radiation power up to 30 MW per beam (including all infrastructure that is not easily upgradeable and is already designed to operate up to the ttbar energy and at 50 MW). The cost estimate under review does not include the civil engineering, the detectors at the IPs with their technical services, and the central computing services.

In the opinion of the committee the cost estimate presented is sufficiently complete to form a proper basis for the next iteration that will be done during the EDR stage.

The responses to the Charge are set out below, followed by some general observations, and then some specific issues on which we have more to say.

CEPC Accelerator International TDR Cost Review was held Sept. 11-15, 2023, in HKUST-IAS, Hong Kong

<https://indico.ihep.ac.cn/event/19262/timetable/>



9th CEPC IAC 2023 Meeting (important!)

9th CEPC IAC 2023 Meeting
Oct. 30-31, 2023, IHEP, China

Chaired by Brian Foster



<https://indico.ihep.ac.cn/event/20107>

The CEPC accelerator TDR status and EDR plan have been reported to IAC and the report (draft) from the IAC:

-IAC endorse the CEPC TDR Review Report including recommendations in the report.

-Another key conclusion in the TDR Review Report , supported by the IAC, is that the accelerator team is well prepared to enter EDR phase

-The CEPC accelerator will be ready for construction after the successful completion...outlined in TDR Review Report, the engineering, and industrial preparation work and site studies being addressed in the EDR phase.



CEPC Engineering Design Report (EDR) Goal



CEPC EDR Phase General Goal: 2024-2027

After completion CEPC accelerator TDR in 2023, CEPC accelerator will enter into the Engineering Design Report (EDR) phase (2024-2027), which is also the preparation phase with the aim for CEPC PROPOSAL to be presented to and selected by Chinese government around 2025 for the construction start during the "15th five year plan (2026-2030)" (for example, around 2027) and completion around 2035 (the end of the 16th five year plan).



CEPC EDR Goal, Plan and Scope

CEPC Accelerator EDR Phase Working Plan (preliminary) 2024 - 2027 (Oct. 16, 2023 draft)

CEPC EDR general goals:

According to the general CEPC plan, CEPC Conceptual Design Report (CDR) was completed in Nov. 2018, after the completion of CEPC accelerator TOR in 2023. CEPC accelerator will enter into the Engineering Design Report (EDR) phase (2024-2027), which is also the preparation phase with the aim for CEPC to be presented to and selected by Chinese government for the construction start during the "15th five year plan" (under way).

Chinese government for the construction start during the "15th five year plan" (under way).

2027) and completion around 2035 (the end of the 16th five year plan" (under way).

- Work closely with CAS and MOST and to prepare CEPC to be put in the "15th five year plan" (under way)
- Work closely with local governments towards a construction site (under way)
- Work closely with local government, CAI and MOST on EDR-related funds (under way)

CEPC Accelerator EDR Plan and Scope:

According to the general CEPC plan, CEPC Conceptual Design Report (CDR) was completed in Nov. 2018, and the CEPC accelerator Technical Design Report (TDR) will be formally released in 2026 after international review(s) (including a CEPC accelerator cost review). Therefore, CEPC accelerator will enter into the EDR phase (2024-2027), which is also the preparation phase with the aim for CEPC to be presented to and selected by Chinese government for the construction start during the "15th five year plan" (under way).

Chinese government for the construction start during the "15th five year plan" (under way).

2027) and completion around 2035 (the end of the 16th five year plan" (under way).

Breakdown of CEPC Accelerator EDR working plan and goals (2024-2027)

According to the CEPC and CEPC Accelerator EDR general goals described above, CEPC accelerator EDR working plan and goals, with year to do list (items) and deliverables, milestones, etc. are briefly described as follows:

- (A) Based on the CEPC TDR accelerator design, demonstrate a complete and coherent feasibility EDR design, which will guarantee the construction, commissioning, operation, and upgrade possibilities.
- (B) The CEPC EDR accelerator design should guarantee the project goals with required energies (pulsed, W and 2 pole, with 1000 ns upgrade possibility) and corresponding required luminosities with 300W synchrotron radiation power/beam as a baseline and 500W as upgrade possibility.
- (C) Based on the CEPC TDR accelerator key technology R&D achievement, complete the accelerator engineering design and necessary EDR R&D to be ready for industrial fabrications.
- (D) Complete a practical procurement strategy and register with both domestic and international suppliers.
- (E) In collaboration with local government, CAI and MOST (central government), CEPC also converge from several candidates to a EDR construction site satisfying the natural geological conditions, electric power and water resources, social and environment conditions, domestic and international transportation relevant conditions, international science city and sustainable development, etc.
- (F) Complete detailed construction site geological studies and corresponding site dependent cost engineering design and general utility facility design.
- (G) Complete the radiation, security, environment assessment studies and necessary documents (including EDR report) ready for the application to the central government to get the formal approval of construction.

Accelerator EDR Phase Working Plan (preliminary) of 35 WGs is a documents of 20 pages

human resources needed for the completion of CEPC
 obtain a complete database, such as cost items with design completeness, and cost limit, to identify and location,
 in relation with industrial fabrications, measurements, limited resource availability, etc.
 including items of the total accelerator cost,
 including MDX and cryogenics) and develop system

to and procurement plans to eliminate major risk items and multiple production lines (for example, 6 NEG coated vacuum chambers mass production

big effect of BPM errors and multi-fault errors, the long range alignment errors
 to main magnets of all
 to and possible feedback, including the injection (JIT), the power source (JIT),
 from the candidate sites
 ketic lattice and strong-strong beam-beam interaction, to study the effects
 performance and the interplay with the luminosity-focusing knobs.
 first turn injection, tuning, operation, different modes switching at all
 (and operation.

structure with half ring distribution (Higgs mode & Higgs) to confirm
 structure.
 to reduce the number of BPM, collecting

(power test bench and test the RF system, verify the accelerating gradient. The
 depend on the high-power test. According to the test result, make a new list
 for better accelerating structures
 (CAI normal conducting 2 cell cavity, Cold test of the CAI normal conducting 2-
 cell and frequency synthesizer for the C-band LUX system, and build a
 if we already forward:
 I phase proceed to further improve the accuracy and stability of the
 place the first prototype, and meet basic production

including during ring
 react beam energy

40) Accelerator Water and cooling (the Higgs (i.e., Zhang) (under way))
 41) CEPC High-Pressure Insulation System (under way)
 The laboratory of CEPC
 laboratory

2020 system mainly includes single magnet, solenoid and vacuum etc. It
 will be made of components through the EDR phase, verify the feasibility
 and package manufacturing. To ensure the CEPC being completed in
 full requirements, including 4 kinds of heater system, 3 kinds of
 more flexible system and construction height.
 software development for the hardware design and
 hardware development.
 based on the impedance calculation from the
 impedance, such as bandwidth, characteristic
 impedance, etc.


generation to narrow the difference with future
 simulation results, the interface between different tools,
 using Amegun pipe and to speed up beam pipe. It
 by the key technology such as the manufacture of the
 the between the content and the pipe in relation
 rate the aluminum, the window to LowCAI and to
 the high specific insulation problem. Expect
 on pipe insulation alignment.

to get an explicit loading time and instructions
 including errors, beam injection efficiency
 that beam before it acceptable.


to of the long prototype of the star
 detection design of dual sections
 resonator magnet, considering
 treatment in play its magnet
 Develop a testable magnet



Automatic Production Lines of the CEPC Magnets in EDR



Conceptual design type-I




Conceptual design type-II

To reduce the fabrication cost of the magnets of CEPC, automatic magnet production lines will be demonstrated in EDR and used during construction



Massive Production Line of NEG Coating Vacuum Chambers in EDR


- The coating device A: Vacuum chambers are connected in parallel to 6 groups, each group of vacuum chambers length should be lower than 3.5m, outer diameter is about 0.47m;
- The coating device B: Antechamber are connected in parallel to 4 groups, each group of vacuum chambers length should be lower than 1.5m, due to its discharge difficulty.
- Two setups of NEG coating have been built for vacuum pipes of HEPS at IHEP Lab. And a lot of test vacuum pipes have been coated, which shows that NEG film has good adhesion and thickness distribution.
- **In EDR phase a dedicated CEPC NEG coated vacuum chamber production line is planned**





CEPC Planning and Schedule

TDR (2023), EDR(2027), start of construction (2027-8)







CEPC Site Implementation and Construction Plans

CEPC site implementation plan in EDR


CEPC construction plan



CEPC Evolution Milestones with Human Resources

Year	2015	2018	2023	2025	2027	2030	2035
Human resource	~50	~100	~200	~300	~500	~2800	~2500

Year	Accelerator human resource	Accumulated spending Billion RMB
2015	50	-
2018	100	-
2023	200	0.2
2025	300	0.3
2027	500	0.4
2031	2800	9
2035	2500	20





Participating and Potential Collaborating Companies in China (CIPC) and Worldwide

	System
1	Magnet
2	Power supplier
3	Vacuum
4	Mechanics
5	RF Power
6	SRF/ RF
7	Cryogenics
8	Instrumentation
9	Control
10	Survey and alignment
11	Radiation protection
12	e-e+Sources

CEPC Industrial Promototion Consortium (CIPC, established in Nov. 2017)



Potential international collaborating suppliers worldwide



CEPC International Collaboration -1



The first CEPC-SppC international Collaboration Workshop
Nov 6-8, 2017, IHEP, Beijing

<http://indico.ihep.ac.cn/event/6618>




Workshop on the Circular Electron Positron Collider-EU edition
May 24-26, 2018, Università degli Studi Roma Tre, Rome, Italy

<https://agenda.infn.it/conferenceDisplay.py?ovw=True&confId=14816>



3rd CEPC IAC, Nov 8-9, 2017,
IHEP, Beijing



IAS High Energy Physics Workshop
(Since 2015)

<http://iasprogram.ust.hk/hep/2018>



CEPC Workshop-EU , 2019 Sep 2019, Oxford,UK

<https://agenda.infn.it/conferenceDisplay.py?ovw=True&confId=14816>

CEPC Workshop, EU-Edition, 3-6 July 2023, Edinburg,

11th IHEP-KEK, SCRF Collaboration Meeting, IHEP
UK



CEPC Workshop, 22-23 April 2020, USA

<https://indico.cern.ch/event/863751/>

More than
20 MoUs
have been
signed with
international
institutions
and
universities



CEPC International Collaborations-2

HKIAS23 HEP Conference Feb. 14-16, 2023

<https://indico.cern.ch/event/1215937/>



The 2024 HKUST IAS Mini workshop and conference will be held from Jan. 18-9, and Jan. 22-25, 2024, respectively.

The 2023 International Workshop on Circular Electron Positron Collider, EU-Edition, University of Edinburgh, July 3-6, 2023

<https://indico.ph.ed.ac.uk/event/259/overview>



The 2024 international workshop of CEPC, EU-Edition is planned to be held in France



CEPC International Collaborations-3

International workshop CEPC 2023
Oct. 23-27, 2023, Nanjing, China



<https://indico.ihep.ac.cn/event/19316/>

FCPPL2023
Nov. 6-10, 2023, Zhuhai, China



<https://indico.ihep.ac.cn/event/20622/>



Invitation to sign up CEPC TDR

CEPC TDR preparation is currently in its final stage and is scheduled to be published soon. **We invite you to read the latest version of CEPC TDR draft**: (https://docs.ihep.ac.cn/anyshare/zh-cn/link/AA9FC882F906714CE1BC59DAF3BB048A60?_tb=none&expires_at=2023-12-30T15%3A28%3A28%2B08%3A00&item_type=&password_required=false&title=CEPC-TDR-draft-v4.pdf&type=anonymous)

(This version is almost converged to the final one, but we will make the necessary adjustments and polishing later.)

We sincerely inquire if you would be willing to sign the TDR authorship. Your continued support and recognition would greatly contribute to the future development of the CEPC.

- **If you agree to sign, please fill in your information in TDR Authorship Collection** (<https://indico.ihep.ac.cn/event/20817/registrations/1668/>) **page.**
- **We will also appreciate if you could kindly help to invite people from your institutes or collaboration group, please also update information in TDR Authorship Collection** (<https://indico.ihep.ac.cn/event/20817/registrations/1668/>) **page.**
- **The Deadline for collection is Nov. 20th.**

Thanks for your cooperation. We greatly appreciate your support and dedication to CEPC Project.



Summary

- The CEPC TDR parameter and design optimizations with high luminosity (30MW and 50MW) operations, for all four energies (Higgs, W/Z and ttbar) have been studied. The results demonstrate that the physics design satisfies the scientific goals.
- A comprehensive key technology R&D program has been carried out in TDR with CEPC key technologies in hands ready for industrialization preparation in EDR.
- CEPC accelerator **TDR international review and cost review** were held from June 12-16, 2023 and Sept. 11-15, 2023, respectively, and TDR will be released formally soon in 2023.
- Detailed preparation of CEPC accelerator EDR phase (2024-2027) before construction working plan and beyond have been established (preliminary), with the aim of starting the construction in “15th five-year-plan” (2026-2030), and completing the construction around 2035.
- **International collaboration and participation are warmly welcome.**



Acknowledgements

Thanks go to CEPC-SppC accelerator team's hard works,
international and CIPC collaborations

Special thanks to CEPC, IAC, IARC and TDR review (cost) committee's
critical comments, suggestions and encouragement

Thanks



Backup Slides



Physics Goals of CEPC-SppC

• Circular Electron-Positron Collider (CEPC) as a Higgs Factory (91, 160, 240, 360 GeV)

– Higgs Factory ($>10^6$ Higgs) :

- Precision study of Higgs(m_H , JPC, couplings), Similar & complementary to ILC
- Looking for hints of new physics, DM...

– Z & W factory ($>10^{10}$ Z0) :

- precision test of SM
- Rare decays ?

– Flavor factory: b, c, t and QCD studies

• Super proton-proton Collider(SppC) (~100 TeV)

– Directly search for new physics beyond SM


– Precision test of SM

- e.g., h_3 & h_4 couplings


Precision measurement + searches for new physics:

Complementary with each other !

CEPC-SppC was proposed by Chinese scientists in Sept. 2012 after Higgs Boson was discovered on July 4, 2012 at CERN



Cross sections for major SM physics processes at the electron positron collider



Anticipated accuracy on Higgs properties at CEPC and at LHC/HL-LHC



CEPC Operation Plan


Particle	$E_{c.m.}$ (GeV)	Years	SR Power (MW)	Lumi. per IP ($10^{34}cm^{-2}s^{-1}$)	Integrated Lumi. per year (ab^{-1} , 2 IPs)	Total Integrated L (ab^{-1} , 2 IPs)	Total no. of events
H^*	240	10	50	8.3	2.2	21.6	4.3×10^6
			30	5	1.3	13	2.6×10^6
Z	91	2	50	192**	50	100	4.1×10^{12}
			30	115**	30	60	2.5×10^{12}
W	160	1	50	26.7	6.9	6.9	2.1×10^8
			30	16	4.2	4.2	1.3×10^8
$t\bar{t}$	360	5	50	0.8	0.2	1.0	0.6×10^6
			30	0.5	0.13	0.65	0.4×10^6

* Higgs is the top priority. The CEPC will commence its operation with a focus on Higgs.

** Detector solenoid field is 2 Tesla during Z operation, 3Tesla for all other energies.

*** Calculated using 3,600 hours per year for data collection.

Main Timelines of CEPC Accelerator Development



Pre-CDR in 2015

1) CEPC CDR Vol. I, Accelerator

http://cepc.ihep.ac.cn/CEPC_CDR_Vol1_Accelerator.pdf

2) CEPC CDR Vol. II, Physics and Detector

http://cepc.ihep.ac.cn/CEPC_CDR_Vol2_Physics-Detector.pdf

3) CEPC Accelerator white paper


to Snowmass21, arXiv:2203.09451

CEPC Video (BIM design)

1) http://cepc.ihep.ac.cn/Qinhuang_Island.mp4

2) <http://cepc.ihep.ac.cn/Huzhou.mp4>

3) <http://cepc.ihep.ac.cn/Changsha.mp4>



Progress report in 2016



CEPC CDR Released (2018.11)



CDR Accelerator and Detector/Exp. in 2028

CEPC Accelerator IARC Meeting 2019-2022

International Accelerator Review Committee (IARC) under IAC

The 2019 CEPC International Accelerator Review Committee

Review Report

December 2, 2019

The 2021 CEPC International Accelerator Review Committee

Review Report

May 19, 2021

2021 Second CEPC IARC Meeting

IARC Committee

October 20th, 2021

2022 First CEPC IARC Meeting

IARC Committee

June 17th, 2022



Nov. 2019: <https://indico.ihep.ac.cn/event/9960/>

May, 2021: <https://indico.ihep.ac.cn/event/14295/>

October, 2021: <https://indico.ihep.ac.cn/event/15177/>

June, 2022: <https://indico.ihep.ac.cn/event/16801/>

After the completion of CEPC CDR in Nov. 2018, since the first CEPC IARC meeting in **2019**, there has been **toally 4 IARC meetings till 2022**, with each meeting a carefully written IARC report, which are very helpful for CEPC accelerator in TDR phase and beyond.

All IARC reports (**2019-2022**) on IAC2022 Meeting Indico:

<https://indico.ihep.ac.cn/event/17996/page/1415-materials>

The Committee congratulates the CE last months and presented at this me R&D of the hardware components lool the table of parameters for the high-l and components for all accelerator sy lider.

A total of 24 talks were presented on a variety of topics. The charges to CEPC IARC for this meeting are:

1. For the TDR, how are the accelerator design and the technology R&D progress towards the TDR completion at the end of 2022. Are there any important missing points in the accelerator design and optimization?
2. based on CEPC TDR design, the CEPC dedicated key technology R&D status and the technologies accumulated from the other IHEP responsible large-scale accelerator facilities, such as HEPs, could the CEPC accelerator group start the TDR editorial process and EDR preparation?
3. with the new progresses between CEPC and FCCee possible synergy and the continuing collaboration with SuperKEKB, are there more suggestions on the next steps of international collaborations?



CEPC Project Development

X. Lou

- **TDR has been completed** (review + revision) to be released in 2023
- CAS is planning for the 15th 5-years plan for large science projects, and a steering committee has been established, chaired by the president of CAS
- **High energy physics**, as one of the 8 groups, has been working on this for a year:
 - Setting up rules and the standard(based on scientific and technological merits, strategic value and feasibility, R&D status, team and capabilities, etc.), established domestic and international advisory committees
 - Collected 15 proposals and selected 9, based on the above-mentioned standard
 - Evaluations and ranking by committees after oral presentations by each project
- **CEPC is ranked No. 1, with the smallest uncertainties, by every committee**
- A final report will be submitted to CAS for consideration





IHEP International Assessment Sept.20-24, 2023)

International Assessment of the Institute of High Energy Physics

Preliminary Draft Report

September 20-24, 2023, IHEP, Beijing, China

Ursula Bassler, Roger Blandford, Andrew Glen Cohen, Cristinel Diaconu, Georges El Fakhri, Angeles Faus-Golfe, Wolfgang Parak, Harald Reichert, Yang Ren, Ian Shipsey, W. Michael Snow, Hans Weise, Harry Westfahl Jr., Frank Zimmermann.

6. CEPC Accelerators

	A+	A	B	C	D
Overall ranking	X				
Is the scientific goal(s) well defined, significant, and credible?	X				
Is there a clear and credible research and R&D plan to realize the scientific goal(s)?	X				
How has the program performed over the last 5 years?	X				
Is the progress of research, R&D and personnel development going according to the plan?		X			
Are the research resources, e.g. funding and laboratories, adequate to support the R&D?		X			