



# CEPC Detector **Mechanical integration**

Ji Quan



中国科学院高能物理研究所  
*Institute of High Energy Physics*  
*Chinese Academy of Sciences*

# Content

- Introduction
- Requirements
- **Technical challenges**
- **Comparison and selection of different schemes**
- **Overall installation concept design**
- Research team
- Summary and working plan

# Introduction

## CEPC Detector Mechanical integration : (R&D content)


1. Draw and optimize the overall mechanical layout drawing  
Based on the design requirements of the sub-detectors and its electronics
2. Design and optimize the connection structure between the sub-detectors  
Based on (After have completed) each sub-detectors structure design
3. Plan and optimize installation steps for each sub-detector
4. Plan and optimize configuration of the auxiliary equipment between the detectors and the experiment room  
layout and lifting capacity , etc. (Underground experiment room)
5. Others (underground auxiliary room , ground room)

## Overall Design Progress :


1. Initial mechanical overall layout drawing
2. Initial configuration drawing between the detectors and the underground experiment room
3. Basic frame structure design of the sub-detectors

# Introduction

## Mechanical integration progress : Initial Size distribution




Further optimization and improvement are needed



# Introduction

Mechanical integration progress : Configuration drawing between the detectors and the experiment room




Installation location :  
**Collision point**

# Introduction

Total weight :  
≈ 6000 t


Yoke : ≈ 3800 t  
Magnet : ≈ 265 t  
HCAL : ≈ 1780 t



# Requirements

Minimum gap principle :  
As small as possible


Gap between sub detectors :  
Installation gap :  $\leq 10\text{mm}$




# Requirements

## Connection design :

The design of the connection structure should follow the principle of proximity connection



- Barrel Yoke : **Fixed on the** Base
- Magnet : **Fixed on the** Barrel Yoke
- Barrel HCAL : **Fixed on the** Barrel Yoke
- Barrel ECAL : **Fixed on the** Barrel HCAL
- TPC+OTK : **Fixed on the** Barrel ECAL
- ITK : **Fixed on the** TPC
- Beampipe(Vertex and LumiCal) : **Fixed on the** ITK
- End-cap ECAL+OTK : **Fixed on the** Barrel HCAL
- End-cap HCAL : **Fixed on the** Barrel HCAL  
(Auxiliary cylinder or Flange)
- End Yoke : **Fixed on the** Base





# Requirements

## MDI boundary

Consists of 4 channels :

Detection angle :  $8.1^\circ$  ( $\arccos 0.99$ )  
(Before ECAL)


(After ECAL)

ECAL :  $\varnothing 700$  mm

HCAL :  $\varnothing 800$  mm

Yoke :  $\varnothing 1300$  mm



Conical hole and stepped holes are reserved spaces for accelerators



# Technical challenges

In the current mechanical design process, we encounter many technical challenges:

## 1. The installation design of **zero-assist Tools** for Barrel Yoke



Typical installation design :


Assembly must be possible with the help of the auxiliary tooling

If there are no auxiliary fixtures, how can the 12 modules be assembled together?  
And its assembly accuracy is very high

# Technical challenges

In the current mechanical design process, we encounter many technical challenges:

## 2. Processing of thin-walled beryllium pipe



Size of outer Be pipe: 0.15 X 170 mm

Size of inner Be pipe: **0.20 X 220mm**




Processing capability : 0.2 X 100 mm

Development of longer beryllium pipe technology is required

# Technical challenges

In the current mechanical design process, we encounter many technical challenges:

## 3. Connection between the Acc MDI component and the Be beampipe



This is a connection design that **cannot be operated** using conventional methods

**Technical difficulties :**

leak rate :  $2.66 \times 10^{-11} \text{ Pa} \cdot \text{m}^3 / \text{s}$








**Need to improve and develop current technology**

**Pillow seal can be used for remote vacuum automatic connection**

# Comparison and selection of different schemes

Installation scheme design starts from the yoke


Comparison and Selection :




Start with optimizing the structural design of the yoke

# Comparison and selection of different schemes

From the perspective of Muon detector design :



Drawing 1




Drawing 2

Drawing 1 :  
Undetectable blind zones

Drawing 2 :  
No detect blind zones

# Comparison and selection of different schemes


From the perspective of maintenance design :



The  $\mu$  detector can be installed from the side

**Spiral structure :**

Easy to maintain and replace





**Symmetrical structure :**

Almost impossible to maintain and replace

The  $\mu$  detector can be installed from the both end

# Comparison and selection of different schemes

From the perspective of muon detector and mechanical strength :



The more layers of the detector,  
the higher the detection accuracy  
and efficiency

The more layers of the detector,  
the lower the mechanical strength  
and stiffness



Seeking the optimal  
structure and parameters



# Comparison and selection of different schemes

From the perspective of deformation control :

Requirements :

Tolerance :




$$10970 \pm 1$$



Meet : < 1 mm

## Baseline Parameters


(Comparison and selection)




# Comparison and selection of different schemes

From the perspective of deformation control :



Step 1 :




Symmetrical structure




V: Copy of Static Structural 600 juxin  
Total Deformation  
Type: Total Deformation  
Unit: mm  
Time: 1  
2024/8/4 14:04





Self-weight deformation :  
≈ 20.00 mm



Spiral structure



P: Static Structural  
Total Deformation  
Type: Total Deformation  
Unit: mm  
Time: 1  
2024/8/4 19:44




Self-weight deformation :  
≈ 13.00 mm

**Comparison :**  
Symmetrical  
Spiral

# Comparison and selection of different schemes

From the perspective of deformation control :


Step 2 :



# Comparison and selection of different schemes

From the perspective of deformation control :

Step 3 :




# Comparison and selection of different schemes



From the perspective of deformation control :

Step 4 :

The flange bottom is suspended




T: Static Structural 600 12  
Total Deformation  
Type: Total Deformation  
Unit: mm  
Time: 1  
2024/8/4 13:23





Self-weight deformation :  
 $\approx 1.40 \text{ mm}$

**Comparison :**  
Suspended  
Supported

The flange bottom is supported



U: Static Structural 600 juxin  
Total Deformation  
Type: Total Deformation  
Unit: mm  
Time: 1  
2024/8/4 13:24



Self-weight deformation :  
 $\approx 0.6 \text{ mm}$


Meet :  $< 1 \text{ mm}$

# Comparison and selection of different schemes

From the perspective of installation design :

Key : Different structural designs result in different installation designs

**Scheme 1** : Conventional structure



**Shortcomings :**



1. Installation steps are complex  
**Assembly must be possible with the help of the auxiliary tooling**
2. Every step of the installation requires collimation
3. Installation process requires more space and time
4. **Uncontrollable installing accuracy**

# Comparison and selection of different schemes

From the perspective of installation design :

Key : Different structural designs result in different installation designs

**Scheme 2** : Self supporting structure



The whole installation process,  
without any additional auxiliary tools.

# Overall installation concept design


## Overall installation design:

1. Reliability and safety assessment of integral detectors and their connecting structures  
(FEA --- stress and deformation)
2. Overall installation steps
3. Installation sequence of the detectors
4. Modular lifting and integral lifting of components



# Overall installation concept design

## 1. Overall reliability and safety assessment



Simplified computational model

### Key :


Deformation and stress of the Yoke and the connection structure  
(Yes ? No)

### As shown in the left figure:


1. Simplified the simulated connection structure between the yoke, magnet and HCAL
2. Other lighter components are ignored  
These components do not affect the calculation results and overall assessment

# Overall installation concept design

## 1. Overall reliability and safety assessment




Yoke




Connection Ring


Connection Flange and Cylinder



Rear end suspension



End HCAL



Barrel HCAL


Check Yoke, Ring, Flange, Cylinder

# Overall installation concept design

## 1. Overall reliability and safety assessment

L: 桶輻+超导+HCAL简化Static Structural  
Total Deformation 5  
Type: Total Deformation  
Unit: mm  
Time: 1  
2024/8/4 10:00


7.4081 Max  
6.585  
5.7619  
4.9388  
4.1156  
3.2925  
2.4694  
1.6463  
0.82313  
0 Min



Deformation :  
 $\approx 7.37$

L: 桶輻+超导+HCAL简化Static Structural  
Equivalent Stress 3  
Type: Equivalent (von-Mises) Stress  
Unit: MPa  
Time: 1  
2024/8/4 9:59

1637.9 Max  
1455.9  
1274  
1092  
909.97  
727.97  
545.98  
363.99  
182  
0.0070131 Min




Stress :  
 $\approx 1638 \text{ MPa}$

In the middle of the two connections

L: 桶輻+超导+HCAL简化Static Structural  
Total Deformation 7  
Type: Total Deformation  
Unit: mm  
Time: 1  
2024/8/4 10:02


7.365 Max  
6.5514  
5.7378  
4.9242  
4.1106  
3.297  
2.4834  
1.6698  
0.85617  
0.042568 Min



Need improvement and optimization  
(End HCAL)

L: 桶輻+超导+HCAL简化Static Structural  
Total Deformation 6  
Type: Total Deformation  
Unit: mm  
Time: 1  
2024/8/4 10:01

1.4305 Max  
1.2737  
1.117  
0.96028  
0.80354  
0.64681  
0.49007  
0.33333  
0.1766  
0.019863 Min



Deformation :  
 $\approx 1.43$

Stress :  
 $\approx 40.9 \text{ MPa}$

It's safety

# Overall installation concept design

## 2. Overall installation steps

### Note :

Combination guideway is the installation reference, and is pre-aligned with yoke

### The steps are as follows :

#### 1. In the ground room


Complete the assembly work of each sub-detector, including electronics, etc.

#### 2. In the shaft

Each sub-detector is lifted into the underground experimental room through vertical shaft in sequence

#### 3. In the underground experimental room


Assembly the sub-detectors combination guideway and push them into the yoke in sequence



# Overall installation concept design

## 3. Installation sequence of detectors (As shown in the exploded view)

1. Install the barrel sub-detector first, in the following order :  
Yoke, Magnet, HCAL, ECAL, TPC(OTK), ITK, Beampipe(Vertex)
2. Then install the end sub-detectors, in the following order :  
End ECAL(OTK), End HCAL




# Overall installation concept design

## 4. Modular lifting and integral lifting of components : (relates to the design of the shaft and the hoists)


### Modular lifting

heaviest single module  
**≈ 400 t**

Largest single size  
**9050 L X  $\Phi$  8470**




### Integral lifting



# Research team

## Team characteristics:

1. Optimize and configure the engineering design team with the mechanical engineers from the High Energy Institute as the core
2. Resource allocation is comprehensive and reasonable, can complement each other's shortcomings



## Future planning and visioning :

1. Allocate more mechanical engineers to join CEPC R&D as needed
2. There are many cooperative units in conventional fields, but CEPC requires cooperation in special fields
3. We will also seek international cooperation

# Summary and working plan

## Summary

1. Supporting frame structure has been preliminary designed of each sub-detectors
2. The top-level installation design is basically completed, but further feasibility needs to be demonstrated



# Summary and working plan

## Working plan

1. Refine the installation plan and connection design of sub detectors
2. Complete the layout of **the underground** experimental room and its auxiliary room (as soon as possible)
3. Complete the layout of **the ground** room



# Thank you for your attention!



中国科学院高能物理研究所  
*Institute of High Energy Physics*  
*Chinese Academy of Sciences*