




Asian School on Superconductivity and Cryogenics for Accelerators (ASSCA 2025)

# Cryogenic Engineering in SHINE

Prof. Ouyang Zhengrong  
ShanghaiTech University  
([ouyangzhr@shanghaitech.edu.cn](mailto:ouyangzhr@shanghaitech.edu.cn))



**SHINE**

March 28<sup>th</sup>, 2025

# Outline





- **1. Overview of Cryogenic Engineering**
  - Introduction of Cryogenic
  - Introduction of Engineering
  - Overview of Cryogenic system
- **2. Case study - SHINE project**
  - Introduction of SHINE cryogenic system
  - Engineering experience of SHINE cryogenic system
- **3. Lessons Learned**
- **4. Outlook and Summary**

**SHINE**

# 1. Overview of Cryogenic Engineering

## ➤ What is Cryogenic?



**SHINE** ➤ In this lecture we focus on cryogenic >100W@1.8K-4.5K: **Cryoplant**

# 1. Overview of Cryogenic Engineering


- ✓ **Cryogenic engineering** primarily involves technologies related to the production, maintenance, and application of extremely cold temperatures, typically below **120 K**). Key technical aspects include:
  - **Cryogenic Refrigeration & Liquefaction** – Technologies like **Stirling cycles**, **Gifford-McMahon (GM) coolers**, **pulse tube**, and **Joule-Thomson Bryton expansion** for cooling and liquefying gases (e.g., nitrogen, oxygen, **helium**, hydrogen).
  - **Cryogenic Fluid Storage & Handling** – Insulation techniques (**vacuum jackets**, **multilayer insulation (MLI)**, **superinsulation**) and specialized containers (**Dewar flasks**, **cryostats**) to minimize heat leakage.
  - **Thermal Management & Heat Transfer** – Studying **cryogenic heat exchangers**, **counterflow designs**, and **Kapitza resistance** to optimize cooling efficiency.

**SHINE**

# 1. Overview of Cryogenic Engineering




- What is Engineering? In a full life cycle perspective.



# 1. Overview of Cryogenic Engineering



- **What is Engineering? In a R&D perspective (V-shaped development)**




**SHINE** ➤ Cryogenic Engineering involves lots of development-verification iterations

# 1. Overview of Cryogenic Engineering



➤ What is the combination of “Cryogenic” and “Engineering” ?



**SHINE**

➤ Cryogenic Engineering is complicated and takes long time to build

# 1. Overview of Cryogenic Engineering



- Cryogenic Engineering is to Construct the cryoplant following the Blueprint



Blueprint



Cryo  
plant



Construction


**SHINE**

- Cryogenic Engineering is to **Turn your dreams into reality**




# 1. Overview of Cryogenic Engineering

## ➤ What does a cryogenic system consist of?




# 1. Overview of Cryogenic Engineering

## ➤ What does a cryogenic system consist of?



# 1. Overview of Cryogenic Engineering


## ➤ What does a cryogenic system consist of?



# 1. Overview of Cryogenic Engineering



- 纸上得来终觉浅，绝知此事要躬行。 *Real understanding comes through lived **experience***



**SHINE** ➤ We take **SHINE** real project to share the experience of Cryogenic Engineering

# Outline



- **1. Overview of Cryogenic Engineering**
  - Introduction of Cryogenic
  - Introduction of Engineering
  - Overview of Cryogenic system
- **2. Case study - SHINE project**
  - Introduction of SHINE cryogenic system
  - Engineering experience of SHINE cryogenic system
- **3. Lessons Learned**
- **4. Outlook and Summary**


**SHINE**

# End users of SHINE cryogenic system





1

Cryomodules Operation



2




SC Undulators Operation




3

SHINE

Test of Cryomodules (components and assembled)




# Function of SHINE cryogenic system



- 1. Provide adequate cryogenic cooling to the linac consists of SRF cavities;
- 2. Supply cryogenic cooling to the superconducting undulator lines
- 3. Fulfill the cryogenic requirements from the SHINE SRF test facility

**SHINE**

# SHINE cryogenic architecture






# SHINE cryogenic system capacity



Cryoplants	Numbers	Total Heat loads @ Temperature			Status
Accelerator cryoplant (ACCP)	3	12kW@2K	4.5kW@4.5K	45kW@40K	Under construction
Undulator Cryoplant (UNCP)	1	500W@4.4K?		26kW@60K?	To be specified
Test Facility Cryoplant (TFCP)	1	1kW@2K	350W@4.5K	3.75kW@40K	Under operation


# SHINE cryogenic system layout




**SHINE**

- 2 Cryo-stations are located in the two ends of SC linac

# Overview- TFCP P&ID




# Overview- TFCEP layout




## Cryoplant system

- Warm Compressor Station
- Oil Removal System
- Cold box
- Dewar
- Helium Analysis
- Regeneration skid
- Process Pumps

# Overview – general target



# Overview- Installation and commissioning Progress



- ★ 2020.10.30 First drop of LHe
- ★ 2020.12.02 First arrival of 2K
- ★ 2021.04.09 350W@2K Acceptance
- ★ 2021.06 Cryomodule first arrival to 2K
- ★ 2021.06.25 Cryoplant cold power reached 1kW@2K
- ★ 2021.06.30 1kW@2K Acceptance

# SRF test facility cryoplant status



- The cryogenics system for SHINE SRF test facility has turned into operation since 07.2021.
- Series tests including **horizontal test**, **vertical test**, **magnet test**, **superconducting undulator test** have been carried out to support the SHINE SRF developments.



1kW@2K Cold box



Cryogenic distribution in No.1 test hall



CDS in No.2 test hall

# SHINE accelerator cryogenic architecture





Cryoplat

CDS and 2K CB


SRF Linac

SHINE






# SHIEN ACCP cryogenic process overview




SHINE

# Cooling down process


## 1. Slow cooldown: 300K → 45K




## 2. Fast cooldown: 45K → 4.5K



## 3. Pumpdown: 4.5K → 2K



# Process design of accelerator cryogenic system



ORIGIN PAGE


2K cold box

SHINE


WCS & 4.5K cold box

He flow direction


# Process design of accelerator cryogenic system




# Process design of accelerator cryogenic system



# Process design of accelerator cryogenic system





# Cryo-station at No. 1 Shaft






➤ Two accelerator cryoplants with 4kW@2K will be installed

# Cryo-station at No. 1 Shaft






# Cryo-station at No. 2 Shaft



- 1 accelerator cryoplant
- 1 test facility cryoplant
- 1 undulator cryoplant

# Cryo-station at No. 2 Shaft



# Outline



- **1. Overview of Cryogenic Engineering**
  - Introduction of Cryogenic
  - Introduction of Engineering
  - Overview of Cryogenic system
- **2. Case study - SHINE project**
  - Introduction of SHINE cryogenic system
  - Engineering experience of SHINE cryogenic system
- **3. Lessons Learned**
- **4. Outlook and Summary**

**SHINE**



# Specification

**SHINE**

# Technical specification

- Codes and Norms
- Site condition / Utility interfaces
- **Performance**
- Key component (**WCS and Cold box**)
- Spare parts
- Control
- Instrumentation, interlocks and electrical design
- Requirements on design, manufacture and mounting
- **Test**
- Quality management
- **Documentation**

**SHINE**

**SHINE CONTRACT - Appendix II  
TECHNICAL SPECIFICATION**

DOCUMENT REF : SHINE-AC/CF/CR-SP-001/2020 - REV1  
Date : 28 February, 2020

*Qiyangzhongrong*  
*JWS*

# SHINE Cryoplant Specification



## TABLE OF CONTENTS

### TABLE OF CONTENTS

- 1 INTRODUCTION
- 2 ABBREVIATIONS AND UNITS
  - 2.1 Abbreviations
  - 2.2 Units
- 3 GENERAL INFORMATION
  - 3.1 Plant Location
  - 3.2 Delivery
  - 3.3 Working Language
  - 3.4 Applicable Documents
    - 3.4.1 Chinese Codes
    - 3.4.2 ASME B&PV Codes
    - 3.4.3 ASME Process Piping Codes
    - 3.4.4 ASTM Standards
    - 3.4.5 Others
- 4 STATEMENT OF WORK AND SUPPLY
  - 4.1 Scope of the supply
    - 4.1.1 Equipment system
    - 4.1.2 Control system
    - 4.1.3 Engineering services
    - 4.1.4 Site services
  - 4.2 Deliverable documentation
  - 4.3 Execution of Order
    - 4.3.1 Responsibilities
    - 4.3.2 Project management
    - 4.3.3 Project meetings and fabrication inspections
    - 4.3.4 Procurement approval
    - 4.3.5 Delivery approval
    - 4.3.6 Procedure in case of Variation
    - 4.3.7 Deviations
    - 4.3.8 Compensation Events
- 5 DESIGN CONDITIONS AND PERFORMANCES
  - 5.1 Process Design Conditions
  - 5.2 Steady-state operation mode

- 5.2.1 Nominal design mode 36
- 5.2.2 Nominal turndown mode 36
- 5.2.3 Single string 2 K standby mode 37
- 5.2.4 Full linac 2 K standby mode 37
- 5.2.5 Single string 4.5 K standby mode 37
- 5.2.6 Full linac 4.5 K standby mode 38
- 5.2.7 Maximum liquefaction mode 38
- 5.2.8 Automation of operation modes 38
- 5.3 Transient operation modes 38
  - 5.3.1 Cool down 38
    - 5.3.1.1 Cool down the ACCP alone 38
    - 5.3.1.2 Cool down the ACCP simultaneously with all CMs 38
    - 5.3.1.3 CMs Cool down from 300 K – 45 K 39
    - 5.3.1.4 CMs Cool down from 45 K – 4.5 K 39
  - 5.3.2 Pump-down 39
    - 5.3.2.1 Pump-down of 2 K CMs 39
    - 5.3.2.2 Re-establishment of 2 K conditions in CMs 39
  - 5.3.3 Warm up 39
    - 5.3.3.1 Warm up the ACCP alone 39
    - 5.3.3.2 Warm up the ACCP with all CMs simultaneously 40
  - 5.3.4 Fault conditions 40
    - 5.3.4.1 RF power trips off 40
    - 5.3.4.2 Loss of beam line vacuum 40
    - 5.3.4.3 Loss of CM insulating vacuum 40
    - 5.3.4.4 Loss of utility power 41
    - 5.3.4.5 Cold compressors exchange during 4.5 K standby mode 41
- 6 WARM COMPRESSOR STATION 42
  - 6.1 General information 42
  - 6.2 Location 42
  - 6.3 Arrangement 43
    - 6.3.1 Compression stages 43
    - 6.3.2 Main helium circuits 44
  - 6.4 Oil lubricated screw compressor skids 44
    - 6.4.1 Compressors 44
    - 6.4.2 Electrical motors 45
    - 6.4.3 Vibrations 45


- 7 4.5 K COLD BOX 36
  - 7.1 General information 36
  - 7.2 Location 36
  - 7.3 Vacuum vessel and insulation system 36
  - 7.4 Heat exchangers 37
  - 7.5 Turbines 37
  - 7.6 Adsorbers 37
  - 7.7 Filters 37
  - 7.8 Phase separator and sub-cooler 38
  - 7.9 Electrical Heaters 38
  - 7.10 4.5 K Cold box interfaces 38
    - 7.10.1 Connections to the WCS 38
    - 7.10.2 Connections to the LHe Dewar 38
    - 7.10.3 Connections to the 2 K cold box 38
    - 7.10.4 Connections to the ambient heater 38
  - 7.11 Acceptance test equipment/cryostat 38
  - 7.12 Gas analysis equipment 38
  - 7.13 Ambient heater 38
  - 7.14 Purge system 38
  - 7.15 Safety valves 38
  - 7.16 Measuring points 38
    - 7.16.1 Connected to the process control system 38
      - 7.16.1.1 Electrical measurement 38
      - 7.16.1.2 Flow measurement 38
      - 7.16.1.3 Level measurement 38
      - 7.16.1.4 Pressure measurement 38
      - 7.16.1.5 Impurity measurement 38
      - 7.16.1.6 Rotation speed measurement 38
      - 7.16.1.7 Temperature measurement 38
    - 7.16.2 Local measuring points 38
      - 7.16.2.1 Electrical measurement 38
      - 7.16.2.2 Pressure measurements 38
      - 7.16.2.3 Vacuum 38
    - 7.16.3 Vacuum 38
    - 7.17 Leak-tightness 38
- 8.5 Acceptance test equipment 73
- 8.6 Electrical Heaters 73
- 8.7 Heat exchangers 73
- 8.8 2K Cold box interfaces 74
  - 8.8.1 Connections to the 4.5 K cold box 74
  - 8.8.2 Connections to the CDS 75
- 8.9 Purge system 76
- 8.10 Safety valves 76
- 8.11 Measuring points 76
  - 8.11.1 Connected to the process control system 76
    - 8.11.1.1 Electrical measurement 76
    - 8.11.1.2 Flow measurement 76
    - 8.11.1.3 Level measurement 76
    - 8.11.1.4 Pressure measurement 77
    - 8.11.1.5 Rotation speed measurement 77
    - 8.11.1.6 Temperature measurement 77
  - 8.11.2 Local measuring points 77
    - 8.11.2.1 Electrical measurement 77
    - 8.11.2.2 Pressure measurements 77
    - 8.11.2.3 Vacuum 77
- 8.12 Leak-tightness 77
- 9 LHE DEWAR 78
  - 9.1 General information 78
  - 9.2 General requirements and design data 78
  - 9.3 Main components 79
- 10 SPARE PARTS 80
  - 10.1 Capital Spare Parts 80
  - 10.2 Operational Spare Parts 81
- 11 1.8K OPERATION MODE 83
  - 11.1 1.8 K cold box 83
    - 11.1.1 General information 83
    - 11.1.2 Process condition 83
- 12 ACCP CONTROL SYSTEM 84
  - 12.1 Overview and Control strategy 84
    - 12.1.1 Manual control of devices from the operator's screen 84
      - 12.1.1.1 Local control screens 84

*Pratt*      *Qiyangzhongrong J*



The technical specification is very important and the **key document** of Engineering

# SHINE ACCP scope



**SHINE**

➤ ALaT scope of equipments

# SHINE ACCP **scope**

- **GHe storage**
- ● **LN2 storage**
- ● **Distribution box**
- ● **Helium recovery**
- ● **Interconnection warm line**
- ● **Interconnection cryogenic transfer line between 4.5K and 2K cold box**
- **Interconnection cryogenic transfer line between 2K cold box and Cryomodules**
- ● **Utilities (IA, LN2,CW)**
- ● **On site installation and supervision**

SHINE

SHINE

- **3x 4.5K Cold boxes (CB) with LN2 precooling and Warm Panel**
- **3x 2K CB including 4x Cold Compressors (CC) from AL-aT and Warm Panel**
- **3 x warm compression station (WCS), including for each:**
  - ○ 1x Very Low Pressure (VLP) compressor
  - ○ 1x Low Pressure (LP) compressor with VFD
  - ○ 1x High Pressure (HP) compressor
  - ○ 1x Oil Removal System (ORS) + 1x Full Flow Dryer + 1x GMP
- **3x Dewar 20 m3 (one per 4.5K CB) with 1x coaxial cryoline + 1x single cryoline**
- **Spare parts for 2 years + critical spares (Cold and Warm Compressors, Turbines)**

ALaT



# SHINE Cryogenic supplier matrix



## Helium Refrigerator



## CDS and auxiliary system



合肥聚能电物理高技术开发有限公司  
Hefei Juneng Electro Physics High-tech Development Co., Ltd



Installation



SHINE


Operation



# SHINE ACCP operation modes



- **There are 8 steady-states operation modes to be calculated:**




-Load of the cold box will adapt to the customer power requirement.

-Some signals from operators or upper control level will be required for mode change (CC starts, operation in full linac, in 4.5K standby...)

# Steady states operation



- On steady states operations :
  - 4 Loads are required function of the operation mode
    - Thermal Shield: TS
    - Cold Intercepts: CI
    - Cavities
    - Liquefaction rate: Dewar



## Steady states operation-2K performance



Load case	Q1 (W)	Conditions at diamond 7 (CB Supply)		Conditions at diamond 11 (CB Return)	
		≥3 bara	4.5K	≥ 0.0256 ba	3.5K
Nominal	4 000	≥3 bara	4.5K	≥ 0.0256 ba	3.5K
Nominal TD	2 649.1	≥3 bara	4.5K	≥ 0.0275 ba	3.43K
2K standby single string	289.1	≥3 bara	4.5K	≥ 0.028 ba	5.06K
2K standby Full linac	575.7	≥3 bara	4.5K	≥ 0.0274 ba	4.05K
4.5K standby Single string	384.6	≥3 bara	4.5K	≥ 1.2 ba	7.0K
4.5K standby Full linac	671.2	≥3 bara	4.5K	≥ 1.2 ba	5.7K
Maximum liquefaction	337	≥3 bara	4.5K	≥ 1.2 ba	5.7K
1.8K	2 083	≥3 bara	4.5K	≥ 0.0125 ba	3.1K

**SHINE**


➤ **186 g/s** of mass flow rate will be used to test the 2K cold compressor




# Design

**SHINE**

# Engineering design of “plant”



# SHINE Layout Design



04



④ Functional area integration planning

03




③ Piping Layout Planning



② Equipment Function Area Planning

02


01



① Space Utilization Planning



# SHINE Layout Design-Piping complex




**SHINE**



# SHINE Layout Design-3D model




## ➤ Cryo-station at Shaft 1




# SHINE Layout Design-3D model



## ➤ Cryo-station at Shaft 1



# Cryo-station at No. 2 Shaft





# Manufacturing

**SHINE**

# SHINE WCS manufacturing



## Performance test of Oil pump

TEST RECORDS		TEST RECORDS																																	
FORM	TESTED ON	FORM	TESTED ON																																
DATE	TIME	DATE	TIME																																
TEST RESULT	TEST RESULT	TEST RESULT	TEST RESULT																																
<p><b>SYMBOLIC AND LEAK TEST</b></p> <p>TEST RESULT: PASS</p>		<p><b>SYMBOLIC AND LEAK TEST</b></p> <p>TEST RESULT: PASS</p>																																	
<p><b>PERFORMANCE TEST</b></p> <table border="1"> <tr> <th>PARAMETER</th> <th>UNIT</th> <th>TEST VALUE</th> <th>DESIGN VALUE</th> </tr> <tr> <td>Flow Rate</td> <td>m³/hr</td> <td>1.5</td> <td>1.5</td> </tr> <tr> <td>Pressure</td> <td>bar</td> <td>10</td> <td>10</td> </tr> <tr> <td>Temperature</td> <td>°C</td> <td>40</td> <td>40</td> </tr> </table>		PARAMETER	UNIT	TEST VALUE	DESIGN VALUE	Flow Rate	m³/hr	1.5	1.5	Pressure	bar	10	10	Temperature	°C	40	40	<p><b>PERFORMANCE TEST</b></p> <table border="1"> <tr> <th>PARAMETER</th> <th>UNIT</th> <th>TEST VALUE</th> <th>DESIGN VALUE</th> </tr> <tr> <td>Flow Rate</td> <td>m³/hr</td> <td>1.5</td> <td>1.5</td> </tr> <tr> <td>Pressure</td> <td>bar</td> <td>10</td> <td>10</td> </tr> <tr> <td>Temperature</td> <td>°C</td> <td>40</td> <td>40</td> </tr> </table>		PARAMETER	UNIT	TEST VALUE	DESIGN VALUE	Flow Rate	m³/hr	1.5	1.5	Pressure	bar	10	10	Temperature	°C	40	40
PARAMETER	UNIT	TEST VALUE	DESIGN VALUE																																
Flow Rate	m³/hr	1.5	1.5																																
Pressure	bar	10	10																																
Temperature	°C	40	40																																
PARAMETER	UNIT	TEST VALUE	DESIGN VALUE																																
Flow Rate	m³/hr	1.5	1.5																																
Pressure	bar	10	10																																
Temperature	°C	40	40																																


TEST RECORDS		TEST RECORDS																																	
FORM	TESTED ON	FORM	TESTED ON																																
DATE	TIME	DATE	TIME																																
TEST RESULT	TEST RESULT	TEST RESULT	TEST RESULT																																
<p><b>SYMBOLIC AND LEAK TEST</b></p> <p>TEST RESULT: PASS</p>		<p><b>SYMBOLIC AND LEAK TEST</b></p> <p>TEST RESULT: PASS</p>																																	
<p><b>PERFORMANCE TEST</b></p> <table border="1"> <tr> <th>PARAMETER</th> <th>UNIT</th> <th>TEST VALUE</th> <th>DESIGN VALUE</th> </tr> <tr> <td>Flow Rate</td> <td>m³/hr</td> <td>1.5</td> <td>1.5</td> </tr> <tr> <td>Pressure</td> <td>bar</td> <td>10</td> <td>10</td> </tr> <tr> <td>Temperature</td> <td>°C</td> <td>40</td> <td>40</td> </tr> </table>		PARAMETER	UNIT	TEST VALUE	DESIGN VALUE	Flow Rate	m³/hr	1.5	1.5	Pressure	bar	10	10	Temperature	°C	40	40	<p><b>PERFORMANCE TEST</b></p> <table border="1"> <tr> <th>PARAMETER</th> <th>UNIT</th> <th>TEST VALUE</th> <th>DESIGN VALUE</th> </tr> <tr> <td>Flow Rate</td> <td>m³/hr</td> <td>1.5</td> <td>1.5</td> </tr> <tr> <td>Pressure</td> <td>bar</td> <td>10</td> <td>10</td> </tr> <tr> <td>Temperature</td> <td>°C</td> <td>40</td> <td>40</td> </tr> </table>		PARAMETER	UNIT	TEST VALUE	DESIGN VALUE	Flow Rate	m³/hr	1.5	1.5	Pressure	bar	10	10	Temperature	°C	40	40
PARAMETER	UNIT	TEST VALUE	DESIGN VALUE																																
Flow Rate	m³/hr	1.5	1.5																																
Pressure	bar	10	10																																
Temperature	°C	40	40																																
PARAMETER	UNIT	TEST VALUE	DESIGN VALUE																																
Flow Rate	m³/hr	1.5	1.5																																
Pressure	bar	10	10																																
Temperature	°C	40	40																																

TEST RECORDS		TEST RECORDS																																	
FORM	TESTED ON	FORM	TESTED ON																																
DATE	TIME	DATE	TIME																																
TEST RESULT	TEST RESULT	TEST RESULT	TEST RESULT																																
<p><b>SYMBOLIC AND LEAK TEST</b></p> <p>TEST RESULT: PASS</p>		<p><b>SYMBOLIC AND LEAK TEST</b></p> <p>TEST RESULT: PASS</p>																																	
<p><b>PERFORMANCE TEST</b></p> <table border="1"> <tr> <th>PARAMETER</th> <th>UNIT</th> <th>TEST VALUE</th> <th>DESIGN VALUE</th> </tr> <tr> <td>Flow Rate</td> <td>m³/hr</td> <td>1.5</td> <td>1.5</td> </tr> <tr> <td>Pressure</td> <td>bar</td> <td>10</td> <td>10</td> </tr> <tr> <td>Temperature</td> <td>°C</td> <td>40</td> <td>40</td> </tr> </table>		PARAMETER	UNIT	TEST VALUE	DESIGN VALUE	Flow Rate	m³/hr	1.5	1.5	Pressure	bar	10	10	Temperature	°C	40	40	<p><b>PERFORMANCE TEST</b></p> <table border="1"> <tr> <th>PARAMETER</th> <th>UNIT</th> <th>TEST VALUE</th> <th>DESIGN VALUE</th> </tr> <tr> <td>Flow Rate</td> <td>m³/hr</td> <td>1.5</td> <td>1.5</td> </tr> <tr> <td>Pressure</td> <td>bar</td> <td>10</td> <td>10</td> </tr> <tr> <td>Temperature</td> <td>°C</td> <td>40</td> <td>40</td> </tr> </table>		PARAMETER	UNIT	TEST VALUE	DESIGN VALUE	Flow Rate	m³/hr	1.5	1.5	Pressure	bar	10	10	Temperature	°C	40	40
PARAMETER	UNIT	TEST VALUE	DESIGN VALUE																																
Flow Rate	m³/hr	1.5	1.5																																
Pressure	bar	10	10																																
Temperature	°C	40	40																																
PARAMETER	UNIT	TEST VALUE	DESIGN VALUE																																
Flow Rate	m³/hr	1.5	1.5																																
Pressure	bar	10	10																																
Temperature	°C	40	40																																

## The assembly of the compressor body was completed on March 20,



## April 1, 2021, motor tests finished



# SHINE WCS manufacturing - Inspection



**Screw compressor test record**

\* General information ;  
 Item No. \_\_\_\_\_  
 Report No. \_\_\_\_\_

**Screw Compressor test results**

\* General information ;  
 Item No. : C22500  
 Report No. : \_\_\_\_\_ SURVEYOR

**Screw compressor test record**

\* General information ;  
 Item No. \_\_\_\_\_  
 Report No. \_\_\_\_\_

**Screw Compressor test results**

\* General information ;  
 Item No. : C23400  
 Report No. : 2021232A SURVEYOR

**Screw compressor test record**

\* General information ;  
 Item No. \_\_\_\_\_  
 Report No. \_\_\_\_\_

**Screw Compressor test results**

\* General information ;  
 Item No. : C25100  
 Report No. : 2021233 SURVEYOR

**Screw Compressor test results**

\* General information ;  
 Item No. : C25100  
 Report No. : 2021233 SURVEYOR

\* Performance test ;

Standard	Actual	Judgment	Criteria
Capacity [m <sup>3</sup> /h] : 7448.6	7630.1 ( 102.4 % )	Accepted	95% and r
Kilowatts [kW] : 535.8	536.0 ( 100.0 % )	Accepted	105% or le

\* Mechanical running test ;

Allowable Maximum	Actual	Judgment
Temp. of rotor casing [°C] : 73	≥ 51	Accepted
Temp. of bearing head [°C] : 73	≥ 53	Accepted
Temp. of shaft seal [°C] : 58	≥ 42	Accepted

\* Vibration and Noise tests ;

Allowable Maximum	Actual	Judgment
Noise [dB](A) : 104	≥ 97.4	Accepted

(Frequency range : 10 - 1000Hz)

Allowable Maximum	Actual	Judgment
Vibration [mm/s RMS] V : 8	≥ 0.2	Accepted
H : 8	≥ 0.2	Accepted
A : 8	≥ 0.2	Accepted




Compressor body completed the factory test in April 2021.

November 2021, the inspection before the compressor unit FAT

# SHINE manufacturing - Cold box



Vacuum vessel production



Installation of the internal support structure



Leak test






**SHINE** ➤ Quality Control - On-site follow-up (4K cold box / 2K cold box vacuum vessels)

# SHINE manufacturing - Cold box Assemble



ID	Task Name	Duration	Start	Finish
19	<b>Long leads (cold box)</b>	<b>415 days</b>	<b>Thu 08/03/18</b>	<b>Wed 09/10/19</b>
20	BAHX	190 days	Mon 23/04/18	Fri 11/01/19
21	Cryogenic valves	120 days	Mon 16/07/18	Fri 26/12/18
22	Cryogenic compressors casing	200 days	Thu 08/03/18	Wed 12/12/18
23	Cryogenic compressors cartridge	300 days	Thu 08/03/18	Wed 01/05/19
24	Cryogenic turbines casing	415 days	Thu 08/03/18	Wed 09/10/19
25	Cryogenic turbines cartridge	415 days	Thu 08/03/18	Wed 09/10/19
26	<b>Cold box internals</b>	<b>120 days</b>	<b>Tue 17/07/18</b>	<b>Mon 31/12/18</b>
27	pressure vessels	65 days	Mon 17/09/18	Fri 14/12/18
28	piping material	50 days	Mon 01/10/18	Fri 07/12/18
29	Cold box top plate / vacuum vessel	120 days	Tue 17/07/18	Mon 31/12/18
30	<b>Warm panel</b>	<b>150 days</b>	<b>Mon 17/09/18</b>	<b>Fri 12/04/19</b>
31	Safety valves	130 days	Mon 17/09/18	Fri 15/03/19
32	Others	70 days	Mon 07/01/19	Fri 12/04/19
33	Control panel	60 days	Tue 23/10/18	Mon 14/01/19
34	<b>Warm compression station</b>	<b>220 days</b>	<b>Mon 19/11/18</b>	<b>Fri 20/09/19</b>
35	Cycle compressors	180 days	Mon 19/11/18	Fri 26/07/19
36	VLP vacuum pump skid	140 days	Mon 19/11/18	Fri 31/05/19






# SHINE manufacturing - Cold box Assemble





SCHXFEL Project - C1348 PM 103(4)

ID	Task Name	Duration	Start	Finish	SCHXFEL Project - C1348 PM 103(4)																							
					1st Quarter	2nd Quarter	3rd Quarter	4th Quarter	1st Quarter	2nd Quarter	3rd Quarter	4th Quarter																
					Nov	Dec	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	
37	Oil Removal Skid	140 days	Mon 11/03/19	Fri 20/09/19																								
38	<b>Cold Box Manufacturing</b>	<b>102 days</b>	<b>Mon 01/04/19</b>	<b>Tue 20/08/19</b>																								
39	Piping isometrics prefabrication	20 days	Mon 01/04/19	Fri 26/04/19																								
40	Pressure vessels preparation	20 days	Mon 01/04/19	Fri 26/04/19																								
41	Assembly on top plate	68 days	Mon 29/04/19	Wed 31/07/19																								
42	Final insulation	2 days	Thu 01/08/19	Fri 02/08/19																								
43	Closing	2 days	Mon 05/08/19	Tue 06/08/19																								
44	Warm panel premanufacturing	45 days	Mon 13/05/19	Fri 12/07/19																								
45	Assembly of warm panel	15 days	Mon 15/07/19	Fri 02/08/19																								
46	Assembly of control panel	15 days	Mon 15/07/19	Fri 02/08/19																								
47	Final tests	10 days	Mon 05/08/19	Fri 16/08/19																								
48	Packing/ preparation for shipment	2 days	Mon 19/08/19	Tue 20/08/19																								
49	<b>Delivery to SC HXFEL site</b>	<b>46 days</b>	<b>Wed 21/08/19</b>	<b>Wed 23/10/19</b>																								
50	Warm compression station	9 wks	Wed 21/08/19	Tue 22/10/19																								
51	Peripherals (local part)	3 wks	Thu 03/10/19	Wed 23/10/19																								
52	Cold box	9 wks	Wed 21/08/19	Tue 22/10/19																								
53	Turbines + casing	2 wks	Thu 10/10/19	Wed 23/10/19																								
54	<b>Site works</b>	<b>219 days</b>	<b>Wed 23/10/19</b>	<b>Mon 24/08/20</b>																								
55	Installation work (client responsibility)	64 days	Wed 23/10/19	Mon 20/01/20																								



# SHINE-Cryo-station 1-CDS

## ➤ Cryogenic transfer line manufacturing






# Installation

**SHINE**

# SHINE cryogenic system construction schedule



**SHINE**

# SHINE installation - Cold box

Transportation and handling **simulation** in advance



**SHINE**

**Weight : 60t**

**L\*W\*H : 15m\*4.5m\*4.2m**

# SHINE installation - Cold box positioning



SHINE

# SHINE installation - Piping

## Pre-installation

- 3D model guidance for installation



- Material Preparation
- Pipe routing
- Collision detection
- Construction arrangements



# SHINE installation - Piping



## Quality check during installation



- Material check
- Cleanness check
- Welding check
- After welding check
- Etc.



SH



# SHINE installation - Piping



## Test after installation



Pressure test



Cleanness test




Leak test

Each pipe need to be tested after installation. Only if the radiation detection , pressure test , cleanness test and leak test etc. were passed, the pipe could be used.

# SHINE installation



3D Model



Photos



**SHINE**

# SHINE installation



3D Model




Photos




**SHINE**

# SHINE Cryogenic system construction



B2 in No.1 Shaft




2K cold boxes (X2) & Distribution box (X3) installation done

1<sup>st</sup> WCS commissioning finished

# SHINE 1<sup>st</sup> Cryoplant

## Cryoplant installation milestones




- 2020.03 Contract with ALAT
- 2021.07 BDR1/BDR/DDR1/DDR2 Design fixed
- 2022.06 1<sup>st</sup> train of equipment arrived at site
- 2023.04 WCS1 MAT
- 2023.04 2K CB installation finished
- 2023.05 4K CB MAT
- 2024.01 4K CB & 2K CB final connection

# SHINE

## Installation Progress



1<sup>st</sup> train of WCS installation finished at early April, 2023.



# SHINE

## Installation Progress-WCS



Equipment location



Equipment erection




Insulation installation

# SHINE

## Installation Progress-4K CB

1<sup>st</sup> train of 4K CB installation finished at early June, 2023.






# SHINE

## Installation Progress-4K CB



Location of 4K CB



Main process pipe installation



Main components installation

Size: nearly

20000mm\*5000mm\*5000mm

Weight:


Nearly 90tons




# Commission

**SHINE**

# SHINE Commission




- 2023.04 WCS commission start
- 2023.06 4K CB pre-commission start
- 2022.07 WCS Performance test
- 2023.09 Warm circulation
- 2023.12 1st drop of liquid ( 4.5K)
- 2024.01 4K & 2K cold box finnal connection
- 2024.02 1st 2K acheive



# SHINE ACCP Train 1 4.5K cold box commissioning



Main steps	Pre Commissioning activities					Commissioning activities		
	Power and Network config.	Electrical loop checks	ORS and ads. drying	Leak tests and conditioning	Compressor start and Warm sequences tests	Turbine installation	Cold sequences testings and Tuning	Performance tests and customer training



2 months has been spent in the warm circulation to remove the particles in the system, especially to the turbine filter

SI

# SHINE Commission - 4.5K cold box




Adsorber regeneration



Dummy Turbine install

08.28

warm  
circulation  
Turbine&filter  
cleaniness check



HP : 1.8PPM N2  
WP : 0.5PPM N2

10.20

Pre-comm : 4 m  
Circulation : 3 m


→11.21 Pre-comm  
finish

**NO.11**

Warm circulation

11.21

07.20




Adsorber  
regeneration

Conditioning

Dumm turbine install

loop check



Purification




Particles found

Oil contents→Re-circulation  
T2 check→Turbine install



**SHINE**

# ACCP2-4.5 K cold box




日期: 2024.10.18 ID: 1024101801 A012001	位置: 过滤器检查记录 操作: 检查	位置: 过滤器检查记录 操作: 检查	位置: 过滤器检查记录 操作: 检查	位置: 过滤器检查记录 操作: 检查
日期: 2024.10.21 ID: 1024102101 A012001	位置: 过滤器检查记录 操作: 检查	位置: 过滤器检查记录 操作: 检查	位置: 过滤器检查记录 操作: 检查	位置: 过滤器检查记录 操作: 检查
日期: 2024.10.22 ID: 1024102201 A012001	位置: 过滤器检查记录 操作: 检查	位置: 过滤器检查记录 操作: 检查	位置: 过滤器检查记录 操作: 检查	位置: 过滤器检查记录 操作: 检查
日期: 2024.10.23 ID: 1024102301 A012001	位置: 过滤器检查记录 操作: 检查	位置: 过滤器检查记录 操作: 检查	位置: 过滤器检查记录 操作: 检查	位置: 过滤器检查记录 操作: 检查
日期: 2024.10.24 ID: 1024102401 A012001	位置: 过滤器检查记录 操作: 检查	位置: 过滤器检查记录 操作: 检查	位置: 过滤器检查记录 操作: 检查	位置: 过滤器检查记录 操作: 检查
日期: 2024.10.25 ID: 1024102501 A012001	位置: 过滤器检查记录 操作: 检查	位置: 过滤器检查记录 操作: 检查	位置: 过滤器检查记录 操作: 检查	位置: 过滤器检查记录 操作: 检查
日期: 2024.10.26 ID: 1024102601 A012001	位置: 过滤器检查记录 操作: 检查	位置: 过滤器检查记录 操作: 检查	位置: 过滤器检查记录 操作: 检查	位置: 过滤器检查记录 操作: 检查
日期: 2024.10.27 ID: 1024102701 A012001	位置: 过滤器检查记录 操作: 检查	位置: 过滤器检查记录 操作: 检查	位置: 过滤器检查记录 操作: 检查	位置: 过滤器检查记录 操作: 检查
日期: 2024.10.28 ID: 1024102801 A012001	位置: 过滤器检查记录 操作: 检查	位置: 过滤器检查记录 操作: 检查	位置: 过滤器检查记录 操作: 检查	位置: 过滤器检查记录 操作: 检查
日期: 2024.10.29 ID: 1024102901 A012001	位置: 过滤器检查记录 操作: 检查	位置: 过滤器检查记录 操作: 检查	位置: 过滤器检查记录 操作: 检查	位置: 过滤器检查记录 操作: 检查
日期: 2024.10.30 ID: 1024103001 A012001	位置: 过滤器检查记录 操作: 检查	位置: 过滤器检查记录 操作: 检查	位置: 过滤器检查记录 操作: 检查	位置: 过滤器检查记录 操作: 检查

- Duration of warm circulation : 19 days ( 10.17→11.04 )
- Turns of filter dis/assemble : 10 rounds

Records of filter check

**4K warm circulation done!!!!**

Filter cleanliness check



# SHINE Commission - 4.5K cold box



Turbine installation

First cool down

First drop of  
Liquid Helium

4 Turbines operation





11.23


11.29

12.06

12.11




# SHINE Commission - 4.5K cold box







# SHINE Commission - 4.5K cold box





# SHINE Commission - 2K cold box



# SHINE Commission - 2K cold box

**20240227**

**First reach** nominal mode 2K , mass flow **187g/s** , Inlet temperature 3.5K , CC Margin 14.5%





- **A static mixer** was added before the electrical heater inside the 2K CB in order to reduce the flow instability in case the mass flow rate is higher than **~120g/s** taking the lessons learned in IBS project

**SHINE**

# SHINE Commission - 2K cold box



- Oscillation was observed when the supercritical turbine T4 turned into operation and many different measures have been applied to eliminate such effect in order to reach the nominal performance of the whole cryoplant



# SHINE Commission - 2K cold box





Figure3 : The characteristic temperature changes during cooling down progress

# Commission of CDS at Cryo-station 1



➤ Commission of CDS at Cryo-station 1 had been finished



✓ 5 Channel MTL low heat load, vacuum tight, no frozen

2024年1月23日至30日配合完成管线热循环

2024年2月降温后，五通道真空表现良好

低温工厂 A1管: 1.98E-6Pa  
B2层 C管: 1.63E-6Pa  
B1层 A2管: 2.43E-6Pa

4K冷箱接口 Lake Shore Model 240-BP  
3: 4.5789 K  
4: 18.192 K

降温后，五通道 2K回路升温小


✓ First cool down of CDS verified the design and control ;  
✓ **First achieve 2K in the user side (feed-cap - test box).**

4K CB, 2K CB, 低温工厂, B2层, B1层, 注入器隧道, 直线加速器隧道

IV85200自动  
PT85210 0.03 bar IV85200 ON PT85200 2885  
TE85201

# Commission of CDS at Cryo-station 1

➤ Commission of CDS at Cryo-station 1 had been finished



✓ 19th July Cool down proposal review

1号井注入器降温调试方案

低温分总体传输分配系统

2024年7月19日

SHINE

控制界面

✓ 17th Aug Before cool down check

降温前条件检查与确认

低温分总体传输分配系统

2024年8月17日

SHINE

降温前低温相关工作

序号	检查内容	单位	日期	结果
1	注入器冷却系统检查	控制室	2024.08.17	正常
2	注入器冷却系统压力检查	控制室	2024.08.17	正常
3	注入器冷却系统流量检查	控制室	2024.08.17	正常
4	注入器冷却系统温度检查	控制室	2024.08.17	正常
5	注入器冷却系统液位检查	控制室	2024.08.17	正常
6	注入器冷却系统报警检查	控制室	2024.08.17	正常
7	注入器冷却系统安全联锁检查	控制室	2024.08.17	正常
8	注入器冷却系统启动/停止检查	控制室	2024.08.17	正常
9	注入器冷却系统故障排除检查	控制室	2024.08.17	正常
10	注入器冷却系统维护检查	控制室	2024.08.17	正常

SHINE

✓ Auto PID control was implemented

Preparation | Injector cool down ready

✓ PID control to achieve Inj8 liquid level  $70.5 \pm 0.5\%$ , Inj1:  $75 \pm 1\%$  ;


✓ 2K pressure  $30.9 \pm 0.1 \text{ mbar}$ .

Leak tight problem

# Commission of CDS at Cryo-station 1



➤ Commission of CDS at Cryo-station 1 had been finished



- 7th Sep Sub-atmospheric circuit leak untight was observed
- ✓ Valve tight
- ✓ Leak check and tight
- ✓ Piping disconnection

- ✓ Commission finished in October turned into operation;
- ✓ **Since 18th Oct, long term continues stable operation more then 9 weeks to support SRF commission.**

**Liquid level  $\pm 1\%$  , Pressure stability  $\pm 0.1\text{mbar}$ .**



# Commission of CDS at Cryo-station 1

➤ Cryogenic transfer line performance had been tested

	制冷量	阀箱	低温管线
SHINE 1号井	8 kW@2 K	3	630 m
E-XFEL	4 kW@2 K	2	340 m
LCLS II	8 kW@2 K	2	255.2 m

SHINE	2K回路	漏热 W/m	设计值 W/m
五通道	4.5K供+	0.45	< 0.8
六通道	2K回气	0.41	




同类装置	2K回路	每米漏热 W/m
EXFEL	4.5K供+	1.57
LCLS II	2K回气	1.25

SHINE	回路	漏热 W/m	设计值 W/m
五通道	冷隔段回气	0.126	0.3
	冷屏	5.10	7.8
六通道	冷隔段	0.564	0.6
	冷屏	5.15	7.8

2 ACCPs



实测指标满足设计指标



# Outline



- **1. Overview of Cryogenic Engineering**
  - Introduction of Cryogenic
  - Introduction of Engineering
  - Overview of Cryogenic system
- **2. Case study - SHINE project**
  - Introduction of SHINE cryogenic system
  - Engineering experience of SHINE cryogenic system
- **3. Lessons Learned**
- **4. Outlook and Summary**

**SHINE**

# 3. Lessons learned



## Installation and commissioning

- Detailed communication with construction department should be done in advance to avoid misunderstanding.
- Enough manpower and spare parts are necessary if you want to speed up the installation.
- Important Tools(torque machine, leak detector... ) need to be calibrated and checked before using.
- Never relax the quality standards( cleanness., welding...), otherwise you will pay 5 times effort to fixed problems.

## WCS

- Cleanness check and filter check are very important for start-up.
- Purifier is useful especially if you want to save helium during commissioning.
- Oil content of Gas at outlet of ORS need to monitor regularly especially during the first several months of running.
- The N<sub>2</sub> impurity will influence the analyzer's measurement of oil content.
- Pay attention to the cooling water if you want stable operation( water quality, flowmeter type...)


## CB

- Vacuum for CB and cryogenic line need to be start as early as possible if you want to speed up.
- Cleanness of the adsorber filters and turbine inlet filters are very important.
- Warm circulation of the whole system should be done if possible.
- Get the Spare turbines ready before you start the cryoplant.

**SHINE**

# SHINE

- During the room temperature cycling stage, there are many activated carbon **particles**/molecular sieve **particles** in the 80K&20K adsorber **filter** and the 4th stage turbine filter
- Solution: It took more than **2 months**, after **11 rounds** of room temperature cycling, multiple cycles of cleaning, which was severely time-consuming. The filling process needs to be improved



# Outlook and Summary



**SHINE**



Your comments are highly appreciated!

Many thanks!