


Characterization, mass tests and first results of the FBK SiPMs for the Photon detection system of DUNE Far Detector HD

Marco Guarise on behalf of the DUNE Collaboration

LIDINE conference 2025, *Hong Kong*

October 22th, 2025



Università
degli Studi
di Ferrara



Contents

- Overview of the DUNE experiment
- DUNE FAR Horizontal Drift detector:
 - SiPMs in the Photon Detection System
- FBK SiPMs
- CACTUS: the quality assurance test setup
 - Features
 - Procedure
 - Tests
- Characterization Results of the FBK spanish production lot
- Conclusions

Deep Underground Neutrino Experiment (DUNE)


DUNE, main physics goals:

- Precise measurement of neutrino oscillation parameters (mass ordering and δ_{CP});
- Study supernova low energy neutrino;
- Physics beyond SM;

EPJC 80 (2020) 978

EPJC 81 (2021) 322

EPJC 801(2021) 423



- New neutrino **beam facility** @ FNAL (LBNF)
- **Near detectors** @ FNAL → measure unoscillated neutrino spectrum & flux constraints
- **Far detectors** @SURF → oscillated neutrino studies

JINST 15 (2020) T08008

JINST 15 (2020) T08010

See C. Cattadori talk “Using Argon for neutrino Physics: the Deep Underground Neutrino Experiment”




DUNE Far Detector

- Located ~1300km from the production site ~1.48 km underground @ Sanford Underground Research Facility in Lead, South Dakota (USA)
- Four 17-kt LAr TPC modules
- Phase I:

- **FD-HD horizontal drift**
- FD-VD vertical drift

FD HD

- 4 drift volumes. Anode-cathode drift distance 3.5 m with $E = 500 \text{ V/cm}$.
- 150 Anode Plane Assemblies (APAs). Each APA consists of three wire planes for charge collection and 10 Photon Detection modules.
- 10 (2m x 12cm) PD modules per APA each composed by 4 X-ARAPUCA supercells.
- A X-Arapuca supercell consists of six $10 \times 10 \text{ cm}^2$ pTP-coated dichroic filters, a 60 cm WLS bar and 48 SiPMs.
- ~300k SiPMs in total.




The DUNE photosensors

- **SiPMs**

- A matrix of single-photon avalanche photodiodes operating in reverse bias above breakdown voltage V_{bd} ;
- Robust, high sensitivity and dynamic range, immune to B field, reduced cost/size;

- **Specifications for DUNE:**

- Quantum efficiency $> 35\%$ for 430 nm light @ 87 K;
- Dimensions compatible w/ ARAPUCA design;
- SiPM + FEE w/ dynamic range 1-2000 photons, even for events far from the ARAPUCA;
- Dark count Rate (DCR) subdominant wrt noise from ^{39}Ar ;
- Cross-talk (CT) and after-pulse (AP) $< 15\%$;
- Durability (> 10 y) and cryoreliability (resistant to multiple cool-downs);
- Few μs recovery time.




The DUNE photosensors

- **SiPMs:**

- Several models tested from two vendors: HPK, FBK; ~50% of FD-HD SiPMs each;
- Chosen models HPK S16517 & FBK NUV-HD-Cryo 3T;
- Mounted in arrays with 6 SiPMs each in common cathode configuration w/ independent anode;



- ~100 SiPMs during selection process;
- ~8k SiPM for ProtoDUNE-HD tested in 2022;
- ~300k SiPM for DUNE FD-HD under test (2023 – ...).
- **Measurements to be performed:**
 - IV curves in FWD and REV bias @ room temperature and LN2 temperature;
 - Thermal stresses resilience;
 - DCR @ LN2 temperature.






HPK tray example

FBK SiPMs

- **FBK NUV-HD-Cryo 3T:**

- Customization for DUNE experiment;
- Based on the NUV-HD Cryo technology;
- 54um cell pitch and 6x6mm² area;
- 3 isolating trenches between cells to decrease cross talk probability;
- Cryo reliability.







Microscope picture


- PDE was measured also at LAr temperature;
- Measurements at TRIUMF (F. Di Capua & F. Gallina) with a dedicated custom setup based on LN2 cooling and monochromator (VERA setup) ;
- No large variations in PDE wrt the one measured at room temperature by FBK

FBK SiPMs

- Preliminary characterization for a batch of 250 sample;
- Measurements at the single sensor level with commercial instrumentation:
 - IV curves Source Meter Unit 10pA precision
 - Custom amplifier for signal acquisition + oscilloscope (min requirements 1GHz band, 5GS/s and 8bit res) half p.e.



The Quality Assurance Test Setup



- Custom setup developed by INFN and Universities of Ferrara and Bologna;
- **Massive tests on the entire FD-1 SiPMs production** to assess:
 - SiPM identity;
 - Failure/mortality rate;
 - Quality assurance;
- Capability: test of 120 SiPMs (20 arrays) in a single session of complete characterization (lasting < 6 h);
- 5 different test sites: Bologna, Ferrara, Granada, Milano Bicocca and Prague;
 - Test rate ≥ 2400 SiPMs/month @ each site

Features:

- 55 liters liquid Nitrogen auto refilling system;
- 120 parallel channels;
- Voltage range [-210;210]V;
- Voltage precision 10mV;
- DC acquisition mode;
- Measured current in range 10nA-3mA;
- AC acquisition mode;
- Programmable threshold DCR from 30ke to 16Me;
- 60cm long translator stage.

Quality assurance procedure




Unique Labview interface → perform each step of the QA tests

A panel shows the final report and if the SiPMs are in specs

Steps & parameters:

- IV@roomT (10min)→(FW) R_q^{RT} + (REV) V_{bd}^{RT} ;
- First LN2 immersion (20min);
- IV@LN2T (10min)→(FW) $R_q^{LN2T_pre}$ + (REV) $V_{bd}^{LN2T_pre}$;
- 2 thermal cycles (1.5h);
- IV@LN2T (10min)→(FW) $R_q^{LN2T_post}$ +(REV) $V_{bd}^{LN2T_post}$;
- Extended IV@LN2T (10min)→ dark current
- DCR@LN2 T (5min)→global-DCR total dark signals, AP, CT + bursts;





Labview interface

Single measurements examples



- LN2 temperature IV:

	Voltage range (V)	Current range	Step (mV)	Fit
Forward curve	0-2	[0.1-3.5]mA	20	Linear
Reverse curve	26-28	[10-500]nA	15	parabolic




FBK production lot



FBK tray


- FBK **Spanish lot** 10500 arrays of 6 SiPM each: 63000 sensors;
- To now 9 deliveries: in total 19 boxes have been produced (8200 boards) and are under test (78% of Spanish lot);
- Mechanical tests;
- Batches shared among CACTUS test sites for electrical characterization;
- **Deliveries 3, 5 and 7 completely tested** (3500 boards= 21000SiPMs) results are in this presentation (33% of Spanish lot).

Results: LN2 V_{bd}




- **Breakdown voltage** distribution at LN2 3rd thermal cycle;
- 600mV total width;
- Behaviour as from vendor;
- SiPMs are in specs;
- Accordance with thermal coefficient ($\sim 26\text{mV/K}$).

Results: LN2 R_q




- **Quenching resistor** distribution at LN2 3rd cycle ;
- Behavior as expected from vendor;
- SiPMs in specs;
- Mean value @LN2 $\sim 267\Omega$;
- Accordance with thermal coefficient ($\sim 1\Omega/K$);
- STD deviation of distribution @LN2 $< 50\Omega$.

Results: thermal cycles



- **Resilience to thermal stresses** has been checked looking at data at the 1st and at the 3rd thermal cycle;
- Distribution of the discrepancies between the breakdown voltage measured at 3rd and at 1st thermal cycle center at 0V;
- V_{bd} Data within errors (50mV)

Results: DCR



- Distribution of the **DCR measured at LN2** in a time window of 120s in a complete dark environment;
- Considering all dark signals (primary, cross talk, afterpulses, bursts);
- Few dark counts are dominant;
- Almost all SiPMs below 200mHz/mm²
- 61 failed sensors with a very high DCR (>1kHz/mm²), rejected.

Bursts: JINST 16 (2021) T10006


Results: DCR



- Sensors with high DCR has been double checked looking at the current in reverse mode at LN2: extended IV curve
- In case of high DCR also the current (integral of the signals) will increase


Normal SiPM: mHz DCR

Current below CACTUS electric noise (20nA)



Anomalous SiPM: KHz DCR

Count ~ 32 kHz $\rightarrow$ Current $\sim \mu$ A



Conclusions



- DUNE SiPMs 300k sensors FD Horizontal Drift;
- FBK NUV-HD-Cryo 3T SiPMs: 150000 sensors to be produced and tested
- CACTUS setup: quality assurance and massive tests (Ferrara, Bologna, Granada, Milano Bicocca, Prague);
- Tests:
 - IV forward + reverse @ Room Temp;
 - IV forward + reverse @ LN2 Temp before and after thermal stresses;
 - Global DCR;
- Tested so far 21000 sensors (33% of Spanish production);
- FBK sensor failure rate due to high DCR 0.2%;
- We plan to end tests during 2026.

Thanks to all involved in CACTUS measurements!


Thank You

Backup slides

FD-1 HD

- 4 drift volumes. Anode-cathode drift distance 3.5 m with $E = 500$ V/cm.
- 150 Anode Plane Assemblies (APAs).
Each APA consists of three wire planes for charge collection and 10 Photon Detection modules.
- 10 (2m x 12cm) PD modules/APA
each composed by 4 X-ARAPUCA supercells.
- A supercell consists of
six 10×10 cm² pTP-coated dichroic filters,
a 60 cm WLS bar and 48 SiPMs.
- ~300k SiPMs in total.


See X-ARAPUCA module



The Quality Assurance Test Setup



Scheme of the setup, featuring modularity, automation, easy replication



Features:

- 55 liters liquid Nitrogen auto refilling system;
- 120 parallel channels;
- Voltage range $[-210; 210]$ V;
- Voltage precision 10 mV;
- DC acquisition mode;
- Measured current in range 10 nA-3 mA;
- AC acquisition mode;
- Programmable threshold DCR from 30 ke to 16 Me;
- 60 cm long translator stage.

The Quality Assurance Test Setup



- **Motherboards + front-end cards (@ warm):**

- 4 motherboards/system;
- 15 front-end cards/motherboard;
- 120 independent channels;
- Current measure/digitalization;
- Signals acquisition.




Motherboards + front-end

- **Cold boards (@LN2):**

- 4 boards;
- 5 arrays/board;
- 120 SiPM;
- Temperature monitor;
- Bias voltage.



Cold boards



Ferrara system



- **Python software** for run-time acquisition and analysis

Single measurements examples




- Room temperature IV:

	Voltage range (V)	Current range	Step (mV)	Fit
Forward curve	0-1	[0.1-3.5]mA	20	Linear
Reverse curve	31.5-33.5	[10-500]nA	15	parabolic




LAr VUV Light Detection

- Excited argon interacts creating excited molecules in singlet and triplet states
- LAr VUV scintillation light ($\lambda = 128 \text{ nm}$) is
 - Abundant (25k photons/MeV @ 500 V/cm)
→ enhance calorimetry, especially at low E
 - Fast (fast component has $\tau = 7 \text{ ns}$)
→ provides event t_0 , crucial for triggering non-beam events
 - Topological
→ Slow/Fast component relative contribution has PID and backg
- Detection of light in DUNE LArTPC
 - VUV photons converted to longer wavelength by photofluorecent compounds (WLS)
 - Visible light is trapped inside a module and a fraction of it is conveyed to photosensors (SiPMs)




Near detectors



Near Detector will be located 574 m downstream (60m underground) of the neutrino beam and will include three detectors:






- **ND-Liquid Argon:** 60 tons fiducial mass liquid Argon Time projection chamber (Lar-TPC)
- **Temporary muon spectrometer (TMS):** muon catcher for forward muons not contained in ND-Lar, 100 planes of 192 scintillator strips each + steel
- **SAND:** trackers + ECAL + magnets

DUNE PRISM:
ND-LAr and TMS will move perpendicular to the beam axis in order to sample multiple fluxes using same detectors



HPK sensors

Failure rate $\sim 0.05\%$ at single SiPM level



DUNE status and plans

The work proceeds in all the fields:

Neutrino beam:

- RF-cavity Cryostat built and arrived at FNAL
- Warehouse-sized cooling unit in construction for PIP-II

ND at FNAL:

- Final review ongoing
- SAND: many activity at LNF for the KLOEtoSAND project
- LAr prototype for ND-Lar in operation

FD at SURF:

- Excavation completed in Dec 2024
- Cryostat 2 (FD-VD) warm structure arrived safely in the Rapid City warehouse, installation will start in 2026
- Cryostat 1 (FD-HD) also arrived at the warehouse, with two accidents (dropped load while downloading in Houston and a truck rollover on the way to Rapid City), installation will start in 2026

ProtoDune:

- Following the safety accident of the 17th of January CERN authorized restart of VD-CRP activities NP02 after completion of few recommendations
- Data analysis protoDune-HD ongoing
- ProtoDune_VD ready to start

