

The CEPC Accelerator EDR Status and Plan

J. Gao

IHEP

On behalf of CEPC-SppC Accelerator team

The 2025 International Workshop on the High Energy Circular Electron Positron Collider (CEPC2025)
November 6-10, 2025, Guangzhou, China



Contents



- **Introduction**
- **CEPC accelerator EDR progress status according EDR plan with milestone**
- **CEPC technology industrial preparations and international collaborations**
- **Summary**




CEPC Higgs Factory and SppC Layout in TDR/EDR

CEPC as a Higgs Factory: **H**, **W**, **Z**, upgradable to **ttbar**, followed by a SppC (a Hadron collider) $\sim 125\text{TeV}$
30MW SR power per beam (upgradable to 50MW) , high energy gamma ray 100Kev \sim 100MeV

CEPC has two detectors





CEPC collider ring (100km)





CEPC booster ring (100km)


CEPC TDR S+C-band 30GeV linac injector



TUNNEL CROSS SECTION OF THE ARC AREA



CEPC/SppC in the same tunnel



Z,W, Higgs and ttbar energies

CEPC Accelerator System Parameters in TDR/EDR

Linac

Parameter	Symbol	Unit	Baseline
Energy	E_e/E_{e+}	GeV	30
Repetition rate	f_{rep}	Hz	100
Bunch number per pulse			1 or 2
Bunch charge		nC	1.5 (3)
Energy spread	σ_E		1.5×10^{-3}
Emittance	ε_r	nm	6.5

Booster

		$t\bar{t}$	H		W	Z	
		Off axis injection	Off axis injection	On axis injection	Off axis injection	Off axis injection	
Circumfer.	km	99.955					
Injection energy	GeV	30					
Extraction energy	GeV	180	120		80	45.5	
Bunch number		35	268	261+7	1297	3978	5967
Maximum bunch charge	nC	0.99	0.7	20.3	0.73	0.8	0.81
Beam current	mA	0.11	0.94	0.98	2.85	9.5	14.4
SR power	MW	0.93	0.94	1.66	0.94	0.323	0.49
Emittance	nm	2.83	1.26		0.56	0.19	
RF frequency	GHz	1.3					
RF voltage	GV	9.7	2.17		0.87	0.46	
Full injection from empty	h	0.1	0.14	0.16	0.27	1.8	0.8

Collider

	Higgs	Z	W	$t\bar{t}$
Number of IPs	2			
Circumference (km)	99.955			
SR power per beam (MW)	30			
Energy (GeV)	120	45.5	80	180
Bunch number	268	11934	1297	35
Emittance $\varepsilon_x/\varepsilon_y$ (nm/pm)	0.64/1.3	0.27/1.4	0.87/1.7	1.4/4.7
Beam size at IP σ_x/σ_y (um/nm)	14/36	6/35	13/42	39/113
Bunch length (natural/total) (mm)	2.3/4.1	2.5/8.7	2.5/4.9	2.2/2.9
Beam-beam parameters ξ_x/ξ_y	0.015/0.11	0.004/0.127	0.012/0.113	0.071/0.1
RF frequency (MHz)	650			
Luminosity per IP ($10^{34} \text{ cm}^{-2} \text{ s}^{-1}$)	5.0	115	16	0.5
Luminosity per IP ($10^{34} \text{ cm}^{-2} \text{ s}^{-1}$) From J. Gao's formula below	5	115	12	0.59


Running scenarios: Higgs 10 years, Z 2 years, W 1 year, ttbar 5 years

Transport lines

Factory of
4 Million Higgs
4 Trillion Z bosons
200 Million W+W- pairs
600K $t\bar{t}$ pairs

$$L_{\text{max}} [\text{cm}^{-2} \text{ s}^{-1}] = 0.158 \times 10^{34} \frac{(1+r)}{\beta_y [\text{mm}]} \sqrt{\frac{R [\text{m}]}{C_Y [\text{mGeV}^3] N_{IP}}} (P_b [\text{MW}] / E [\text{GeV}]^2) e^{\frac{\sqrt{\Phi_p}}{3.22}} (1 + 0.000505 \cdot \Phi_p^2) \quad (\text{J. Gao's formula})$$

for isomagnetic machine with crab-waist collision





CEPC Technical Design Report (TDR) includes:
1) CEPC Accelerator TDR released on Dec. 25, 2023
2) CEPC Detector ref-TDR (reference design) has been completed and reviewed by IDRC in April and Sept. 2025, and will be released in 2025



CEPC Milestones and Timeline



Year	Accelerator human resource	Accumulated accelerator spending Billion RMB
2015	50	-
2018	100	-
2023	200	0.2
2025	300	0.3
2027	500	0.4
2031	2800	9
2035	2500	20



Proposal (2030) for CEPC entering 16th five-year-plan

36.4B RMB
Total construction



CEPC EDR site study and civil engineering design



CEPC kickoff meeting in Sept. 2013

CEPC detector reference design released in Oct. 2025



J. Gao, "The Status of the CEPC Project in EDR", submitted to IJMPA , 2025, arXiv:2505.04663, <https://doi.org/10.48550/arXiv.2505.04663>



CEPC Key System EDR Progresses-1

7

CEPC Accelerator Key System EDR Progresses

- 2025 March 20, CEPC booster magnet automatic fabrication line ready for construction (under construction, to be completed in 2025-2026)
- 2025 April 17, CEPC polarization cathode material and test facility ready for fabrication
- 2025 April 25, CEPC vacuum chamber NEG coating automatic fabrication line ready for construction (under construction, to be completed in 2025-2026)
- 2025 April 28, 650MHz full size cryomodule ready for construction (under construction, to be completed in 2025-2026)
- 2025 Feb. CEPC accelerator survey started (99.955428km)
- 2025 July, CEPC accelerator components, vertical shafts (10) and horizontal access tunnels (12) naming systems are decided
- 2025 July, CEPC booster detailed installation scheme studies started

CEPC Accelerator Key System EDR International Mini Reviews (Required by IARC)

- 2025 April 24, CEPC alignment and installation EDR international mini review
- 2025 May 14,15, CEPC cryogenic system (+650MHz cryomodule) EDR international mini review
- 2025 May 29, CEPC booster dipole and sextupole combined magnet EDR international mini review
- 2025 June 9-10, CEPC MDI EDR international mini review
- 2025 June 9-10, CEPC EDR site geological feasibility study review
- 2025 July 31, CEPC vacuum chamber type EDR international mini review



CEPC Accelerator EDR Key Progresses-2

-2024 Dec 9, CEPC EDR site geological study and civil engineering design tasks Have been assigned to “Power China Hua Dong Engineering Corporation Limited (HDEC)”

-2025 June 9-10, CEPC site geological study and site selection choice review meeting was held and CEPC Xinmi Site of Henan province was recommended as the proposed construction site to Chinese government, and more detailed studies will be completed by the end of 2025.

-2025 Sept . 5, CEPC EDR accelerator and civil engineering cost have been updated.

-2025 Sept. 8, CEPC accelerator/auxiliary facilities TDR/EDR progresses and site geological study/selection/civil engineering design status and progresses have been included in the CEPC Proposal



Preliminary replies to the IARC (2024) report
has been sent to IARC/IAC chairs



CEPC IARC, IDRC and IAC Meetings since EDR

10



CEPC IARC meeting was held from Sept. 18-20, 2024

<https://indico.ihep.ac.cn/event/22311/>



CEPC IARC meeting was held from Sept. 16-19, 2025



The International Detector Review Committee (IDRC) held its inaugural meeting at IHEP, Oct 21-23, 2024, to review the status and plan of Ref-TDR.


<https://indico.ihep.ac.cn/event/23265/>



CEPC IAC meeting in 2024 was held from Oct. 29-30, 2024

<https://indico.ihep.ac.cn/event/23450/timetable/>

CEPC IAC meeting will be held from Nov. 20-21, 2025



CEPC Detector Reference Design Report submitted to arXiv on Oct. 7, 2025
<https://arxiv.org/abs/2510.05260>



CEPC IDRC meeting was held from April 14-16, 2025

<https://indico.ihep.ac.cn/event/25539>

CEPC IDRC meeting was held on Sept. 10, 17 and 24, 2025



2nd IARC EDR Review Meeting Talks (2025)

	Beijing time	Talk time	Speaker	Title	Talk n.	Sep 17th 2025	9:00	25'+5'	Luyang Zhao	Conventional facility and control methods for the tunnel temperature	0	
Sep 16th 2025	9:00	15'	IARC preparation meeting (closed)			Wednesday	9:30	25'+5'	Wen Kang	CEPC booster magnet production line	14	
							10:00	25'+5'	Yongsheng Ma	CEPC vacuum chamber production line	15	
Tuesday	9:05	5'	Yifang Wang	Welcome			10:30	30'	Coffee break			
	9:10	15'	Xinchou Lou	CEPC general status and news	1		11:00	25'+5'	Dapeng Jin	Control system	16	
	9:25	30'+5'	Jie Gao	CEPC Accelerator EDR Status and beyond	2		11:30	25'+5'	Xiaohao Cui	Collimators in the collider rings	17	
	10:00	30'	Coffee break				12:00	25'+5'	Song Jin/Lei Ye	DeepC electronic documentation system	18	
	10:30	25'+5'	RuiGe/Mei Li	Summary of cryogenic system mini review	3		12:30	90'	Lunch			
	11:00	25'+5'	Xiaolong Wang	Summary of alignment mini review	4		14:00	25'+5'	Zusheng Zhou	CEPC high efficiency klystron development	19	
	11:30	25'+5'	Sha Bai/Haoyu Shi	Summary of MDI mini review	5		14:30	25'+5'	Na Wang/Yudong Liu	CEPC collective effects	20	
	12:00	25'+5'	Dou Wang	Summary of booster dipole magnet+sextupole mini review	6		15:00	25'+5'	Zhe Duan	CEPC polarization studies	21	
	12:30	90'	Lunch				15:30	30'	Coffee break			
	14:00	25'+5'	Guangyi Tang	Summary of vacuum chamber mini review	7		16:00	30'	IARC discussion and Q/A with CEPC accelerator speakers (partly closed if needed)			
	14:30	25'+5'	Haijing Wang	CEPC survey and hardward design status	8		17:00	60'	IARC members	Closed session		
	15:00	25'+5'	Xiaolong Wang	Installation procedures of the Booster magnets beam pipe	9	Sep 18th 2025	9:00	25'+5'	Jinhui Chen	Injection/extraction system	22	
	15:30	30'	Coffee break			Thursday	9:30	25'+5'	Jingyu Zhang	CEPC linac injector	23	
	16:00	25'+5'	Yiwei Wang	Solenoid compensation scheme and alternative schemes	10		10:00	25'+5'	Dazhang Li	CEPC plasma injector	24	
	16:30	25'+5'	Daheng Ji	Simulation of injection at commissioning and orbit correction	11		10:30	30'	Coffee break			
	17:00	25'+5'	Yiwei Wang/Bin Wang	Studies of the tolerance to machine errors at all energies	12		11:00	25'+5'	Daheng Ji	HEPS and BEPCII-U commissioning experiences		
							11:30	25'+5'	Jianfeng Liu	Civil engineering design	25	
							12:00	25'+5'	Qingjin Xu	SppC high field magnet dipole development	26	
							12:30	90'	Lunch			
							14:00	90'	IARC discussion and Q/A with CEPC accelerator speakers (partly closed if needed)			
							15:30	30'	Coffee break			
							16:00	120'	IARC members	Closed session		
							18:30	180'	Banquet			
							The talks in red are required by IARC					

The talks in red are required by IARC



CEPC IARC EDR Review Report (2025)

12

Second CEPC IARC EDR Review Report

CEPC IARC EDR Review Committee

19 September 2025

The CEPC Study Group, hosted by the Institute of High Energy Physics (IHEP), has been working on the design and development of a forefront e^+e^- collider as a Higgs factory that can extend to energies corresponding to the production of Z, WW and top-quark pairs, with the upgrade potential to a ~ 100 TeV pp collider. The CEPC represents a grand plan proposed, studied, and to be constructed by Chinese scientists in close collaboration with international partners. The CEPC Accelerator Technical Design Report was released in December 2023, which documents the design, the outcomes of the R&D of key technologies, the technical systems, and the cost estimate of the CEPC e^+e^- collider. Going beyond the accelerator TDR and preparing the CEPC for the construction that may begin in 2027-8, the CEPC Study Group has started the Engineering Design Study for which the outcome will be documented in a formal report (EDR). The CEPC Study Group plans to submit a proposal to the Chinese government requesting the inclusion of the CEPC in the 15th Five Year Plan. The International Accelerator Review Committee (IARC), chaired by Dr. Maria Enrica Biagini (INFN, Frascati) is asked to conduct the review on the development of the CEPC accelerator technical systems within the context of the EDR study. The Committee is specifically asked to review and comment on the following aspects:

1. Have the CEPC accelerator activities been carried out according to the EDR plan?
2. Has the CEPC accelerator team implemented or been addressing the recommendations and suggestions given by the IARC and the IAC in 2024?
3. Are the studies and replies to the concerns of the IARC's and the IAC's concerns satisfactory?
4. Is the overall EDR progress on track since the 2024 review?
5. Are there weak points in the CEPC accelerator EDR program? If so how can they be remedied?
6. Any other issues you notice or any improvements you may suggest.

It is requested that a Committee report responding to these charges be forwarded to the CEPC Steering Committee Chair, Professor Yifang Wang by October 20, 2025.

CEPC accelerator team will continue to work EDR and address the recommendations from IARC towards the goal for construction

1 Executive Summary

The second CEPC IARC EDR Review meeting was held in-person (with a few members joining on Zoom) at IHEP over the period of September 16-19, 2025.

The committee was invited to evaluate the advancement made since last year's review (September 2024) of the Engineering Design Study towards the construction of CEPC. A total of 26 talks were presented on the most challenging topics.

The committee wishes to congratulate the CEPC accelerator team for the excellent progress toward completion of the EDR phase.

The committee appreciated the quality of most of the presentations and was impressed by the achievements shown. The committee was pleased to see that many of the key systems, such as, for example, the high-efficiency klystron R&D, are progressing at full speed and with successful results.

An important change since the previous meeting of the committee is the choice of the site, which represents a major milestone for the project. Many work packages can now become more concrete.


2.5 Key Recommendations

The Committee has issued comments and recommendations for the different topics and presentations, which are given in Section A. The most significant of these recommendations are shown below:

1. (A.3.2.2) Pursue a highly reliable and sustainable CEPC cryogenics system enabling to realize full helium resource recovery and conservation in any major failures in superconducting magnets, RF system operations associated by fundamental infrastructure;
2. (A.4.2.2) Define, build and measure the surface geodetic network; prepare the corresponding geodetic reference frames and the related transformation systems to be used for the civil engineering tender documents, survey layouts and CAD systems;
3. (A.4.2.4) Develop and qualify an automated measurement system and its specific alignment targets to fulfill the alignment requirements in the arcs;
4. (A.5.2) Progress and optimize the MDI region design, after deciding on the compensation scheme, and start prototyping work, especially for the final focus quadrupoles;
5. (A.13.2.2) For conventional facilities, analyze dynamic changes on various timescales to ensure that the necessary stability and environmental condition can be maintained during operation and periods of shutdowns and access;
6. (A.25.2.2) As civil engineering work now concentrates on a specific site, exploit the new opportunities to make rapid progress on the many systems that are closely connected to civil engineering and need site-specific guidelines and parameters.



CEPC EDR Milestones





CEPC Accelerator Parameter in EDR-1

14

Table 1: CEPC parameters in EDR

	Higgs (3T)	Z (2T)		W (3T)	t \bar{t} (3T)
Number of IPs	2				
Circumference (km)	99.955				
Half crossing angle at IP (mrad)	16.5				
Bending radius (km)	10.7				
SR power per beam (MW)	30	30	10	30	30
Energy (GeV)	120	45.5		80	180
Energy loss per turn (GeV)	1.8	0.037		0.357	9.1
Damping time $\tau_x/\tau_y/\tau_z$ (ms)	44.6/44.6/22.3	816/816/408		150/150/75	13.2/13.2/6.6
Piwinski angle	4.88	24.23		5.98	1.23
Bunch number	268	11934	3978	1297	35
Bunch spacing (ns)	553.9	23.1	69.2	184.6	3969.8
[\times 23.08 ns]	24	1	3	8	172
Train gap [%]	55	17		17	58
Bunch population (10 ¹¹)	1.3	1.4		1.35	2.0
Beam current (mA)	16.7	803.5	267.8	84.1	3.3
Phase advance of arc FODO (°)	90	60		60	90
Momentum compaction (10 ⁻⁵)	0.71	1.43		1.43	0.71
Beta functions at IP β_x^*/β_y^* (m/mm)	0.3/1	0.13/0.9		0.21/1	1.04/2.7
Emittance $\varepsilon_x/\varepsilon_y$ (nm/pm)	0.64/1.3	0.27/1.4		0.87/1.7	1.4/4.7
Betatron tune n_x/n_y	445/445	317/317		317/317	445/445
Beam size at IP s_x/s_y (um/nm)	14/36	6/35		13/42	39/113
Bunch length (natural/total) (mm)	2.3/4.1	2.5/8.7		2.5/4.9	2.2/2.9
Energy spread (natural/total) (%)	0.10/0.17	0.04/0.13		0.07/0.14	0.15/0.20
Energy acceptance (DA/RF) (%)	1.6/2.2	1.0/1.7		1.05/2.5	2.0/2.6
Beam-beam parameters χ_x/χ_y	0.015/0.11	0.004/0.127		0.012/0.113	0.071/0.1
RF voltage (GV)	2.2	0.12		0.7	10
RF frequency (MHz)	650				
Harmonic number	216720				
Longitudinal tune n_x	0.049	0.035		0.062	0.078
Beam lifetime (Bhabha/beamstrahlung) (min)	40/40	90/2800		60/195	81/23
Beam lifetime requirement (min)	18	77		22	18
Luminosity per IP (10 ³⁴ cm ⁻² s ⁻¹)	5.0	115	38	16	0.5

Table 2: CEPC main parameters with 50 MW upgrade

	Higgs (3T)	Z (2T)	W (3T)	$t\bar{t}$ (3T)
Number of IPs	2			
Circumference (km)	99.955			
Half crossing angle at IP (mrad)	16.5			
Bending radius (km)	10.7			
SR power per beam (MW)	50			
Energy (GeV)	120	45.5	80	180
Energy loss per turn (GeV)	1.8	0.037	0.357	9.1
Damping time $\tau_x/\tau_y/\tau_z$ (ms)	44.6/44.6/22.3	816/816/408	150/150/75	13.2/13.2/6.6
Piwiński angle	4.88	29.52	5.98	1.23
Bunch number	446	13104	2162	58
Bunch spacing (ns)	277.0	23.1	138.5	2585.0
[$\times 23.08$ ns]	12	1	6	112
Train gap [%]	63	9	10	55
Bunch population (10^{11})	1.3	2.14	1.35	2.0
Beam current (mA)	27.8	1340.9	140.2	5.5
Phase advance of arc FODO ($^\circ$)	90	60	60	90
Momentum compaction (10^{-5})	0.71	1.43	1.43	0.71
Beta functions at IP β_x^*/β_y^* (m/mm)	0.3/1	0.13/0.9	0.21/1	1.04/2.7
Emittance $\varepsilon_x/\varepsilon_y$ (nm/pm)	0.64/1.3	0.27/1.4	0.87/1.7	1.4/4.7
Betatron tune ν_x/ν_y	445/445	317/317	317/317	445/445
Beam size at IP σ_x/σ_y (um/nm)	14/36	6/35	13/42	39/113
Bunch length (natural/total) (mm)	2.3/4.1	2.7/10.6	2.5/4.9	2.2/2.9
Energy spread (natural/total) (%)	0.10/0.17	0.04/0.15	0.07/0.14	0.15/0.20
Energy acceptance (DA/RF) (%)	1.6/2.2	1.0/1.5	1.05/2.5	2.0/2.6
Beam-beam parameters ξ_x/ξ_y	0.015/0.11	0.0045/0.13	0.012/0.113	0.071/0.1
RF voltage (GV)	2.2	0.1	0.7	10
RF frequency (MHz)	650			
Harmonic number	216720			
Longitudinal tune ν_s	0.049	0.032	0.062	0.078
Beam lifetime (Bhabha/beamstrahlung) (min)	40/40	90/930	60/195	81/23
Beam lifetime requirement (min)	20	81	25	18
Luminosity per IP (10^{34} cm $^{-2}$ s $^{-1}$)	8.3	192	26.7	0.8



CEPC Accelerator Parameter in EDR-2

Table 3: CEPC low lum. with 3T detector @ Z for 1st stage running Table 4: CEPC high lum. with 3T detector @Z assuming for 2nd stage running

The Z mode running of the CEPC detector Ref Technical Design Report has been based on the 3T detector magnetic field, and TPC technology has been adopted

	Z (3T)	
Number of IPs	2	
Circumference (km)	99.955	
SR power per beam (MW)	8.7	12.1
Half crossing angle at IP (mrad)	16.5	
Bending radius (km)	10.7	
Energy (GeV)	45.5	
Energy loss per turn (GeV)	0.037	
Damping time $\tau_x/\tau_y/\tau_z$ (ms)	816/816/408	
Piwinski angle	24	
Bunch number	3978	
Bunch spacing (ns)	69.2	
Bunch population (10^{11})	1.22	1.7
Beam current (mA)	233.2	325.0
Phase advance of arc FODO (°)	90	60
Momentum compaction (10^{-5})	0.71	1.43
Beta functions at IP β_x^*/β_y^* (m/mm)	0.2/1.0	0.13/1.0
Emittance $\varepsilon_x/\varepsilon_y$ (nm/pm)	0.092/1.7	0.27/5.1
Betatron tune ν_x/ν_y	445/445	317/317
Beam size at IP σ_x/σ_y (um/nm)	4/42	6/72
Bunch length (natural/total) (mm)	2.1/8.3	2.1/8.8
Energy spread (natural/total) (%)	0.04/0.11	0.04/0.15
Energy acceptance (DA/RF) (%)	1.0/1.9	1.0/2.2
Beam-beam parameters ξ_x/ξ_y	0.0065/0.11	0.0053/0.082
RF voltage (GV)	0.09	0.16
RF frequency (MHz)	650 (2 cell cavity)	
Longitudinal tune ν_s	0.021	0.041
Beam lifetime (Bhabha/beamstrahlung) (min)	120/200	150/180
Beam lifetime requirement (min)	68	
Hourglass Factor	0.97	
Luminosity per IP ($10^{34} \text{ cm}^{-2} \text{ s}^{-1}$)	24	26

	Z	
Number of IPs	2	
Circumference (km)	99.955	
SR power per beam (MW)	30	50
Half crossing angle at IP (mrad)	16.5	
Bending radius (km)	10.7	
Energy (GeV)	45.5	
Energy loss per turn (GeV)	0.037	
Damping time $\tau_x/\tau_y/\tau_z$ (ms)	816/816/408	
Piwinski angle	24.2	29.5
Bunch number	11934	13104
Bunch spacing (ns)	23.1 (17% gap)	23.1 (9% gap)
Bunch population (10^{11})	1.4	2.1
Beam current (mA)	806.9	1345.2
Phase advance of arc FODO (°)	60	
Momentum compaction (10^{-5})	1.43	
Beta functions at IP β_x^*/β_y^* (m/mm)	0.13/1.0	
Emittance $\varepsilon_x/\varepsilon_y$ (nm/pm)	0.27/5.1	
Betatron tune ν_x/ν_y	317/317	
Beam size at IP σ_x/σ_y (um/nm)	6/72	
Bunch length (natural/total) (mm)	2.5/9.3	2.2/10.6
Energy spread (natural/total) (%)	0.04/0.15	0.04/0.15
Energy acceptance (DA/RF) (%)	1.2/1.7	1.2/2.1
Beam-beam parameters ξ_x/ξ_y	0.0045/0.069	0.0046/0.074
RF voltage (GV)	0.12	0.15
RF frequency (MHz)	650 (1 cell cavity)	
Harmonic number	216720	
Longitudinal tune ν_s	0.035	0.040
Beam lifetime (Bhabha/beamstrahlung) (min)	170/95800	120/932
Beam lifetime requirement (min)	77	81
Luminosity per IP ($10^{34} \text{ cm}^{-2} \text{ s}^{-1}$)	50.3	95.2



Table 5: Main Booster parameters at injection energy.

	Unit	<i>tt</i>	<i>H</i>	<i>W</i>	<i>Z</i>	
Circumference	km	99.955				
Beam energy	GeV	30				
Bunch number		35	268	1297	3978	5967
Threshold of single bunch current	μA	8.68	6.3	5.8		
Threshold of beam current (limited by coupled bunch instability)	mA	97	106	100	93	96
Bunch charge	nC	1.1	0.78	0.81	0.87	0.9
Single bunch current	μA	3.4	2.3	2.4	2.65	2.69
Beam current	mA	0.12	0.62	3.1	10.5	16.0
Growth time (coupled bunch instability)	ms	2530	530	100	29.1	18.7
Energy spread	%	0.025				
Synchrotron radiation loss/turn	MeV	6.5				
Momentum compaction factor	10 ⁻⁵	1.12				
Emittance	nm	0.076				
Natural chromaticity	H/V	-372/-269				
RF frequency	MHz	1300				
Harmonic number		433440				
RF voltage	MV	761.0	346.0	300.0		
Betatron tune ν_x/ν_y		321.23/117.18				
Longitudinal tune		0.14	0.0943	0.0879		
RF energy acceptance	%	5.7	3.8	3.6		
Damping time	s	3.1				
Bunch length of linac beam	mm	0.4				
Energy spread of linac beam	%	0.15				
Emittance of linac beam	nm	6.5				

Table 6: Main Booster parameters at extraction energy.

	Unit	<i>x</i>	<i>y</i>		<i>w</i>	<i>z</i>	
		Off axis injection	Off axis injection	On axis injection	Off axis injection	Off axis injection	
Circumference	km	99.955					
Beam energy	GeV	180	120		80	45.5	
Bunch number		35	268	261+7	1297	3978	5967
Maximum bunch charge	nC	0.99	0.7	20.3	0.73	0.8	0.81
Maximum single bunch current	μA	3.0	2.1	61.2	2.2	2.4	2.42
Threshold of single bunch current	μA	91.5	70		22.16	9.57	
Threshold of beam current (limited by RF system)	mA	0.3	1		4	16	
Beam current	mA	0.11	0.56	0.98	2.85	9.5	14.4
Growth time (coupled bunch instability)	ms	16611	2359	1215	297.8	49.5	31.6
Bunches per pulse of Linac		1	1		1	2	
Time for ramping up	s	7.1	4.3		2.4	1.0	
Injection duration for top-up (Both beams)	s	29.2	23.1	31.8	38.1	132.4	
Injection interval for top-up	s	65	38		155	153.5	
Current decay during injection interval		3%					
Energy spread	%	0.15	0.099		0.066	0.037	
Synchrotron radiation loss/turn	GeV	8.45	1.69		0.33	0.034	
Momentum compaction factor	10 ⁻⁵	1.12					
Emittance	nm	2.83	1.26		0.56	0.19	
Natural chromaticity	H/V	-372/-269					
Betatron tune ν_x/ν_y		321.27/117.19					
RF frequency	MHz	1300					
Harmonic number		433440					
RF voltage	GV	9.7	2.17		0.87	0.46	
Longitudinal tune		0.14	0.0943		0.0879	0.0879	
RF energy acceptance	%	1.78	1.59		2.6	3.4	
Damping time	ms	14.2	47.6		160.8	879	
Natural bunch length	mm	1.8	1.85		1.3	0.75	
Full injection from empty ring	h	0.1	0.14	0.16	0.27	1.8	0.8



Table 7: Main parameters of the Linac.

Parameter	Symbol	Unit	Baseline
Energy	E_{e^-}/E_{e^+}	GeV	30
Repetition rate	f_{rep}	Hz	100
Bunch number per pulse			1 or 2
Bunch charge		nC	1.5 (3)
Energy spread	σ_E		1.5×10^{-3}
Emittance	ε_r	nm	6.5

Table 6: Main Parameters of the Linac Accelerating Structures

Parameter	Unit	S-band		C-band
Frequency	MHz	2860		5720
Length	m	3.1	2.0	1.8
Cavity mode		$2\pi/3$		$3\pi/4$
Aperture	mm	19~26	25	12~16
Gradient	MV/m	22/27	22	40
Cells		86	55	89
Number of Acc. Stru.		93	16	470
Number of Klystron		34		236
Klystron Power	MW	80		50

Table 8: Main Parameters of the Damping Ring

	DR V3.0
Energy (Gev)	1.1
Circumference (m)	147.5
Number of trains	2 (4)*
Number of bunches/trian	1 (2)#
Total current (mA)	12.4 (24.8)*
Bending radius (m)	2.87
Dipole strength B_0 (T)	1.28
U_0 (keV/turn)	94.6
Damping time $\tau_x/\tau_y/\tau_z$ (ms)	11.4/ 11.4/ 5.7
Phase/cell (degree)	60/60
Momentum compaction	0.013
Storage time (ms)	20 (40)*
Natural energy spread (%)	0.056
Norm. natural emittance (mm-mrad)	94.4
Inject bunch length (mm)	4.4
Extract bunch length (mm)	4.4
Norm. inject emittance (mm-mrad)	2500
Norm. extract emittancce x/y (mm-mrad)	166 (97)* / 75 (3)*
Energy spread inj/ext (%)	0.18 / 0.056
Energy acceptance by RF (%)	1.8
RF frequency f_{RF} (MHz)	650
Harmonic number	320
V_{RF} (MV)	2.5
Longitudinal tune	0.0387

CEPC Key Taks in EDR-1


18

CEPC Booster Magnet Automatic Production Line in EDR




Status: construction started, to be completed in 2025-2026

CEPC NEG Coated Vacuum Chamber (200km) Automatic Production Line in EDR



Status: construction started, to be completed in 2025-2026

CEPC NEG Coated Vacuum Chamber (200km) Automatic Production Line in EDR



Status: construction started, to be completed in 2025-2026

CEPC 650MHz SRF Development in EDR




The collider Higgs mode for 30 MW SR power per beam will use 32 units of 11 m-long collider cryomodules will contain six 650 MHz 2-cell cavities, and therefore, a full size 650 MHz cryomodule will be developed in EDR

Status: construction started, to be completed in 2026

CEPC Key Taks in EDR-2

19

CEPC Tunnel Mockup for Installation in EDR



A 60 m long tunnel mockup, including parts of arc section and part of RF section

To demonstrate the inside tunnel alignment and installation, especially for booster installation on the roof of the tunnel

Plan: to be completed in 2026


The CEPC accelerator EDR, Shao-Ha Gas

CEPC TARI Meeting, Sept. 18, 2025, IHEP

21

CEPC C-Band Linac Test Bench in EDR


- CEPC EDR will establish the **C-band test bench** and test the components. With pulsed compressor, waveguides, directional couplers, loads, bend and straight waveguides, etc. **as a basic unit of CEPC C-band linac**
- The C-band test band is equipped with a CEPC 5720MHz 80MW power source
- The CEPC C-band test band will be completed in 2026



CEPC C-band linac test band will be completed in 2026

Other CEPC Accelerator and MDI EDR Activities

CEPC MDI designs



CEPC Collider Ring Magnets in EDR



CEPC Alignment and Installation Plan in EDR



Design parameters of SC quadrupoles with CCT coil

• Design parameters of Q1a, Q1b, Q2 magnet with iron-free CCT coil @ Higgs

	Q1a	Q1b	Q2
Field gradient (T/m)	142.3	85.4	96.7
Magnetic length (m)	1.21	1.21	1.5
Excitation current (A)	788 (Traditional) 730 (Direct winding)	640	760
Conductor diameter (HTS or LTS, mm)	7	0.8	0.8
Current density (A/mm ²)	2000 / 1900	3270	1510
Maximum dipole field in aperture (G)	226	124	127
Stored energy (kJ)	16.7	15.2	36.1
Peak field in coil (T)	4.3	3.8	4.2
Integrated field harmonics:			
(Single aperture) Cyl inner radius (mm)	20	28	31
(Single aperture) Cyl outer radius (mm)	30.5	38	44
Magnet mechanical length (m)	1.23	1.23	1.53
Net weight (kg)	25	32	43
Total weight of Q1a, Q1b, Q2 (kg)			100
For comparison, old net weight with iron option (kg)			100


Direct winding CCT coil is preferred for CEPC



IHEP fabricated CEPC CCT coil prototype with direct winding, inner diameter 40mm, 600mm long

Q1a Direct winding CCT coil

Preliminary design
Round 0.7mm conductor, coated angle: 24 deg
8 layers CCT quadrupole coil. The inner radius of the coil is 20mm
Excitation current: 730A @ 4.2K (2K is also under study)
3D calculation in OPERA-3D
Radius of single aperture < 31mm



Q1b Q2 Direct winding CCT coil


Round 0.8mm conductor, cantal angle: 24 deg
8 layers CCT quadrupole coil.
After correction, local dipole field decreases to less than 150G (Higgs)
Calculated integrated field harmonics are smaller than 2×10^{-4}

22

CEPC Key Taks in EDR-3

20


CEPC Accelerator EDR: Survey and Mechanical 2D/3D Design



CEPC Polarization in Preparation Study

-Compton Polarimeter at BEPCII-U

- A Compton polarimeter is now under commissioning at BEPCII-U
 - simulated performance: ~1% stats uncertainty within 20 second
 - Ready for tuning of laser-electron collision-> backscattered gamma signal from laser-electron collision has been observed




Advanced Technologies Development in Progress

IBS Technology for High Field Magnets




I₀ of IBS expected to be similar as FoBCD in 5 years with better mechanical properties and lower cost

SppC HF Magnet Development




CEPC Polarized Beam Studies(alternative option)



CEPC Cool Copper C-Band Linac Technology R&D

- CEPC is exploring the Cool Copper C-band linac technology (5712MHz is the test facility frequency)
- Two types of structures have been studied, type I and type II
- Type I has reached Eac 92.08MV/m, Q0 26162 with 20MW input (80MW input will reach Eac 199.2MV/m) (iris diameter 5.25mm)
- Type II will reach 144MV/m with 80MW input (iris diameter 10.49mm)



This cool copper C-band type-II structure has the potential to be applied to CEPC injector when necessary



CEPC Accelerator Components-Types and Quantities

There are 244 types of hardware along beam, with a total quantity of **105354***.

*When counting the quantity, the vacuum chambers are not included, because the detailed vacuum chambers should be designed after the vacuum segmentation and layout definition.

Collider	Hardware types	Quantity
Magnets	58	25280
EMS	1	32
RF modules	1	32
Collimators	5	64
Beam instrument	7	7134
Vacuum devices	4	19130
Waveguides	1	32
Cryogenic devices	1	32
MDI devices	5	20
Total	83	51756

Booster	Hardware types	Quantity
Magnets	18	19610
RF modules	1	12
Beam instrument	6	2418
Vacuum devices	3	18402
Waveguides	1	12
Cryogenic devices	1	12
Total	30	40466

Linac	Hardware types	Quantity
Magnets	34	690
Accelerator devices	14	1164
Beam instrument	10	244
Vacuum devices	4	7585
RP devices	7	7
Total	69	9690

Damping Ring	Hardware types	Quantity
Magnets	8	310
Cavity	1	2
Beam instrument	3	42
Vacuum devices	3	144
Total	15	498

INJ&EXT	Hardware types	Quantity
LSM	23	134
Kicker	4	52
Total	27	186


Transport line	Hardware types	Quantity
Magnets	9	752
Beam instrument	5	86
Vacuum devices	5	1912
DUMP	1	2
Total	20	2758




CEPC Accelerator Components Types

22


Magnet assembly in collider




RF module in Collider



Some instruments




Magnet assembly in Booster




PT & AMD for Linac




INJ & EXT magnets



QRFB in collider




Magnets for Linac



Magnets for damping ring



Quadrupoles in TL



BEPCII-based PWFA Test Facility Development Status

23

CEPC Plasma Injector (alternative option) and TF Plan

CEPC plasma injector scheme:

From 10 GeV \rightarrow 30 GeV \rightarrow TR ≥ 2

Simulation results show that it works on paper with reasonable error tolerances for both electron and positron beams injected to the booster



CEPC IARC, 2022.06



- Phase I (Year0-Year2)
1. Re-design and install transport beamline system, optimize the e⁺/e⁻ beam quality
 2. Clean room and high power installation 200TW
 3. Beam instrumentation
 4. RF Gun platform
 5. Commissioning systems
- Phase II (Year3-Year4)
1. Re-design and install transport beamline system, optimize the e⁺/e⁻ beam quality (1PW \rightarrow 20/40 TW)
 2. Commissioning systems

- Positron and electron acceleration
- Cascading acceleration
- Future linear collider technologies (possible application)

PWFA/LWFA TF based on BEPC-II Linac and HPL has been founded by CAS 90M RMB in Sept. 2023
Under development in the experimental hall #10 of BEPC-II




- From 2023.09 to 2028.08
- Unique TF for e⁺ and cascaded PWFA

Beam quality

Beamline I

Parameters	Unit	BL-I e ⁻ (AM3)	BL-I e ⁻ (IP1)	BL-I e ⁺ (AM3)	BL-I e ⁺ (IP1)	BL-I e ⁻ (IP1, block)	BL-I e ⁺ (IP1, block)
Energy	GeV	2	2	2	2	2	2
Charge	pC	2000	2000	100	100	9.4	0.2
bunch length	ps	10	1	10	1	~1	~1
Geo. emittance	mm-mrad	0.1/0.1	0.1/0.1	0.4/0.4	0.4/0.4	0.011/0.005	0.04/0.02
RMS beam size	μm	-	150/150	-	300/300	30/40	54/76

33



PWFA LAB: 35 m \times 14 m \times 2



Goals: demonstration of acceleration of positron and electron beams with staging in next few years
Key technology for future linear colliders



Green CEPC and Sustainability Efforts

24

- **SR power per beam: 30 MW** (CEPC-TDR p965)

- Total electricity consumption: 262 MW

- RF power (109 MW)
- Magnet (58 MW)
- Utilities (44 MW)
- Cryogenics (11.6 MW)
- Other auxiliary power combined (29 MW)

} Need to improve these

- **SR power per beam: 50 MW** (CEPC-TDR p967)

- Total electricity consumption: 340 MW

- RF power (177 MW)
- Magnet (58 MW)
- Utilities (54 MW)
- Cryogenics (11.1 MW)
- Other auxiliary power combined (29 MW)

} Need to improve these

Participated the 4th edition of the Sustainable High Energy Physics (HEP) workshop, May 12-15, 2025, with green CEPC and sustainability presentation and Panel discussions <https://indico.global/event/4745/>

On-going sustainability projects:

- High efficiency klystron:
 - 650 MHz
 - 80 MW C-band
- Permanent magnets transport lines
- High Q-factor SRF cryogenic-modules
- Recovery of waste heat (HEPS)
- Recovery and recycling of Helium
- Photovoltaic (PV) power generation systems (HEPS)



Permanent quadrupole's prototypes for CEPC collider rings

Prototypes have been developed addressing green collider technologies

Power efficiency, energy recycling, and clean energy generation are being addressed as comprehensive measures for sustainable operation

Publication: Dou Wang; Jie Gao; Yuhui Li; Jinshu Huang; Song Jin; Manqi Ruan; Mingshui Chen; Shanzhen Chen,
"The carbon footprint and CO2 reduction optimization of CEPC", *RDMT*, <https://doi.org/10.1007/s41605-025-00535-7> (2025).

CEPC Industrial Preparation

26

Large-scale Cryogenic Refrigeration & Liquefaction Equipment (CIPC member)

First 18kW@4.5K helium refrigerator fabricated in China passes inspection

- It was developed by the Institute of TIPC, CAS, and integrated and manufactured by Fullcryo.
- The super large horizontal cold box with a length of 28m and a diameter of 4.2m achieves ultra-high vacuum and extremely low leakage.
- The horizontal cold box at megawatt-level is the largest of its kind in China and even in the world.
- The horizontal cold box system has exceeded the set targets.
- On-site testing: 1. The airtightness test of each internal channel revealed a pressure drop of 0, surpassing the target value of 0.02 bar. 2. The overall leakage rate is 9.1×10^{-10} Pa.m³/s, surpassing the target value of 1×10^{-7} Pa.m³/s.
- Expected Goals: Achieving 3 operational mode adjustments: the cooling capacity ≥ 18 kW@4.5K; the cooling capacity in the superfluid helium temperature range ≥ 4 kW@2K.




北京中科富海低温科技有限公司
Beijing Sinoscience Fullcryo Technology CO., Ltd. (CIPC member)

CEPC cryogenic system need four 14kW@4K cryogenic refrigerators.
SpnC needs 18kW@4.5K helium refrigerator as well

CEPC 650MHz 800kW CW High Efficiency Klystrons

国力研究院 (CIPC member)




Kunsan National Research Institute has successively developed 650MHz/800kW klystron sample tubes, 650MHz/800kW high-efficiency klystron sample tubes, 648MHz pulse klystron tubes, 650MHz/800kW multi-injection klystron beam tubes, and the latest 324MHz pulse klystron tubes Electro vacuum products for 50 years. Provide high power thyratron of GL1536A in batches for BEPCII in 2012.

HE-RACING Technology and OTIC on SRF Technologies (CIPC members)

高能锐新 (CIPC member)



东方铝业 (CIPC member)




CEPC booster and colliders: 2GeV 1.3GHz and 650MHz SRF accelerators (Higgs); 10GeV 1.3GHz and 650MHz SRF accelerators (Itar)

RF Shielding all Metal Gate Vacuum Valve

日播科技 SHZK

- Two prototypes of RF shielding All metal developed, and the leakage of one of them have been tested.
- The delivery inspection leakage test results for two valves, conducted by the manufacturer, were found to be $< 1 \times 10^{-9}$ mbar · L/s (30 times open and closed).
- The difference of leakage by IHEP & manufacture will be checked and retested in next.



Tested by IHEP
Expectation leakage $< 1 \times 10^{-9}$ mbar · L/s



CEPC needs ~1700 all metal valves

The Key industries also for ILC and LCF



CEPC International Collaboration-1

HKUST IAS23 HEP Conference, Feb. 14-16, 2023,
Hong Kong

<https://indico.cern.ch/event/1215937/>

The 2024 HKUST IAS Mini workshop and conference were held from Jan. 18-19, and Jan. 22-25, 2024, respectively.

<https://indico.cern.ch/event/1335278/timetable/?view=standard>



The 2025 HKUST IAS fundamental physics conference:
Jan. 14-17, 2025, Hong Kong

<https://indico.cern.ch/event/1454867/overview>

CEPC Workshop EU Edition (Barcelona, Spain)
June 16-19, 2025

<https://indico.ifae.es/event/2054/overview>



The 2026 HKUST IAS fundamental physics conference
Jan. 12-16, 2026, Hong Kong

CEPC Workshop EU, April 7-10, 2026, Lisbon, Portugal

The CEPC accelerator EDR Status and
Plan-Jie Gao

The 2023 International Workshop on Circular
Electron Positron Collider, EU Edition,
University of Edinburgh, July 3-6, 2023

<https://indico.ph.ed.ac.uk/event/259/overview>



The 2024 international workshop on the high
energy Circular Electron Positron Collider (CEPC)
was held from Oct. 23-27, 2024, Hangzhou, China

<https://indico.ihep.ac.cn/event/22089/>



The 2025 international workshop on the high
energy Circular Electron Positron Collider (CEPC)
will be held from Nov. 6-10, 2025,
Guangzhou, China

<https://indico.ihep.ac.cn/event/25300/>



CEPC Workshop 2025, Nov. 6, 2025, Guangzhou

The 2023 international workshop
on the high energy Circular
Electron Positron Collider (CEPC)

<https://indico.ihep.ac.cn/event/19316/>



The 2024 international workshop of CEPC
EU-Edition were held in Marseille, France,
April 8-11, 2024.

<https://indico.in2p3.fr/event/20053/overview>



FCPPNL, Bordeaux, France, June 10-14, 2024
<https://indico.in2p3.fr/event/20434/overview>

FCPPNL, Qingdao, China, July 21-25, 2025
<https://indico.ihep.ac.cn/event/25400/>




Since March 4th 2025 (kick off meeting), IHEP has joined an international collaboration on beam-beam effects at SuperKEKB among CERN, IHEP, KEK and USTC. **(As recommended and encouraged by IARC and IAC)**

IHEP has participated all SuperKEKB international collaboration meetings and one Ph.D student Meng Li and one Post Doc. Chuntao Lin from IHEP have long stay at KEK on SuperKEKB injection related background and beam-beam effects joint studies.

Prof. Jie GAO from IHEP has sent presentations to the collaboration about the possible reason why SuperKEKB’s design luminosity ($80 \times 10^{34} @ \beta_y = 0.3 \text{mm}$) could not be achieved, and it is recommended that the next round SuperKEKB experiment go to $\beta_y = 1.79 \text{mm}$ (instead of stay at $\beta_y = 1 \text{mm}$ and smaller) possibly achieved luminosity would be around $8.7 \times 10^{34} \text{cm}^{-2} \text{s}^{-1}$ (about a factor of ten lower than the design goal), close to the Super KEK B post-LS1(1) luminosity target goal of $10 \times 10^{34} \text{cm}^{-2} \text{s}^{-1}$. If on axis injection is adopted, the luminosity could reach $14.6 \times 10^{34} \text{cm}^{-2} \text{s}^{-1}$ with $\beta_y = 1 \text{mm}$.

Super KEK B is an important high luminosity e+e- collider in operation with crab waist scheme, and it is important to learn the experimental experiences for future advanced colliders such as Higgs factories of CEPC and FCC



The oral presentation will be in Nov. 2025

$$L_{max}[\text{cm}^{-2}\text{s}^{-1}] = \frac{0.158 \times 10^{34}(1+r)}{\beta_y^2[\text{mm}]} I_b[\text{mA}] \sqrt{\frac{U_0[\text{GeV}]}{N_{IP}}} e^{\frac{\sqrt{\Phi p}}{3.22} (1 + 0.000505 \cdot \Phi p^2)} \quad \text{Eq. 1}$$
$$L_{max}[\text{cm}^{-2}\text{s}^{-1}] = \frac{0.158 \times 10^{34}(1+r)}{\beta_y^2[\text{mm}]} I_b[\text{mA}] \sqrt{\frac{U_0[\text{GeV}]}{N_{IP}}} e^{\frac{\sqrt{\Phi p}}{3.22} \frac{A}{\beta_{y, \text{on axis}}(\text{mm})^2} (1 + 0.000505 \cdot \Phi p^2)} \quad \text{Eq. 2}$$

for Super KEK B: $A=1.6 \text{mm}^2$ (off axis injection)
for Super KEK B: $A=0.56 \text{mm}^2$ (on axis injection)

The luminosities of Super KEK B without (Eq. 1) and with (Eq. 2) DA limitation effects as shown in Figure 1.




Figure 1: Super KEK B luminosities from the experiments and the analytical formulae Eq. 1 and Eq. 2

β_y (mm)	Luminosity of Super KEK B ($10^{34}/\text{cm}^2/\text{s}$) (Experiments and designed)	Luminosity of Super KEK B ($10^{34}/\text{cm}^2/\text{s}$) (Jie Gao formulae, no DA effects, Eq. 1)	Luminosity of Super KEK B ($10^{34}/\text{cm}^2/\text{s}$) (Jie Gao formulae considering DA effects, Eq. 2) (Off axis injection)	Luminosity of Super KEK B ($10^{34}/\text{cm}^2/\text{s}$) (Jie Gao formulae considering DA effects, Eq. 2) (On axis injection)
0.3	80 (designed value from Table 1)	85	0	0.17
0.8	2.5 (2022abRun)	32	2.6	13.3
1	5.1 (Dec. 27, 2024)	26	5.1	14.6
1.788	To be experimented (recommended)	14.2	8.65	12
2	To be experimented	12.8	8.55	11.1
3	To be experimented	8.5	7.1	8
6	To be experimented	4.25	4.25	4.2

Table 2: Comparison of Super KEK designed and experimental luminosities with Jie Gao’s luminosity analytical formulae, Eq. 1 and Eq. 2

Eq. 1 and Eq. 2 could be found in following reference:
J. Gao, “The CEPC Project Status”, Nov. 2025, arXiv:2505.04663,
<https://doi.org/10.48550/arXiv.2505.04663>



Summary

- CEPC accelerator full spectrum EDR activities including EDR site geological investigation and civil engineering design have progressed well according to EDR plan
- IARC/IAC recommendations have been well taken into account and all five international mini reviews have been conducted in 2025
- CEPC detector reference design report has been reviewed by IDRC in April and Sept. 2025, which promote also MDI activities in general
- CEPC IARC 2025 meeting report is a good guide for the following EDR works
- CEPC will keep and strengthen strong international and industrial collaborations
- CEPC goal is to complete EDR and continue to prepare and apply for construction in the 16th five year plan and start construction around 2030's



Acknowledgements

30

Thanks go to CEPC-SppC team's hard works, international and CIPC collaborations

Special thanks to CEPC IB, SC, IAC, IARC and IDRC committee's advices,
suggestions and supports

Thanks for your attention