





- **Status of TPC R&D**

High granularity readout: Production of TPC module

- **Key issues to address #1**


- Development of the pillar is constrained by the **height** of the transmission interface
- After three rounds of process optimization, this issue **has been resolved** using flat-plate pressing




High granularity readout: Production of TPC module

- **Key issues to address #2**


- Stainless steel wire mesh stretching and rolling are optimization
- **Improved detector gain**, resolution and overall performance




(a) 未辊压的不锈钢网




(b) 辊压后的不锈钢网



(c) 不锈钢网拉伸平台







(d) 拉伸后的钢网






High granularity readout: Micromegas detector tests

- Detector optimization completed
- Test chamber fabrication completed
- Readout system & preliminary electronics prepared with Tsinghua
- Detector installation & gas tests in progress



Fe-55 spectrum of TPC module

- Achievement of TPC module:
 - Used Fe-55 source to acquire energy spectrum on mesh; energy spectra obtained through the small pixel readout and the two results are consistent.
 - Micromegas detector gain measured in T2K gas — good gain linearity achieved
 - TPC module with TEPIX v1 testing ongoing and validation



Some improvements

- Impartments of mesh production:
 - Stainless steel pressure bars & Al alloy flat plates: improved fabrication in progress

