

**Anne M. Sickles**  
**L3 Manager for block production**

**EMCal status & plans**  
**April 22, 2018**




**1st sPHENIX Workshop in China**


- the EMCal group has developed extensive experience building 2D projective tungsten powder-scintillating fiber calorimeter blocks
  - until we built them, these were thought to be either impossible or impractical to build
  - as Craig said, these blocks are an essential part of the sPHENIX physics program
- this talk:
  - how the blocks are built
  - main challenges in block production
  - plans and ongoing activities



- 6 screens / block & 22 block shapes = 132 distinct screens
- photoetched brass made by TechEtch



each screen is clearly printed  
with which screen it is!






# filling screens with fibers



fiber filling: screens held in place  
by 3d printed fixtures and  
supported by plastic cup  
screens give the fibers the 2D  
projectivity

fibers are 0.47mm scintillating  
clear fibers



3d printed filled screen storage




# making blocks

machined delrin mold

tungsten and epoxy poured in top


ends attached

vacuum ports to draw  
epoxy through






# finished blocks



after epoxy dried and mold  
top removed  
(molds are cleaned and  
reused)

finished block







space shared with other nuclear physics projects in Urbana and includes  
a dedicated machine shop



good light for  
fiber filling



low dust area  
of high bay



vibration table  
for filling  
tungsten

epoxy work in fume hood








large milling machine for bulk machining of blocks

custom diamond fly cutter to have good surfaces for the fiber ends without hand polishing






- main requirements:
  - high density: packed  $> 10 \text{ g/cm}^3$
  - allows epoxy to flow through the block
  - the combination of these two criteria make us sensitive to the particle size distribution of powders
  - not possible to get the density requirement without  $\sim 99\%$  pure tungsten
- bulk of R & D with Technon 100\* from Tungsten Heavy Powder (San Diego)
  - powder source is ultimately China, unclear what THP itself does to the powder

\*THP says what they send us meets additional specs beyond those listed for Technon 100, but it is unclear what that specifically means



# SEM pictures of THP powder



particle size: 30-130 µm

**all SEM pictures from M. Phipps and A. Romero Hernandez  
using Illinois Materials Research Lab facilities**






# density measurements

Sample	Mass Used (g)	Volume (cm <sup>3</sup> )	Density (g/cm <sup>3</sup> )	Trial 1 Density (g/cm <sup>3</sup> )	<b>Avg Density (g/cm<sup>3</sup>)</b>
<b>THP 2016 a</b>	200.0	19.5	10.26	10.27	<b>10.27</b>
<b>THP 2016 b</b>	200.0	17.8	11.24	11.26	<b>11.25</b>
<b>THP 2015</b>	200.0	20.5	9.76	9.66	<b>9.71</b>
Buf-Tun	200.0	22.0	9.09	9.38	<b>9.24</b>
Tungsten Metal Powder	200.0	27.0	7.41	7.34	<b>7.38</b>
KennaMetal	200.0	30.4	6.58	6.08	<b>6.33</b>

**for a long time we were unable to find other powder suppliers which met our density requirements**

**even THP has exhibited some variability historically**





particle size: 10-200  $\mu\text{m}$

"boulder" rate can be adjusted post production

identified by connections with ATLAS ZDC work at Illinois




# block comparison

**$\rho > 9.0 \text{ g/cm}^3$  is the block density spec**

## THP

Packing density:  
 $10.9 \pm 0.1 \text{ g/mL}$


Density of block:  $9.5 \pm 0.2 \text{ g/mL}$



## HC Starck

Packing density:  
 $10.5 \pm 0.1 \text{ g/mL}$

Density of block:  $9.2 \text{ g/mL}$






- block parameters:
  - dimensions: they need to fit together
  - density: need to maintain high and uniform density
  - light transmission
- extensive QA plan developed for ongoing work
  - for sPHENIX collaborators: <https://docdb.sphenix.bnl.gov/cgi-bin/private/ShowDocument?docid=123>


**maintaining these criteria is key for getting the needed energy resolution**



# light testing setup in Urbana





- quality pictures obviously key to doing detailed QA of the blocks
- test setup: **LED light-source** shined through a **large diffuser** illuminates the blocks which we then photograph
- improvements being made to fix block position
- expect to count  $>99.5\%$  fibers with an image clustering program



**Yongsun Kim**  
**Anabel Romero Hernandez**  
**Eric Thorsland**



1 block = 4 towers (separate lightguides)



fibers brought in from edges on the readout side (collaring) to improve light collection efficiency near edges  
→ reduces the position dependence of showers



# blocks positioned in 2018 prototype





**goal of mechanical tolerances:** minimal gaps between the blocks



## block geometry is complicated due to two dimensional projectivity

currently take 6 measurements of the block size  
require a tolerance of 0.01" on each dimension



mold provides dimensions on 3 sides, top and ends are machined to required dimensions



- successful production of tungsten scintillating fiber blocks with two dimensional productivity
- good understanding of how to achieve the necessary QA benchmarks for a uniform detector which meets our physics requirements
- moving on to mass production of blocks in Urbana
  - "sector 0" preproduction prototype: 96 blocks covering 0-1.1 in  $\eta$  and  $32 / 2\pi$  in azimuth
  - 12 sectors of advanced R&D to develop and refine the production and sector assembly process