

# sPHENIX EMCAL Project Status

## Overview of the EMCAL System

Craig Woody (BNL)  
L2 Manager EMCAL Subsystem

sPHENIX China Workshop  
April 22, 2018

## EMCAL Design Specs:

- Coverage:  $\pm 1.1$  in  $\eta$ ,  $2\pi$  in  $\phi$
- Segmentation:  $\Delta\eta \times \Delta\phi \approx 0.025 \times 0.025$
- Readout channels:  $96 \times 256 = 24576$  (towers)
- Energy Resolution:  $\sigma_E/E < 15\%/ \sqrt{E}$
- Provide an e/h separation  $> 100:1$
- Approximately projective
- Compact (in order to fit inside Babar solenoid)
- Works inside a 1.5T magnetic field

## Contributions to sPHENIX physics measurements :



- Jet measurements
- Photon measurements
- $\Upsilon$  measurements

## Jet measurements


- Measure the EM component of the jet energy along with HCAL
- Requirements on energy resolution and segmentation are determined mainly by the underlying event

For a 5 GeV electron from  $\Upsilon$  decay  
 $15\%/\sqrt{E} \Rightarrow \sim 335 \text{ MeV}$

True jets begin to dominate fake jets for  $p_T > 20 \text{ GeV}/c$





## $\Upsilon$ measurements



Provide electron id ( $e:h > 100:1$ )

## $\gamma$ -jet and direct photon measurements




Tag and measure photons for  $p_T > 20 \text{ GeV}$

# EMCAL Subsystem


Electromagnetic calorimeter covering  $\pm 1.1$  in  $\eta$  and  $2\pi$  in  $\phi$

$2(\pm\eta) \times 32(\phi) = 64$  Sectors




**1 Sector = 24 modules**  
**= 96 Blocks**  
**= 384 towers**

~14 cm absorber ( $\eta=0$ )




7.5 cm readout



26 cm total radial space


Designed to be compact to fit inside the BaBar magnet

## EMCAL Sector






# Tilted Block Configuration

- Sectors consist of 96 blocks each of which consist of 2x2 projective towers
- The blocks are tilted in both  $\eta$  and  $\phi$  in order to avoid channeling of particles along projective lines



$\phi$  tilt = 87.6 mrad  
 $\eta$  tilt = 160.0 mrad

Blocks are tilted in  $\eta$   
Sectors are tilted in  $\phi$







# Sector Design

First three  $\phi$  slices are 1D projective

Remaining  $\phi$  slices are 2D projective



Sawtooth support structure for blocks




Electronics, cables and cooling

# 1D Projective vs 2D Projective

Projectivity in 2 dimensions is required to minimize the transverse size of the showers at large rapidity

2D Projective

1D Projective



Transverse shower profile for 8 GeV electrons at large rapidity

Energy from the underlying event is a large background in central heavy ion collisions and having a small transverse shower size helps to reduce this

**Improves energy resolution and e/h separation**

Design driver: Must be compact to fit inside Babar magnet & minimize cost of HCAL  $\Rightarrow$  **W/SciFi SPACAL**

## Absorber


- Matrix of tungsten powder and epoxy with embedded scintillating fibers
- Density  $\sim 9\text{-}10\text{ g/cm}^3$
- $X_0 \sim 7\text{ mm}$  (18  $X_0$  total),  $R_M \sim 2.3\text{ cm}$

## Scintillating fibers


- Diameter: 0.47 mm, Spacing: 1 mm
- Sampling Fraction  $\sim 2\%$
- Modules are formed by pouring tungsten powder into a mold containing an array of scintillating fibers and infusing with epoxy
- Fibers are held in position with metal meshes spaced along the module

Design originally developed by O. Tsai at UCLA

1D Projective




100 Mesh tungsten powder







# 2D Projective Absorber Blocks



2D Projective Block



Fiber Assembly




Fibers are tapered inward at readout end to improve light collection



Block fabrication area at UIUC





2D projective blocks for the large  $\eta$  prototypes



# Light Collection and Readout

Blocks are read out in individual towers using optical light guides and SiPMs




Four SiPMs are passively summed for each tower

Light guide focuses light onto four  $3 \times 3 \text{ mm}^2$  SiPMs

Important factors affecting the energy resolution are light collection efficiency and uniformity

- Area matching between tower readout area and 4 SiPMs is only 6.4%
- Short light guide is a poor mixer
- Photostatistics gives  $\sim 500 \text{ p.e./GeV}$ 
  - $\Rightarrow \sim 4.5\%/\sqrt{E}$  contribution to energy resolution
  - $\Rightarrow 0.5 \text{ pixels/MeV}$  (each SiPM has 40K pixels)








# Prototyping and Testing

The design has undergone 3 stages of prototyping and testing in the test beam at Fermilab

2016 - 1D Projective ( $\eta \sim 0$ )




2017 & 2018 - 2D Projective ( $\eta \sim 0.9$ )




4x4 array of 2x2 tower blocks (64 towers)

2018 Prototype (V2.1) was constructed as part of an actual sector in terms of mechanics, electronics and cooling




# Test Beam Results

2016 Beam Centered on a single tower 2017




1D Projective ( $\eta = 0$ )



2D Projective ( $\eta \sim 0.9$ )




2014 - UCLA



1D Projective ( $\eta = 0, 0.3, 0.9$ )

O.Tsai (2014)

Sampling fraction changes with rapidity



Beam spread over more than one block

- The engineering design for the EMCAL is in a very mature state. Full 3D models exist for all major components.
- We have gone through numerous design reviews and prototype testing and are very close to a final design.
- We are now preparing for the CD-1/OPA review that will take place on May 23-25, 2018 at BNL.
- Approval of CD-1 will allow us to begin procurement of long lead time items such as tungsten powder, fibers and SiPMs.

- Our next prototyping phase will be the construction of a pre-production prototype of a complete sector (Sector 0). This sector is not intended to be used in the final detector, but will allow us to complete the overall sector design.
- All materials (powder, fibers, screens, etc) for Sector 0 are in hand at UIUC.
- Final block design for Sector 0 has been approved.
- We expect production of the 96 blocks for Sector 0 to begin soon at UIUC.




- After the completion of Sector 0, any subsequent design changes will be implemented for the final blocks and sectors.
- We then plan to build 12 complete additional preproduction sectors (Sectors 1-12). These will be built to cover the full rapidity range to  $\eta=1.1$ . It is envisioned that these sectors *would be* used in the final detector.
- Orders for the materials for these sectors are now starting to make their way through BNL Contracts & Procurements.

# Final Production Schedule



Delivery date for all EMCAL sectors is September 2021  
**EMCAL is on the Critical Path**



# Descoping of the EMCAL


In order to stay within the \$32M spending cap, it was necessary to reduce the EMCAL acceptance from  $|\eta|=1.1$  to  $|\eta|\sim 0.85$

## Impact on the EMCAL


- We need to save  $\sim \$1\text{M}$  from the total cost of the EMCAL (not including electronics)
- The main savings would come from purchasing less materials for fabricating the blocks (W powder, fibers) + labor. However, many of the fixed costs would remain the same.

Note: A geometrical cut from  $|\eta|=1.1$  to  $|\eta|=0.85$  implies a fiducial cut from  $|\eta|\sim 1.0$  to  $|\eta|\sim 0.75$  for jet physics


Jet acceptance -  $\sim 25\%$  loss in statistics



$\Upsilon \rightarrow e^+e^-$  acceptance -  $\sim 35\%$  loss in statistics



Descoping plan eliminates blocks 19-24 at large rapidity



- Once final production begins, it would be essentially impossible to add the missing blocks after assembly of the sectors
- Possible *re-scoping* could be to start building complete coverage sectors using UIUC blocks and use Chinese blocks to build the last remaining sectors


- ❑ We have been working on the EMCAL design for over four years and have brought it to a very advanced stage.
- ❑ Several prototypes have been built and tested and have been shown to meet the design requirements for sPHENIX.
- ❑ We believe the technical design for the baseline detector is technically sound and will meet the physics objectives for the sPHENIX physics case.
- ❑ Descoping the EMCAL as proposed would have a significant effect on the physics performance of sPHENIX and we would like to work with you to find ways to restore it.

# Uniformity of Response


## Non-Uniformities at block boundaries are an inherent property of SPACALs

- Fibers essentially channel light to the photodetector.
- Rely on light guide to mix and randomize the light
- Difficult to do when there is limited space and limited photocathode coverage


### sPHENIX 1D Projective




Original SPACAL (Wigmans 1995)



### sPHENIX 2D Projective




2014 Test Beam Data (UCLA)





# Electron Hadron Separation

Transverse energy distribution of 4 GeV electrons and pions



p+p

Pion rejection vs electron id probability

Central Au+Au Hijing

